

Screen Specifications and data sheet

Display Configuration: 16:9 Aspect Ratio

Brightness: 6000 nits with manual and automatic adjustment capability

Pixel Pitch: 10mm (P10)

Module Alignment: Max of 3% of pixel pitch between any adjoining module.

LED Type: SMD

Colour Temperature: 3500k - 8500k minimum

Colour Depth: 14 Bit per Colour

Horizontal Viewing Angle: Up to 170 degrees (85 degrees R/85 degrees L) with no significant colour shift or reduction in Brightness

Vertical Viewing Angle: Up to 140 degrees

Refresh rate of display: Minimum of 3840hz

Frame Rate: 50-60hz

Weather and Ingress Protection: IP65 Front and IP54 Back

Operating Temperature: -20c to +60c

Access for Maintenance: Rear

