



MATERIALITY:

1. Grey facing brick to basecourse.
2. Pavestone Black Rock stack cladding (or equiv.) - Colour black.
3. Smooth proprietary render system - Colour white.
4. uPVC double glazed windows and doors to achieve U-Value 1.2w/m²k. Colour - Anthracite Grey/ RAL 7016.
5. Double glazed spandrel panel to achieve U-Value 1.2w/m²k. Colour - Anthracite Grey/ RAL 7016.
6. 950x1180mm electrically operated Velux Windows to achieve U-Value 1.2w/m²k. Slatted patio.
7. Marley Modern Concrete roof tiles - Colour grey.
8. PV panels.
9. "Schüco" aluminium double glazed Bi-Fold Doors. External face finished to dark grey RAL Colour 7016. Internal face with white finish. Doors to achieve 1.4w/m²k u-value.
10. Aluminium double glazed windows and doors to achieve U-Value 1.2w/m²k. Colour - Anthracite Grey/ RAL 7016.
11. Proprietary single ply roofing membrane.

All new window cills to be precast concrete eternit colour grey.
All new soffits, fascias & rainwater goods to be Anthracite Grey/ RAL 7016 Eurocell uPVC.

