

Flat Rooflight Datasheet



- **Exceptional thermal performance**
 - ✓ Overall U value (double glazing and frame) 1.3 w/m²k
 - ✓ Structural PVCu internal core with superior thermal properties
- **Minimal external and internal sightlines**
- **Simple installation**
 - ✓ Hidden direct fixing and strap fixing alternative
 - ✓ Internal plasterboard pocket for easy boarding and plastering
 - ✓ Clip in external weather bar and internal cover trim
- **Weather resistant** - 5 degree pitched kerb allowing the water to drain off the glazing unit unto the existing flat roof
- **Insulated kerb upstands** available to purchase from Atlas
- Standard toughened double glazed spec - 6mm active neutral solar/16mm gas/6mm Low e (U value 1.0 w/m²k)/self cleaning
- **Manufactured** and **kitemarked** to BS EN 1279-2 and toughened to BS EN 12150-1
- **10 year seal and easy clean coating warranty** as standard
- Available (as standard) in:
 - Grey Ral 7016 matt
 - Black Ral 9005 matt
 - **White Ral 9910 satin**
 - Grey on white
 - Black on white
- Stock sizes (internal measurements):
 - 1000 x 1000 - 40kg
 - 1000 x 1500 - 57kg
 - 1000 x 2000 - 75kg