



Samuel House
5 Fox Valley Way
Stocksbridge
Sheffield, S36 2AA

T: 0114 321 5151
hello@enzygo.com
www.enzygo.com

Project Title: **Phase 2, Lathom Pastures**
Client: **Bellway Homes (NW Division) Ltd.**
Project Number: **MAN.1154.023**
Drawing Number: **ENZ.02.00.SC.L.45.408**
Dated: **17/12/2020**

Drawn: **WH**
Checked: **CG/PB**
Approved: **PB**
Revision: **First Issue**
Status: **DRAFT**

Lathom Pastures - Public Plant Schedule

| QTY | UNIT | CODE | PLANT NAME | STOCK | FORM | GIRTH/HEIGHT | SPECIFICATION |
|--------------------------------|------|-------------------|--------------------------------|-------|------|--------------|--|
| Proposed Specimen Trees | | | | | | | |
| 25 | No. | ACE STR xhs14 | Acer campestre 'Streetwise' | RB | STD | 14-16cm | 3x; Extra Heavy Standard; clear stem minimum 200cm; 5 breaks |
| 52 | No. | BET PEN Edin hs14 | Betula pendula "Edinburgh" | RB | STD | 14-16cm | 3x; extra heavy standard;clear stem minimum 175-200,425-600cm ht |
| 17 | No. | CAR STR xhs14 | Carpinus betulus "Streetwise" | RB | STD | 14-16cm | 3x; extra heavy standard;clear stem minimum 175-200 |
| 22 | No. | LIQ STY xhs14 | Liquidamber styraciflua | RB | STD | 14-16cm | 3x; extra heavy standard;clear stem minimum 175-200 |
| 36 | No. | PYR CHA xhs14 | Pyrus calleryana "Chanticleer" | RB | STD | 14-16cm | 3x;extra heavy standard;clear stem minimum 175-200, 5 breaks |
| 41 | No. | QUE ROB xhs14 | Quercus robur | RB | STD | 14-16cm | 3x; extra heavy standard;clear stem minimum 200cm, 400-450cm ht |
| 39 | No. | SOR AUC xhs14 | Sorbus aucuparia | RB | STD | 14-16cm | 3x; extra heavy standard;clear stem minimum 175-200,425-600cm ht |

| QTY | UNIT | CODE | PLANT NAME | STOCK | FORM | GIRTH/HEIGHT |
|--------------------------------------|------|-------------|-----------------------|-------|--------|--------------|
| Multistem Tree/Specimen Shrub | | | | | | |
| 7 | No. | AME LAM ms3 | Amelanchier lamarckii | RB | MSTEM3 | 200-250cm |
| 11 | No. | PRU SER ms3 | Prunus serrula | RB | MSTEM3 | 200-250cm |

| PERCENT | QTY | UNIT | PLANT NAME | STOCK | SIZE |
|--------------------|-----|------|------------|-------|------|
| Hedge Mixes | | | | | |

558m LATHOM PASTURES NATIVE HEDGE MIX planted @ 6/m in a Double Staggered Row

| | | | | | |
|-----|------|-----|--------------------|---------|----------|
| 20% | 670 | No. | Acer campestre | B Trans | 80-100cm |
| 15% | 502 | No. | Cornus sanguinea | B Trans | 80-100cm |
| 15% | 502 | No. | Corylus avellana | B Trans | 60-80cm |
| 30% | 1004 | No. | Crataegus monogyna | B Trans | 80-100cm |
| 10% | 335 | No. | Ilex aquifolium | C 5L | 80-100cm |
| 10% | 335 | No. | Viburnum opulus | B Trans | 60-80cm |

To be planted in a double staggered row at 6 plants per lin. metre. Individual varieties to be planted in groups of between 5 and 9. Notch planted with rabbit protection (minimum 600mm height) and staked. Ilex to have mesh rabbit protection. Mulched after planting to a depth of min. 50mm of fine bark mulch.

| QTY | UNIT | CODE | PLANT NAME | STOCK | SIZE |
|--------------------------|---|------|----------------------------|-------|---------|
| Ornamental Hedges | | | | | |
| 77 m | Lon pil Hedge 5L | | Lonicera pileata | C 5L | 40-60cm |
| 385 No. | Plants spaced @ 5/m in a Single Row | | | | |
| 168 m | Pru lus Hedge 5/m | | Prunus lusitanica | C 5L | 40-60cm |
| 840 No. | Plants spaced @ 5/m in a Double Staggered Row | | | | |
| 172 m | Vib Eve Hedge 5/m | | Viburnum tinus "Eve Price" | C 3L | 40-60cm |
| 860 No. | Plants spaced @ 5/m in a Double Staggered Row | | | | |

| QTY | UNIT | CODE | PLANT NAME | STOCK | SIZE | SPACING | SPECIFICATION |
|--|----------------|------|-------------------------------------|----------|----------|---------|--------------------|
| Shrubs (Specimen & Mixed Ornamental Beds) | | | | | | | |
| 34 No. | Cho Azt | | Choisya ternata "Aztec Pearl" | C 3L | 40-60cm | 3/m2 | Bushy; 4 breaks |
| 52 No. | Cho Sun | | Choisya ternata "Sundance" | C 3L | 40-60cm | 3/m2 | |
| 279 No. | Cot Dec | | Cotoneaster conspicuus "Decorus" | C 3L | 30-40cm | 4/m2 | Branched; 4 breaks |
| 135 No. | Esc AB | | Escallonia "Apple Blossom" | C 3L | 40-60cm | 3/m2 | Bushy; 4 breaks |
| 23 No. | Euo Gol | | Euonymus fortuneii "Emerald n Gold" | C 3L | 20-30cm | 4/m2 | |
| 6 No. | Euo Harle 10L | | Euonymus fortuneii "Harlequin" | C 10L | 30-40cm | 3/m2 | Bushy; 11breaks |
| 276 No. | Heb EG | | Hebe "Emerald Green" | C 3L | 30-40cm | 4/m2 | |
| 181 No. | Heb Mrs 5-7.5L | | Hebe "Mrs Winder" | C 5-7.5L | 30-40cm | 5/m2 | Bushy; 7 breaks |
| 229 No. | Heb pin Suth | | Hebe pinguiifolia "Sutherlandii" | C 3L | 5-10cm | 5/m2 | |
| 293 No. | Lav Hid 3L | | Lavandula angustifolia "Hidcote" | C 3L | 20-30cm | 5/m2 | Bushy; 5 breaks |
| 231 No. | Lon pil | | Lonicera pileata | C 3L | 30-40cm | 3/m2 | Bushy; 6 breaks |
| 33 No. | Pho Pur 10L | | Phormium tenax "Purpurea" | C 10L | 80-100cm | 1/m2 | Triple crown |
| 13 No. | Phy Dia | | Physocarpus "Diabolo" | C 10L | 40-60cm | 1/m2 | Bushy; 5 breaks |
| 19 No. | Pin Mug | | Pinus mugo "Mughus" | C 10L | 30-40cmD | 1/m2 | Bushy |
| 98 No. | Pot Abb | | Potentilla fruticosa "Abbotswood" | C 3L | 20-30cm | 3/m2 | Bushy; 4 breaks |
| 31 No. | Ros MJU | | Rosmarinus "Miss Jessops Upright" | C 3L | 40-60cm | 3/m2 | Bushy; 4 breaks |
| 147 No. | Sar con | | Sarcococca confusa | C 3L | 20-30cm | 4/m2 | Bushy; 6 breaks |
| 85 No. | Ski KG | | Skimmia x confusa "Kew Green" | C 3L | 30-40cm | 4/m2 | Bushy; 3 breaks |
| 15 No. | Spi nip SM 10L | | Spiraea nipponica "Snow Mound" | C 10L | 60-80cm | 3/m2 | Bushy; 9 break |
| 101 No. | Vib dav | | Viburnum davidii | C 3L | 20-30cm | 4/m2 | Bushy; 3 breaks |
| 13 No. | Wei FP 10L | | Weigela florida "Folils Purpureus" | C 10L | 60-80cm | 1/m2 | Branched; 7 breaks |

| QTY | UNIT | CODE | PLANT NAME | STOCK | SIZE | SPACING |
|--|------|--------------|------------------------------|-------|------|---------|
| Herbaceous plants (Mixed Ornamental Beds) | | | | | | |
| 136 | No. | Car Oshi Eve | Carex oshimensis "Evergold" | C 3L | | 5/m2 |
| 283 | No. | Fes EB | Festuca glauca "Elijah Blue" | C 2L | | 7/m2 |
| 142 | No. | Luz syl | Luzula sylvatica | C 2L | | 5/m2 |
| 84 | No. | Pac ter | Pachysandra terminalis | C 2L | | 3/m2 |

| QTY | UNIT | CODE | PLANT NAME | STOCK | SIZE | SPECIFICATION |
|---|------|------|--------------------------------|-------|------|---------------|
| Plant Mixes | | | | | | |
| 386m2 LATHAM PASTURES GC MIX planted @ 5/m2 | | | | | | |
| 20% | 386 | No. | Lamium maculatum | | C 1L | Full pot; |
| 20% | 386 | No. | Aguja reptens | | C 1L | Full pot; |
| 20% | 386 | No. | Pachysandra terminalis | | C 1L | Full pot; |
| 10% | 193 | No. | Bergenia cordifolia 'Purpurea' | | C 1L | Full pot; |
| 10% | 193 | No. | Dryopteris erythrosora | | C 2L | Full pot; |
| 5% | 97 | No. | Hemerocallis "Stella d'Oro" | | C 2L | Full pot; |
| 5% | 97 | No. | Lazula nivea | | C 1L | Full pot; |
| 5% | 97 | No. | Kniphofia uvaria | | C 2L | Full pot; |
| 5% | 97 | No. | Crocoshmia 'Mistral' | | C 2L | Full pot; |

Individual varieties to be planted in groups of approximately 7-11. Lamium and Ajuga planted to outer edge of bed. Bergenia, Dryopteris, Lazula and Pachysandra to be planted to centre of bed. Crocoshmia, Hemerocallis and Kniphofia to be planted in groups of 1-3 and scattered throughout beds.

Wildflower Mixes

5315m2 SPECIES RICH GRASS (including service verges and areas of POS) sown @ 4g/m2

Emorsgate: EL1 'Flowering Lawn Mixture'

Seed mix is to be sown to supplier's recommendations at a rate of 4g per m2.

1537m2 WILDFLOWER - LOAM SOILS sown @ 4g/m2

Emorsgate: EM5 'Meadow Mixture for Loamy Soils'

Seed mix is to be sown to supplier's recommendations at a rate of 4g per m2.

5589m2 WOODLAND WILDFLOWER planted @ 4g/m2

Emorsgate: EW1 'Woodland Mixture'

Seed mix is to be sown to supplier's recommendations at a rate of 4g per m2.

Amenity Grass

4636m2 Amenity Grass (including front lawns)

Notes and Abbreviations

| | | |
|-------|---|---|
| B | = | Bare root (bagged). |
| C | = | Container (or pot) grown, followed by size of the container (or pot). |
| FORM | = | Shape of tree as supplied by the nursery. |
| QTY | = | Quantity |
| RB | = | Rootballed (balled and wrapped). |
| SIZE | = | Height or Spread of juvenile plant. |
| Std | = | (clear stem) Standard. |
| STOCK | = | Root condition/protection method eg Bare root. |
| Trans | = | Transplant (or undercut seedling). |

- Refer to specification for further information.

- All plants to be completely hardened off

- Substitutions to be agreed with Landscape Architect.

Plant Schedule generated by "Qscape" software 05/10/2020