



Proposed 5.5m wide access with 10m radii

Circa 120m length of 2m wide footway to be provided on east side of Neverstitch Road

Magenta dotted lines show 107.5m forward visibility to vehicle waiting to turn right (equivalent to 41.15mph design speed)

Magenta dotted line shows 106.1m forward visibility to a point 1m from nearside kerbline, 116.5m to centreline and 122m to centre of northbound lane (equivalent to 40.9mph, 43.0mph and 44.3mph design speeds)

Green dotted lines show 2.4 x 122m visibility splay to the south based on 44.3mph 85th percentile approach speed

Roadsign to be lifted to over 1.5m clearance

Green dotted lines show 2.4 x 120m visibility splay to the north based on 43.75mph design speed

Pedestrian crossing with refuge island, road widening and 3m wide lanes as proposed as part of Wain Homes scheme

New footway to be provided on A577 Neverstitch Road south from proposed access to link to existing footway of A577 Neverstitch Road / Ormskirk Road roundabout

D	06.11.20	Addition of footway on A577 Neverstitch Road	SFB	SFB	PRC
C	23.04.20	General amendments to access	SFB	SFB	PRC
B	16.04.20	General amendments to access	SFB	SFB	PRC
A	15.04.20	General amendments to access	SFB	SFB	PRC
Rev.	Date	Revision Details	Drawn	Check	App.

CBO TRANSPORT
 Barnell House
 53 Fountain Street
 Manchester
 M2 2AN
 T: 0161 235 6365
 F: 0161 235 6566
 E: info@cbotransport.co.uk
 W: www.cbotransport.co.uk

Client
 Bellway

Project
 Lathom Pastures Phase 2

Drawing Title
 Proposed Access Arrangements

Drawn	Checked	Approved
SFB	SFB	PRC

Scale / Size
 1:500 @ A1

Date
 06.02.2020

Status	Drg No	Rev
Information	CBO-0603-002	D