



**Notes / Key:**

Stone indents: Sandstone to best match existing as determined by petrographic analysis. Unless otherwise indicated repairs at tracery to be full stone indents (Type 1 potential partial indent).

Stone repairs to be carried out whilst stained glass has been removed from site by Rainbow Glass.

All stone indents to be fixed with 6mm SS dowels to SE spec.

Mason, SE and CA to agree on approach to repair type 3 to achieve a robust solution on site. Team to agree methodology for replacement and schedule of works to avoid destabilisation of structure during indents.

Do not scale from this drawing.  
All existing dimensions to be checked on site prior to commencement of works or manufacturing of components. Any discrepancies to be brought to the attention of the architect - if in doubt, ask.

This drawing is the copyright of John Gilbert Architects Ltd. No copying or distribution of this drawing or any part thereof is permitted without prior written permission.



201 White Studios, 62 Templeton Street, Glasgow, G40 1DA  
Tel: 0141 551 8383  
Web: www.johngilbert.co.uk

Client  
**ABOVE ADVENTURE**

Project  
**WOODSTOCK STREET CHURCH**

Title  
**WEST FACING ROSE LANCET**

Project Status  
**TENDER**

Job No **03749** Scale at A3 **NTS**

Drawn by **SP** Date of issue

Rev.	Amendment	Date
A	REFERENCE NUMBERS ADDED	07.01.20

Main Church, West Facing Lancet - Window ref. W67

Drg No. **[21]11** Rev **A**