



NOTE: exact type of stitching to be agreed on site with CA. Where threaded dowels used they must be stainless and should bed into the stone at least 200mm either side of crack. In some cases a full stone indent may be required

John Gilbert
ARCHITECTS

201 The White Studios
Templeton Business Centre
Templeton Street, Glasgow G40 1DA
Tel 0141-551 8383 Fax 0141-554 7884
e-mail: info@johngilbert.co.uk
www.johngilbert.co.uk

Rev	Date	Alteration
A	24/11/20	Rod set into slot & indented omitted
Job No	03749	Drawn by JG Size A3
Date	29/9/20	Scale NTS
Project	WOODSTOCK CHURCH	
Title	INDENTING, FIXING, STITCHING	
Dwg No	[21]23	Rev A