



Remove perspex and fixings. Restore leaded glazing as schedule. Locally indent fixing holes after removing screws

Notes / Key:

Stone indents: Sandstone to best match existing as determined by petrographic analysis. Unless otherwise indicated repairs to be minimum depth of 100mm (type 4/5 to be agreed on site).

Stone repairs to be carried out whilst stained glass has been removed from site by Rainbow Glass.

All stone indents to fixed with 6mm SS dowels to SE spec.

Team to agree methodology for replacement and schedule of works to avoid destabilisation of structure during indents.

Do not scale from this drawing. All existing dimensions to be checked on site prior to commencement of works or manufacturing of components. Any discrepancies to be brought to the attention of the architect - if in doubt, ask.

This drawing is the copyright of John Gilbert Architects Ltd. No copying or distribution of this drawing or any part thereof is permitted without prior written permission.

John Gilbert ARCHITECTS

201 White Studios, 62 Templeton Street, Glasgow, G40 1DA
 Tel: 0141 551 8383
 Web: www.johngilbert.co.uk

Client
ABOVE ADVENTURE

Project
WOODSTOCK STREET CHURCH

Title
NORTH FACING LANCET - VENTED BELL TOWER

Project Status
TENDER

Job No **03749** Scale at A3 **NTS**

Drawn by **SP** Date of issue

Rev.	Amendment	Date
A	REFERENCE NUMBERS ADDED	07.01.20

Main Church, North Facing Lancet - Vented Bell Tower