



Appendix 3: Tree Works Schedule

Tree Number	Species	Height (m)	Age Class	Tree works prescription	Works Schedule
G1	Broad-Leafed Lime <i>Tilia platyphyllos</i>	3	Y	Linear group of 4 new plantings. Formative prune	6 Months
2	Common Lime <i>Tilia europaea</i>	11	M	. Crown raise over road to 5.2m in height Remove - Basal growth Remove - Major dead wood	3 Months
3	Common Lime <i>Tilia europaea</i>	7	M	Reduce decayed stem by 2m in height Remove - Basal growth	3 Months
4	Common Lime <i>Tilia europaea</i>	15	M	Crown raise over road to 5.2m height Remove - Basal growth Remove - Major dead wood	3 Months



Appendix 3: Tree Works Schedule

Tree Number	Species	Height (m)	Age Class	Tree works prescription	Works Schedule
8	London Plane <i>Platanus x hispanica</i>	10	M	Reduce crown - To previous reduction points	12 Months
10	Silver Maple <i>Acer saccharinum</i>	15	M	Reduce crown - To previous reduction points	12 Months
11	Broad-Leafed Lime <i>Tilia platyphyllos</i>	9	M	Raise low canopy - To 2.5m Remove - Basal growth	3 Months
G13	Leyland Cypress <i>X Cupressocyparis leylandii</i>	5	M	Off-site group. Trim overhanging canopy edge to contain branch spread.	3 Months



Appendix 3: Tree Works Schedule

Tree Number	Species	Height (m)	Age Class	Tree works prescription	Works Schedule
16a	English Elm <i>Ulmus procera</i>	4	EM	Fell - Fell to ground level	2 Months
G19	<i>Birch, Hornbeam, Maple</i>	3	Y	Group of new plantings. Remove tree stakes and apply mulch to tree pits.	3 Months
23	<i>Tilia platyphyllos</i> <i>Broad leaved lime</i>	3	Y	Remove tree stake	3 Months