


What does a conservation package include?

- Roof window with pre-fitted glazing bar.
- Laminated safety glazing as standard.
- Insulation collar and underfelt collar provided for a weathertight and energy efficient installation.



Roof pitch



20°-65°

Suitable for roof pitches between 20° and 65°.

VELUX conservation roof windows

For traditional buildings

When planning dictates that a window of traditional external appearance is required, conservation roof windows should be considered. All of our conservation roof windows have the same technical features of a VELUX roof window but in a traditional black conservation style.

Please visit velux.co.uk/onlinebrochure for information on how to create your own grey conservation package.

- Available in either centre-pivot or top-hung.
- Black external profiles and glazing bar.
- RAL colour 9005.
- Recessed installation for slate and tiled roofs.
- Top-hung roof windows listed below are suitable for emergency escape.
- Other sizes and glazing options available – contact us for further information.

Conservation roof windows

External frame size (nominal w x h) cm

Code	Description	55 x 98	55 x 118	66 x 118	78 x 118	78 x 140	134 x 98
		CK04	CK06	FK06	MK06	MK08	UK04
Centre-pivot white painted							
GGL SD5N2 U-value 1.3 W/m²K	GGL 2570 roof window + EDN recessed flashing for slate up to 8mm thick (min 20° roof pitch).	£484	£502	£555	£584	£629	£732
GGL SD5P2 U-value 1.3 W/m²K	GGL 2570 roof window + EDP flashing for plain tiles up to 14mm thick (min 25° roof pitch).	£426	£442	£491	£517	£558	£652
GGL SD5W2 U-value 1.3 W/m²K	GGL 2570 roof window + EDW flashing for tiles up to 120mm in profile (min 15° roof pitch).	£426	£442	£491	£517	£558	£652
GGL SD5J2 U-value 1.3 W/m²K	GGL 2570 roof window + EDJ recessed flashing for tiles up to 90mm in profile (min 20° roof pitch).	£484	£502	£555	£584	£629	£732
Top-hung white painted. For roof pitches of 55°-75°, please specify special springs when ordering.							
GPL SD5N2 U-value 1.3 W/m²K	GPL 2570 roof window + EDN recessed flashing for slate up to 8mm thick (min 20° roof pitch).	-	-	-	-	£763	-
GPL SD5P2 U-value 1.3 W/m²K	GPL 2570 roof window + EDP flashing for plain tiles up to 14mm thick (min 25° roof pitch).	-	-	-	-	£692	-
GPL SD5W2 U-value 1.3 W/m²K	GPL 2570 roof window + EDW flashing for tiles up to 120mm in profile (min 15° roof pitch).	-	-	-	-	£692	-
GPL SD5J2 U-value 1.3 W/m²K	GPL 2570 roof window + EDJ recessed flashing for tiles up to 90mm in profile (min 20° roof pitch).	-	-	-	-	£763	-

- ▶ All roof windows have a delivery time of 2 days.
- ▶ Delivery time is in working days from receipt of orders placed before 4pm (UK) and 11.30am (NI).

Rooflights for uninhabited spaces

Rooflights

- Frame and integrated flashing made of maintenance-free polyurethane.
- Operated using a handle with three ventilation positions.
- Extruded aluminium sash which can be hinged on both sides, opening to an angle of 90°.
- Opening restrictor that engages at 90° only.
- Black internal and external finish.



Uninhabited spaces

Our rooflights are designed in such a way that you have the opportunity to bring light into uninhabited spaces. It is not advisable to use these rooflights in habitable rooms due to their thermal performance.

Rooflights for uninhabited spaces

External frame size (nominal w x h) cm

Code	Description	54 x 83	46 x 61
GVT 103 0059Z U-value 3.1 W/m²K	Side-hung outward-opening rooflight.	£192	-
GVK 0000Z U-value 5.1 W/m²K	Side-hung outward-opening rooflight.	-	£141

- ▶ All rooflights have a delivery time of 2 days.
- ▶ Delivery time is in working days from receipt of orders placed before 4pm (UK) and 11.30am (NI).