



DRAINAGE STRATEGY REPORT

The Cottage, Main Street, YO25 8HL

Commissioned by Morgan Lloyd Jones Ltd

Report: 18865-L-RP-001 R0 16th October 2020

Notation

DIA Drainage Impact Assessment

EA Environment Agency
FRA Flood Risk Assessment
IDB Internal Drainage Board
LLFA Lead Local Flood Authority

NPPF National Planning Policy Framework
NPPG National Planning Practice Guidance
SFRA Strategic Flood Risk Assessment
SuDS Sustainable Drainage Systems



DRAINAGE STRATEGY ASSESSMENT

The Cottage, Main Street, YO25 8HL

CONTENTS

- 1 INTRODUCTION
- 2 PROJECT DEVELOPMENT
- 3 SURFACE WATER DRAINAGE STRATEGY
- 4 SUSTAINABLE DRAINAGE SYSTEMS
- 5 FOUL WATER DRAINAGE STRATEGY
- 6 CONCLUSION
- **7 LIMITATIONS**

APPENDIX A Existing Site Layout

APPENDIX B Proposed Site Layout

APPENDIX C Infiltration Rate Calculations

APPENDIX D Tedds Soakaway Calculations

APPENDIX E Yorkshire Water Sewer Records

APPENDIX F Source Control Attenuation Calculations

APPENDIX G Drainage Schematic Layout

ISSUE LOG FOR REPORT 18865-L-RP-001

Rev	Date	Description	Author	Checked
RO	16 th October 2020	FIRST ISSUE	BW	GS

Issuing office: Mason Clark (LEEDS). Refer to final page for full office details.



1 INTRODUCTION

Mason Clark Associates (MCA) has been commissioned by Morgan Lloyd Jones Ltd to compile a drainage strategy report for the redevelopment of the cottage, Main Street, Driffield.

The proposed residential development of is located off Main Street, Driffield. An approximate post code is YO25 8HL and coordinates are (509800, 459460).

This report has been carried out to provide an initial feasibility assessment for suitable methods for discharge of surface and foul water from the proposed development.



2 PROPOSED DEVELOPMENT

The proposed residential development of is located off Main Street, Driffield. An approximate post code is YO25 8HL and coordinates are (509800, 459460).

The site is currently the location of a single detached dwelling including a garage and conservatory. The building is to be demolished to accommodate the new dwelling which is to be built on the existing footprint. An Existing Site Plan is included in Appendix A and a Proposed Site Plan can be found in Appendix B.

The proposed finished flood levels are to remain as per the existing levels, external levels have not been provided by the architect at the time of writing this report.

A site visit was carried out by Mason Clark Associates on 27th August 2020, a visual inspection of the site indicated that the site is generally level. External levels towards the front and sides of the property approximately match the finished floor levels however, the garden at the rear of the property is 0.8m higher than the finished floor levels. There is a slight slope at the front of the property towards the access in Main Street.



3 SURFACE WATER DRAINAGE STRATEGY

Building Regulations Part H states that the priority for discharging surface water runoff from a development is as follows; (1st) Infiltration into the ground, (2nd) discharge into a watercourse, (3rd) discharge into a sewer. These receptors have been investigated below.

3.1 Discharge via Infiltration

British Geological Survey (BGS) geological mapping suggests that the superficial deposits beneath the site comprise of Devensian Glacial Till which is described as firm-stiff sandy silty gravelly clay. The geological mapping suggests that bedrock geology beneath the site is Flamborough Chalk Formation. There are no borehole records in the immediate vicinity of the site available on the British Geological Society Borehole Scans.

Auger type soakaway testing was carried at the rear of the dwelling site on 27^{th} August 2020. One trial hole (TH1) was excavated to establish ground conditions and complete the test, a single test was carried out in TH1 and produced an infiltration rate of 6.76×10^{-6} m/s. Infiltration rate calculations are shown in Appendix C.

The infiltration rate extrapolated from the test show 'low' permeability and 'poor' drainage conditions as per figure 1 below.






Figure 1 – Typical Permeability Values

This infiltration rate was used to calculate the size of a geocellular soakaway that would be required for the development. The calculations show a 32.4m³ soakaway would be able to store the volume required however, this size soakaway would fail as the soakaway discharge time is significantly greater than 24 hours to empty the soakaway to half volume. A soakaway of this size would be unsuitable for this site given the scale of the proposed development.

The soakaway calculations can be found in Appendix D.



3.2 Discharge via Watercourse

There are no suitable watercourses within the vicinity of the site. The closest main river is Kelly Beck is

approximately 500m west of the site, an unnamed watercourse which connects into the beck is present

approximately 300m west of the site. Any connection to this would require a sewer that crosses

significant amounts of 3rd party land and a public highway and therefore this would not be an

acceptable method of surface water disposal.

3.3 Discharge to Public Sewers

As a last resort following the hierarchy of surface water, disposal discharge to the public sewer system

can be considered.

Yorkshire Water sewer records (Appendix E) indicate that there are no public sewers recorded in the

vicinity of the site. Connection to public sewers will therefore not be feasible.

3.4 Discharge via Existing Arrangement

A CCTV survey was carried out on site on 27th August 2020. The existing drainage arrangement on site

shows both surface water and foul water connecting into an on-site septic tank before discharging to

a combined manhole in the corner of the site. The final chamber was accessed with a camera via the

upstream pipes however, due to site constraints the chamber lid could not be removed and inspected

and therefore it is unknown where the water discharges downstream of the chamber.

Based on the information available, it has been determined that surface and foul water discharge is

connected to a manhole chamber 25m south west site of the site on the opposite side of Main Street.

It is currently unknown where the water discharges to downstream of the manhole chamber, it is

possible that it discharges to a nearby ditch or alternatively infiltrates via a drainage field.

masonclarkossociates

3.5 Drainage Strategy and Attenuation Requirements for new Development

As discussed in Section 3.4, the surface water shall discharge from site via the existing arrangement.

Impermeable Areas

From the Existing Layout Plan (Appendix A) an estimation of the previous development currently draining to public sewers has been calculated to be 340m² or 0.034ha. Proposed impermeable areas from roofs and external from the Proposed Layout Plan (Appendix B) is 390m² or 0.039ha.

Using the Modified Rational Method, the discharge rate of the existing development is calculated as follows:

0.034ha x $(2.78 \times 50) = 4.73$ l/s. A 50% reduction of this will give a final discharge rate of 2.36 l/s.

Details of the existing connection to the sewer main is to be confirmed. However, the capacity should be sufficient as the proposed impermeable area is not much greater than the existing and does not consider a 50% reduction in discharge rate.

<u>Attenuation Requirements</u>

MicroDrainage Source Control has been used to estimate the storage for the proposed impermeable areas shown above for a 1 in 100 year storm event including 30% increase for impacts of climate change on peak rainfall. The calculations included a limited flow rate of 2.36 l/s, as calculated in the previous section. The results of the modelling are included in Appendix F and summarised below in Table 1.

Return Period	30 Year	100 Year + 30% Climate
		Change
Estimated attenuation	5.2m³	12.1m³
required		

Table 1 - Modelled Attenuation Volume Requirements



A Drainage Schematic Layout can be found in Appendix G which shows that storage can be provided on site so that up to a 1 in 100 year event plus a 30% allowance for climate change can be safely accommodated on site.



4 SUSTAINABLE DRAINAGE SYSTEMS

Where possible, Sustainable drainage (SuDS) systems/techniques should be used to drain the site of surface water runoff. These could be in the form of permeable paving, rainwater harvesting, ponds and other above ground green systems. Swales could also be incorporated into the layout to convey surface runoff rather than below ground pipes (which tend to have a higher velocity).

4.1 Sustainable Drainage (Overview)

Drainage systems can contribute to sustainable development and improve urban design, by balancing the different issues that influence the development of communities. Approaches to manage surface water that take account of water quantity (flooding), water quality (pollution), amenity and biodiversity issues are collectively referred to as Sustainable Drainage Systems (SuDS).

SuDS mimic nature and typically manage rainfall close to where it falls. SuDS can be designed to slow water down (attenuate) before it enters streams, rivers and other watercourses, they provide areas to store water in natural contours and can be used to allow water to soak (infiltrate) into the ground or evaporated from surface water and lost or transpired from vegetation (known as evapotranspiration).

SUDS are technically regarded a sequence of management practices, control structures and strategies designed to efficiently and sustainably drain surface water, while minimising pollution and managing the impact on water quality of local water bodies.

SuDS are more sustainable than traditional drainage methods because they:

- Manage runoff volumes and flow rates from hard surfaces, reducing the impact of urbanisation on flooding;
- Protect or enhance water quality (reducing pollution from runoff);
- Protect natural flow regimes in watercourses;
- Are sympathetic to the environment and the needs of the local community;
- Provide an attractive habitat for wildlife in urban watercourses;
- Provide opportunities for evapotranspiration from vegetation and surface water;
- Encourage natural groundwater/aquifer recharge (where appropriate);
- Create better places to live, work and play.



4.2 SuDS principles

Sustainable drainage is a departure from the traditional approach to draining sites. There are some key principles that influence the planning and design process enabling SuDS to mimic natural drainage by:

- storing runoff and releasing it slowly (attenuation);
- allowing water to soak into the ground (infiltration);
- Slowly transporting (conveying) water on the surface;
- filtering out pollutants;
- allowing sediments to settle out by controlling the flow of the water.

The above was taken from www.susdrain.org

SUDS Technique	Can they be feasibly incorporated into the site?	Comments
Green Roofs	√	The proposed development could be designed to incorporate these elements.
Basins and Ponds	×	The proposed development could not be designed to incorporate these elements due to the size of the site.
Filter Strips, Swales and Bio-Retention	×	The proposed development could not be designed to incorporate these elements due to the size of the site.
Infiltration techniques	×	Soakaway testing results indicate that the site would not be suitable for infiltration.
Permeable surfaces and tree pits	✓	Resurfacing of the external areas could be in a permeable material to provide surface water attenuation.
Rainwater Harvesting	√	The proposed development could be designed to incorporate rainwater harvesting.
Tanked Systems	✓	Attenuation storage could be provided below ground.



4.3 SuDS Maintenance

On-site SuDS systems will be privately managed rather than put forward for adoption by the local Water Authority. Exact details of the drainage systems will be determined during detailed design stage. The below table shows an indicative maintenance schedule for a typical Geo-Cellular Storage system which appears to be the most feasible option to suit the layout on initial assessment.

Schedule	Required Action	Frequency	
Regular	Inspect and Identify any areas that are	Monthly for 3 months,	
Maintenance	not operating correctly. If required,	Annually thereafter.	
	take remedial action.		
	Remove sediment from pre-treatment	Annually, or as required.	
	structures and/or internal forbays.		
Remedial Action	Repair/rehabilitate inlets, outlets and	Annually, or as required.	
	vents.		
Monitoring	Inspect/check all inlets, Outlets and	Annually	
	vents.		
	Survey inside of tank for sediment	Every 5 years, or as	
	build-up and remove if necessary.	required.	



5 FOUL WATER DRAINAGE STRATEGY

Foul water drainage systems should be designed, where possible, to drain via gravity. Yorkshire Water sewer records (Appendix E) that there are no public sewers recorded in the vicinity of the site. Connection to public sewers will therefore not be feasible.

Foul Water currently drains to a septic tank prior to discharging from site. As this system is no longer approved, it is recommended that a package treatment plant such as a Klargester BioDisc is used to treat the sewage to an acceptable level before discharging from site via the existing arrangement.

All below ground foul water drainage is to be designed and constructed to the current Building Regulations standards or where drainage is to be adopted by the local water authority, Sewers for Adoption 7th Edition.

A proposed Drainage Schematic Layout can be found in Appendix G.



6 CONCLUSIONS

Soakaway testing carried out on site prove that the site is not suitable for the use of infiltration systems.

Connection to the nearest watercourses have been ruled out due to the distance away from site and the nature of the surrounding areas (3rd party ownership).

There are no public sewers within the vicinity of the site. Therefore, surface water from the site shall remain as per the existing arrangement however, a restricted discharge rate of 2.4 l/s shall be incorporated. Flows over this rate will be attenuated on site. MicroDrainage Source Control calculations estimate 12.1m³ of storage is required for a 1 in 100 year event plus 30% allowance for climate change.

Sustainable drainage systems should be considered as part of the final site layout design. Systems such as, permeable paving and tanked systems are potentially feasible.

The septic tank on site should be replaced with an approved package treatment plant to allow an acceptable level of treatment to the sewage before discharging from site via the existing arrangement.



7 LIMITATIONS

All comments and proposals contained in this report, including any conclusions, are based on information available to Mason Clark Associates during investigations. The conclusions drawn by Mason Clark Associates could therefore differ if the information is found to be inaccurate or misleading. Mason Clark Associates accepts no liability should this be the case, nor if additional information exists or becomes available with respect to this scheme.

Where we have undertaken preliminary infiltration rate tests on site on your behalf this is for indicative purposes only to enable preliminary designs to progress. Where any subsequent designs rely upon infiltration and/or these test results then you should undertake further infiltration rate tests in accordance with accepted industry standard guidelines as detailed in Building Research Establishment publication BRE Digest 365.

Except as otherwise requested by the client, Mason Clark Associates is not obliged to and disclaims any obligation to update the report for events taking place after: -

- (i) The date on which this assessment was undertaken, and
- (ii) The date on which the final report is delivered

Mason Clark Associates makes no representation whatsoever concerning the legal significance of its findings or the legal matters referred to in the report.

The information presented and conclusions drawn are based on statistical data and are for guidance purposes only. The study provides no guarantee against flooding of the study site or elsewhere, nor of the absolute accuracy of water levels, flow rates and associated probabilities.


This report has been prepared for the use of Morgan Lloyd Jones Ltd. No other third parties may rely upon or reproduce the contents of this report without the written permission of Mason Clark Associates. If any unauthorised third party comes into possession of this report, they rely on it at their own risk and the authors do not owe them any Duty of Care or Skill.



APPENDIX A

Existing Site Layout





Existing Ground Floor GIFA = 107.4m²


EXISTING



APPENDIX B

Proposed Site Layout





PROPOSED GROUND FLOOR PLAN

Scale 1:50

Proposed Ground Floor GIFA = 149.8m²

PROPOSED



APPENDIX C

Infiltration Rate Calculations





Partnership House Monks Cross Drive York YO31 9GZ

Tel: (01904) 438005 Fax: (01904) 435988

Project No.	Sheet No.
18865L	1
Prepared by	Date
BW	27.08.2020
Checked By	Date
00	

The Cottage, Kelk

Soakaway Test Data

TH1

TEST 1

IESI 1	Time elapsed	Time elapsed	Depth to Water		
Real Time	(days hh:mm)	(minutes)	(m)	Water Height	Commen
27/08/2020 11:13	0 00:00	0	0.400	0.350	
27/08/2020 11:15	0 00:02	2	0.500	0.250	75%
27/08/2020 11:17	0 00:04	4	0.530	0.220	
27/08/2020 11:23	0 00:10	10	0.550	0.200	
27/08/2020 11:30	0 00:17	17	0.570	0.180	
27/08/2020 11:32	0 00:19	19	0.575	0.175	50%
27/08/2020 11:35	0 00:22	22	0.580	0.170	
27/08/2020 11:40	0 00:27	27	0.580	0.170	
27/08/2020 11:45	0 00:32	32	0.590	0.160	
27/08/2020 11:50	0 00:37	37	0.600	0.150	
27/08/2020 12:00	0 00:47	47	0.610	0.140	
27/08/2020 12:10	0 00:57	57	0.610	0.140	
27/08/2020 12:20	0 01:07	67	0.620	0.130	
27/08/2020 12:30	0 01:17	77	0.630	0.120	
27/08/2020 12:40	0 01:27	87	0.640	0.110	
27/08/2020 12:50	0 01:37	97	0.650	0.100	
27/08/2020 13:00	0 01:47	107	0.660	0.090	25%
27/08/2020 13:10	0 01:57	117	0.670	0.080	
_	_	_	_		


	TEST 1
Total depth	0.750
H (m)	0.350
H _{75%} (m)	0.263
H _{50%} (m)	0.175
H _{25%} (m)	0.088



Partnership House Monks Cross Drive York YO31 9GZ Tel: (01904) 438005 Fax: (01904) 435988 www.masonclark.co.uk

Project No.	Sheet No.	
18865L	2	
Prepared by	Date	
BW	27.08.2020	
Checked By	Date	
GS		

The Cottage, Kelk



Λ_	TEST 1
A _{P50}	IESII
Side (Round)	0.707
Base	0.040
A _P 50	0.163
•	
V _{p75-25}	0.007
t _{p75}	120
t _{p25}	6420
t _{p75-25}	6300
Soil infiltration rate,	
f (m/s)	6.76E-06

Upper Square Section			
Length/Width	0.250		
Height	0.300		

Lower Circular Section			
Diameter	0.225		
Height	0.550		

APPENDIX D

Tedds Soakaway Calculations





Project				Job no.	
The cottage, Main Street				18865L	
Calcs for				Start page no./Revision	
New Impermeable Area			1	P1	
Calcs by BW	Calcs date 12/10/2020	Checked by GS	Checked date 12/10/2020	Approved by GS	Approved date 12/10/2020

SOAKAWAY DESIGN

In accordance with BRE Digest 365 - Soakaway design

Tedds calculation version 2.0.04

Design rainfall intensity

Location of catchment area York

 $\label{eq:A} \mbox{Impermeable area drained to the system} \qquad \mbox{$A=390.0 m^2$} \\ \mbox{Return period} \qquad \mbox{$Period=100 yr$}$

Ratio 60 min to 2 day rainfall of 5 yr return period r = 0.392

5-year return period rainfall of 60 minutes duration M5_60min = **19.0** mm

Increase of rainfall intensity due to global warming $p_{climate} = 30 \%$

Soakaway / infiltration trench details

Soakaway type Rectangular Minimum depth of pit (below incoming invert) d = 800 mm Width of pit w = 5500 mm Length of pit l = 8000 mm Percentage free volume $v_{\text{free}} = 95 \text{ m/s}$ Soil infiltration rate $f = 6.76 \times 10^{-6} \text{ m/s}$

Wetted area of pit 50% full $a_{s50} = I \times d + w \times d = 10800000 \text{ mm}^2$

Table equations

 $\begin{array}{ll} \text{Inflow (cl.3.3.1)} & \qquad & \text{I} = \text{M100} \times \text{A} \\ \text{Outflow (cl.3.3.2)} & \qquad & \text{O} = a_{s50} \times \text{f} \times \text{D} \\ \text{Storage (cl.3.3.3)} & \qquad & \text{S} = \text{I} - \text{O} \end{array}$

Duration, D (min)	Growth factor Z1	M5 rainfalls (mm)	Growth factor Z2	100 year rainfall, M100 (mm)	Inflow (m³)	Outflow (m³)	Storage required (m³)
5	0.37;	9.2;	1.89;	17.3;	6.75;	0.02;	6.73
10	0.52;	12.9;	1.96;	25.2;	9.81;	0.04;	9.77
15	0.63;	15.6;	1.99;	31.1;	12.12;	0.07;	12.05
30	0.80;	19.8;	2.03;	40.1;	15.64;	0.13;	15.51
60	1.00;	24.7;	2.01;	49.7;	19.37;	0.26;	19.11
120	1.21;	29.9;	1.97;	58.9;	22.96;	0.53;	22.44
240	1.46;	36.0;	1.92;	69.2;	26.98;	1.05;	25.93
360	1.62;	39.9;	1.89;	75.5;	29.44;	1.58;	27.87
600	1.81;	44.8;	1.85;	83.0;	32.36;	2.63;	29.74
1440	2.27;	56.1;	1.77;	99.2;	38.70;	6.31;	32.40

Required storage volume $S_{req} = 32.40 \text{ m}^3$

Soakaway storage volume $S_{act} = I \times d \times w \times V_{free} = 33.44 \text{ m}^3$

PASS - Soakaway storage volume

Time for emptying soakaway to half volume $t_{s50} = S_{req} \times 0.5 \ / \ (a_{s50} \times f) \ = 61 hr \ 38 min \ 14 s$

FAIL - Soakaway discharge time greater than 24 hours

APPENDIX E

Yorkshire Water Sewer Records



YORKSHIRE WATER PROTECTION OF MAINS AND SERVICES

- 1. The position of Yorkshire Water Services Ltd (YWS) apparatus shown on the existing mains record drawing(s) indicates the *general* position and nature of our apparatus and the accuracy of this information cannot be guaranteed. Any damage to YWS apparatus as a result of your works may have serious consequences and you will be held responsible for all costs incurred. Prior to commencing major works, the exact location of apparatus must be determined on site, if necessary by excavating trial holes. The actual position of such apparatus and that of service pipes which have not been indicated must be established on site by contacting the Customer Helpline on 0845 124 24 24 for both water and sewerage.
- 2. The public sewer and water network is lawfully retained in its existing position and the sewerage and water undertaker is entitled to have it remain so without any disturbance. The provisions of section 159 of the Water Industry Act 1991 provides that the undertaker may "inspect, maintain, adjust, repair or alter" the network. Those rights are given to enable the undertaker to perform its statutory duties. Any development of the land or any other action that unacceptably hindered the exercise of those rights would be unlawful. The provisions contained in Section 185 of the Water Industry Act 1991 state that where it is reasonable to do so, a person may require the water supply undertaker to alter or remove a pipe where it is necessary to enable that person to carry out a proposed change of use of the land. The provisions contained in Section 185 also require the person making the request to pay the full cost of carrying out the necessary works.
- 3. Ground levels over existing YWS apparatus are to be maintained. Sewers in highways will *generally* be laid to give 1200mm of cover from finished ground level working to kerb races, other permanent identification of the limits of the road or to an agreed line and level. Substantial increases or decreases to this 1200mm depth of cover will result in the sewer being re-laid at your expense. Water mains and services will *generally* be laid with a minimum of 750mm depth of cover however some mains and services usually those installed over 50 years ago may have less ground cover.
- 4. If surface levels are to be decreased / increased significantly the effects on existing water supply apparatus will be carefully considered and if any alterations are necessary, the costs of the alterations will be recharged to you in full. Outlets on fire hydrants must be no more than 300mm below the new levels and all surface boxes must be adjusted as part of the scheme.
- 5. To enable future repair works to be carried out without hindrance; any pipe, cable, duct, etc. installed parallel to a water main or service pipe should not be installed directly over or within 300mm of a water main or service pipe or 1000mm of a waste water asset. Where a pipe, cable, duct, etc. crosses a main or service it should preferably cross perpendicular or at an angle of no less than 45o and with a minimum clearance of 150mm. These requirements apply to activities within an existing highway and are relevant to the installation of pipes, cables, ducts, etc. up to and including 250mm in diameter (see illustration below). Necessary protection measures for installations greater than 250mm in diameter and/or in private land will need to be agreed on an individual basis. Installations within a new development site must comply with the National Joint Utilities Group publication Volume 2: NJUG Guidelines On The Positioning Of Underground Utilities Apparatus For New Development Sites.
- 6. All excavation works near to YW apparatus should be by hand digging only.
- 7. Backfilling with a suitable material to a minimum 300mm above YW apparatus is required.
- 8. Adequate support must be provided where any works pass under YW apparatus.
- 9. Jointing chambers, lighting columns and other structures must be installed in such a way that future repair or maintenance works to YW apparatus will not be hindered.
- 10. Apparatus such as; railings, sign posts, etc. must not be placed in such a way that they prevent access to or full operation of controlling valves, hydrants or similar apparatus. YWS surface boxes must not be covered or buried. Any adjustment, alteration or replacement of manhole covers must be agreed on site prior to the commencement of the works with a YWS Inspector who may be contacted via our Call Centre on 0845 124 24 24.
- 11. Explosives shall not be used within 100 metres of any Yorkshire Water Services apparatus or installations.
- 12. Vibrating plant should not be used directly over any apparatus. Movement or operation by vehicles or heavy plant is not to be permitted in the immediate vicinity of YWS plant or apparatus unless there has been prior consultation and, if necessary, adequate protection provided without cost to YWS.
- 13. *Under no circumstances* should thrust boring or similar trenchless techniques commence until the actual position of the Company's mains/services along the proposed route have been confirmed by trial holes.
- 14. Any alterations to the highway should be notified following the procedures outlined in the New Road and Street Works Act 1991 Code of Practice; Measures Necessary Where Apparatus Is Affected By Major Works (Diversionary Works).
- 15. You will be held responsible for any damage or loss to YWS apparatus during and after completion of work, caused by yourselves, your servant or agent. Any damage caused or observed to YWS plant or apparatus should be immediately reported to YWS. Should YW incur any costs as a result of non-compliance with the above, all costs will be rechargeable in full.
- 16. You should ensure that nothing is done on the site to prejudice the safety or operation of YWS employees, plant or apparatus.
- 17. In accordance with the New Roads and Street Works Act 1991, Chapter 22, Part 3, Section 80. The location of any identified YW asset "which is not marked, or is wrongly marked, on the records made available" should be communicated back to Yorkshire Water. The location of the apparatus should be identified on copies of the supplied plans which should be returned to Yorkshire Water (Asset Records Team) with photographic supporting evidence where possible.
- 18. The Government has decided that responsibility for private sewers serving two or more properties and lateral drains (the section of pipe beyond the boundary of a single property, connecting it to the public sewer) will be transferred to the water companies on Oct 1 2011.




- Private pumping stations will also transfer during the period 1 October 2011 1 Oct 2016. Records of these assets may not yet be shown on the existing mains record drawing(s). If you encounter any of these assets you must inform Yorkshire Water Services Ltd (YWS).
- 19. Please note that the information supplied on the enclosed plans is reproduced from Ordnance Survey material with the permission of the Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office, © Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings. Licence Number 1000019559.
- 20. This information is for guidance only and the position and depth of any YW apparatus is approximate only. Likewise, the nature and condition of any YW apparatus cannot be guaranteed. YW has no responsibility for recording the locations of privately owned apparatus. As of 1 October 2011, there may be some lateral drains and/or public sewers which are not documented on YW records but may still be present. For the avoidance of doubt, this information is not a substitute for appropriate professional and/or legal advice. YW accepts no responsibility for any inaccuracy or omissions in this information. The actual position of YW apparatus must be determined on site by excavating trail holes by hand. YW requires a minimum of two working days' written notice of the intention to excavate any trial holes before any excavation can be undertaken. If there are any queries in this respect please contact Yorkshire Water on 0845 124 24.



Property Identfier




Sewer Legend







Water Legend











SafeMove A part of YorkshireWater



APPENDIX F

Source Control Attenuation Calculations



Mason Clark Associates Ltd						
Church House						
44 Newland Park						
Kingston upon Hull, HU5 2DW		Micro				
Date 15/10/2020 12:10	Designed by brandon.waddington	Drainage				
File 2020.10.15 - Storage Re	Checked by	Dialilade				
Innovyze	Source Control 2019.1					

Summary of Results for 30 year Return Period

Half Drain Time : 26 minutes.

	Storm	Max	Max	Max	Max	Max	Max	Status
	Event	Level	Depth	Infiltration	Control	Σ Outflow	Volume	
			(m)	(1/s)	(1/s)	(1/s)	(m³)	
	min Summer			0.0	1.7	1.7		O K
30	min Summer	13.124	0.724	0.0	1.9	1.9	4.5	O K
60	min Summer	13.169	0.769	0.0	2.0	2.0	4.7	O K
120	min Summer	13.127	0.727	0.0	1.9	1.9	4.5	O K
180	min Summer	13.059	0.659	0.0	1.8	1.8	4.1	O K
240	min Summer	12.992	0.592	0.0	1.7	1.7	3.7	O K
360	min Summer	12.883	0.483	0.0	1.6	1.6	3.0	O K
480	min Summer	12.803	0.403	0.0	1.4	1.4	2.5	O K
600	min Summer	12.742	0.342	0.0	1.3	1.3	2.1	O K
720	min Summer	12.694	0.294	0.0	1.2	1.2	1.8	O K
960	min Summer	12.626	0.226	0.0	1.0	1.0	1.4	O K
1440	min Summer	12.549	0.149	0.0	0.8	0.8	0.9	O K
2160	min Summer	12.495	0.095	0.0	0.6	0.6	0.6	O K
2880	min Summer	12.469	0.069	0.0	0.5	0.5	0.4	O K
4320	min Summer	12.446	0.046	0.0	0.4	0.4	0.3	O K
5760	min Summer	12.440	0.040	0.0	0.3	0.3	0.2	O K
7200	min Summer	12.435	0.035	0.0	0.3	0.3	0.2	O K
8640	min Summer	12.432	0.032	0.0	0.2	0.2	0.2	O K
10080	min Summer	12.430	0.030	0.0	0.2	0.2	0.2	O K
15	min Winter	13.075	0.675	0.0	1.8	1.8	4.2	ОК

	Stor Even		Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)
15	min	Summer	68.461	0.0	5.0	21
30	min	Summer	45.456	0.0	6.6	31
60	min	Summer	28.921	0.0	8.5	48
120	min	Summer	17.873	0.0	10.5	80
180	min	Summer	13.341	0.0	11.7	114
240	min	Summer	10.790	0.0	12.6	146
360	min	Summer	7.971	0.0	14.0	208
480	min	Summer	6.428	0.0	15.0	268
600	min	Summer	5.437	0.0	15.9	328
720	min	Summer	4.740	0.0	16.6	388
960	min	Summer	3.814	0.0	17.8	508
1440	min	Summer	2.805	0.0	19.7	744
2160	min	Summer	2.060	0.0	21.7	1104
2880	min	Summer	1.653	0.0	23.2	1468
4320	min	Summer	1.211	0.0	25.5	2156
5760	min	Summer	0.971	0.0	27.2	2872
7200	min	Summer	0.817	0.0	28.7	3552
8640	min	Summer	0.710	0.0	29.9	4400
10080	min	Summer	0.630	0.0	31.0	5008
15	min	Winter	68.461	0.0	5.6	21

©1982-2019 Innovyze

Mason Clark Associates Ltd							
Church House							
44 Newland Park							
Kingston upon Hull, HU5 2DW		Micro					
Date 15/10/2020 12:10	Designed by brandon.waddington	Drainage					
File 2020.10.15 - Storage Re	Checked by	Dialitatic					
Innovyze	Source Control 2019.1						

Summary of Results for 30 year Return Period

Storm Event		Max Level (m)	Max Depth (m)	Max Infiltration (1/s)	Max Control (1/s)	Max Σ Outflow (1/s)	Max Volume (m³)	Status	
30	min 1	Winter	13.316	0.916	0.0	2.2	2.2	5.1	Flood Risk
60	min 1	Winter	13.488	1.088	0.0	2.4	2.4	5.2	Flood Risk
120	min 1	Winter	13.177	0.777	0.0	2.0	2.0	4.8	O K
180	min 1	Winter	13.069	0.669	0.0	1.8	1.8	4.1	O K
240	min 1	Winter	12.972	0.572	0.0	1.7	1.7	3.5	O K
360	min	Winter	12.828	0.428	0.0	1.5	1.5	2.6	O K
480	min 1	Winter	12.732	0.332	0.0	1.3	1.3	2.0	O K
600	min 1	Winter	12.665	0.265	0.0	1.1	1.1	1.6	O K
720	min	Winter	12.617	0.217	0.0	1.0	1.0	1.3	O K
960	min	Winter	12.555	0.155	0.0	0.8	0.8	1.0	O K
1440	min 1	Winter	12.495	0.095	0.0	0.6	0.6	0.6	O K
2160	min 1	Winter	12.460	0.060	0.0	0.5	0.5	0.4	O K
2880	min 1	Winter	12.446	0.046	0.0	0.4	0.4	0.3	O K
4320	min	Winter	12.437	0.037	0.0	0.3	0.3	0.2	O K
5760	min	Winter	12.432	0.032	0.0	0.2	0.2	0.2	O K
7200	min 1	Winter	12.429	0.029	0.0	0.2	0.2	0.2	O K
8640	min 1	Winter	12.427	0.027	0.0	0.2	0.2	0.2	O K
10080	min 1	Winter	12.425	0.025	0.0	0.1	0.1	0.2	O K

	Storm		Rain	Flooded	Discharge	Time-Peak
	Event		(mm/hr)	Volume	Volume	(mins)
				(m³)	(m³)	
20	min Wi	n+ox	45.456	0.0	7.4	31
	min Wi		28.921	0.0	9.5	50
120	min Wi	nter	17.873	0.0	11.7	86
180	min Wi	nter	13.341	0.0	13.1	120
240	min Wi	nter	10.790	0.0	14.1	152
360	min Wi	nter	7.971	0.0	15.7	216
480	min Wi	nter	6.428	0.0	16.8	276
600	min Wi	nter	5.437	0.0	17.8	336
720	min Wi	nter	4.740	0.0	18.6	394
960	min Wi	nter	3.814	0.0	20.0	512
1440	min Wi	nter	2.805	0.0	22.1	744
2160	min Wi	nter	2.060	0.0	24.3	1104
2880	min Wi	nter	1.653	0.0	26.0	1460
4320	min Wi	nter	1.211	0.0	28.6	2192
5760	min Wi	nter	0.971	0.0	30.5	2896
7200	min Wi	nter	0.817	0.0	32.1	3616
8640	min Wi	nter	0.710	0.0	33.5	4336
10080	min Wi	nter	0.630	0.0	34.7	4968

Mason Clark Associates Ltd		Page 3
Church House		
44 Newland Park		
Kingston upon Hull, HU5 2DW		Micro
Date 15/10/2020 12:10	Designed by brandon.waddington	Drainage
File 2020.10.15 - Storage Re	Checked by	Dialilade
Innovyze	Source Control 2019.1	

Rainfall Details

Return Period (years) 30 Cv (Summer) 0.750
Region England and Wales Cv (Winter) 0.840
M5-60 (mm) 18.800 Shortest Storm (mins) 15
Ratio R 0.356 Longest Storm (mins) 10080
Summer Storms Yes Climate Change % +0

Time Area Diagram

Total Area (ha) 0.039

Time	(mins)	Area	Time	(mins)	Area	Time	(mins)	Area
From:	To:	(ha)	From:	To:	(ha)	From:	To:	(ha)
0	4	0.013	4	8	0.013	8	12	0.013

©1982-2019 Innovyze

Mason Clark Associates Ltd							
Church House							
44 Newland Park							
Kingston upon Hull, HU5 2DW		Micro					
Date 15/10/2020 12:10	Designed by brandon.waddington	Drainage					
File 2020.10.15 - Storage Re	Checked by	Dialitatic					
Innovyze	Source Control 2019.1						

Model Details

Storage is Online Cover Level (m) 13.500

Cellular Storage Structure

Depth	(m)	Area	(m²)	Inf.	Area	(m²)	Depth	(m)	Area	(m²)	Inf.	Area	(m²)
0.	000		6.5			0.0	0.	.801		0.0			0.0
0.	800		6.5			0.0							

Orifice Outflow Control

Diameter (m) 0.033 Discharge Coefficient 0.600 Invert Level (m) 12.400

Mason Clark Associates Ltd		Page 1
Church House		
44 Newland Park		
Kingston upon Hull, HU5 2DW		Micro
Date 15/10/2020 12:09	Designed by brandon.waddington	Drainage
File 2020.10.15 - Storage Re	Checked by	Drainage
Innovyze	Source Control 2019.1	

Summary of Results for 100 year Return Period (+30%)

Half Drain Time : 63 minutes.

	Storm		Max	Max	Max	Max	Max	Status
	Event	Level	Depth	Infiltration	Control	Σ Outflow	Volume	
		(m)	(m)	(1/s)	(1/s)	(1/s)	(m³)	
15	min Summe	er 12.871	0.471	0.0	1.5	1.5	7.2	O K
30	min Summe	er 12.999	0.599	0.0	1.7	1.7	9.1	O K
60	min Summe	er 13.081	0.681	0.0	1.9	1.9	10.3	O K
120	min Summe	er 13.107	0.707	0.0	1.9	1.9	10.8	O K
180	min Summe	er 13.089	0.689	0.0	1.9	1.9	10.5	O K
240	min Summe	er 13.056	0.656	0.0	1.8	1.8	10.0	O K
360	min Summe	er 12.988	0.588	0.0	1.7	1.7	8.9	O K
480	min Summe	er 12.928	0.528	0.0	1.6	1.6	8.0	O K
600	min Summe	er 12.877	0.477	0.0	1.5	1.5	7.2	O K
720	min Summe	er 12.832	0.432	0.0	1.5	1.5	6.6	O K
960	min Summe	er 12.761	0.361	0.0	1.3	1.3	5.5	O K
1440	min Summe	er 12.664	0.264	0.0	1.1	1.1	4.0	O K
2160	min Summe	er 12.581	0.181	0.0	0.9	0.9	2.8	O K
2880	min Summe	er 12.534	0.134	0.0	0.8	0.8	2.0	O K
4320	min Summe	er 12.486	0.086	0.0	0.6	0.6	1.3	O K
5760	min Summe	er 12.462	0.062	0.0	0.5	0.5	0.9	O K
7200	min Summe	er 12.449	0.049	0.0	0.4	0.4	0.7	O K
8640	min Summe	er 12.444	0.044	0.0	0.4	0.4	0.7	O K
10080	min Summe	er 12.440	0.040	0.0	0.3	0.3	0.6	O K
15	min Winte	er 12.932	0.532	0.0	1.6	1.6	8.1	ОК

	Stor Even		Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)
15	min	Summer	115.077	0.0	8.4	23
30	min	Summer	77.153	0.0	11.3	34
60	min	Summer	49.388	0.0	14.4	54
120	min	Summer	30.553	0.0	17.9	88
180	min	Summer	22.743	0.0	19.9	122
240	min	Summer	18.321	0.0	21.4	156
360	min	Summer	13.442	0.0	23.6	222
480	min	Summer	10.793	0.0	25.2	288
600	min	Summer	9.095	0.0	26.6	350
720	min	Summer	7.904	0.0	27.7	412
960	min	Summer	6.328	0.0	29.6	536
1440	min	Summer	4.617	0.0	32.4	774
2160	min	Summer	3.362	0.0	35.4	1132
2880	min	Summer	2.681	0.0	37.6	1496
4320	min	Summer	1.945	0.0	41.0	2208
5760	min	Summer	1.547	0.0	43.4	2936
7200	min	Summer	1.294	0.0	45.4	3672
8640	min	Summer	1.119	0.0	47.1	4376
10080	min	Summer	0.990	0.0	48.6	5048
15	min	Winter	115.077	0.0	9.4	23

©1982-2019 Innovyze

Mason Clark Associates Ltd		Page 2
Church House		
44 Newland Park		
Kingston upon Hull, HU5 2DW		Micro
Date 15/10/2020 12:09	Designed by brandon.waddington	Drainage
File 2020.10.15 - Storage Re	Checked by	Dialilade
Innovyze	Source Control 2019.1	

Summary of Results for 100 year Return Period (+30%)

	Storm Event		Max Level (m)	Max Depth (m)	Max Infiltration (1/s)	Max Control (1/s)	Max Σ Outflow (1/s)	Max Volume (m³)	Status
30	min 1	Winter	13.078	0.678	0.0	1.8	1.8	10.3	ОК
60	min 1	Winter	13.174	0.774	0.0	2.0	2.0	11.8	ОК
			13.193		0.0	2.0	2.0	12.1	ОК
180	min 1	Winter	13.158	0.758	0.0	2.0	2.0	11.5	ОК
240	min 1	Winter	13.106	0.706	0.0	1.9	1.9	10.7	O K
360	min 1	Winter	13.004	0.604	0.0	1.7	1.7	9.2	O K
480	min 1	Winter	12.920	0.520	0.0	1.6	1.6	7.9	O K
600	min 1	Winter	12.850	0.450	0.0	1.5	1.5	6.8	O K
720	min 1	Winter	12.792	0.392	0.0	1.4	1.4	6.0	O K
960	min 1	Winter	12.706	0.306	0.0	1.2	1.2	4.6	O K
1440	min 1	Winter	12.601	0.201	0.0	1.0	1.0	3.0	O K
2160	min 1	Winter	12.524	0.124	0.0	0.7	0.7	1.9	O K
2880	min 1	Winter	12.488	0.088	0.0	0.6	0.6	1.3	O K
4320	min 1	Winter	12.455	0.055	0.0	0.4	0.4	0.8	O K
5760	min 1	Winter	12.444	0.044	0.0	0.4	0.4	0.7	O K
7200	min 1	Winter	12.439	0.039	0.0	0.3	0.3	0.6	O K
8640	min	Winter	12.435	0.035	0.0	0.3	0.3	0.5	O K
0800	min 1	Winter	12.433	0.033	0.0	0.2	0.2	0.5	O K

Storm		Rain	Flooded	Discharge	Time-Peak	
	Event		(mm/hr)	Volume	Volume	(mins)
				(m³)	(m³)	
2.0			77 150	0 0	10.0	2.4
		Winter	77.153	0.0	12.6	34
60	min	Winter	49.388	0.0	16.2	58
120	min	Winter	30.553	0.0	20.0	94
180	min	Winter	22.743	0.0	22.3	132
240	min	Winter	18.321	0.0	24.0	168
360	min	Winter	13.442	0.0	26.4	236
480	min	Winter	10.793	0.0	28.3	304
600	min	Winter	9.095	0.0	29.8	368
720	min	Winter	7.904	0.0	31.1	430
960	min	Winter	6.328	0.0	33.2	552
1440	min	Winter	4.617	0.0	36.3	790
2160	min	Winter	3.362	0.0	39.6	1144
2880	min	Winter	2.681	0.0	42.1	1500
4320	min	Winter	1.945	0.0	45.9	2208
5760	min	Winter	1.547	0.0	48.6	2872
7200	min	Winter	1.294	0.0	50.9	3648
8640	min	Winter	1.119	0.0	52.8	4400
10080	min	Winter	0.990	0.0	54.5	5008

Mason Clark Associates Ltd		Page 3
Church House		
44 Newland Park		
Kingston upon Hull, HU5 2DW		Micro
Date 15/10/2020 12:09	Designed by brandon.waddington	Drainage
File 2020.10.15 - Storage Re	Checked by	Dialilade
Innovyze	Source Control 2019.1	

Rainfall Details

Return Period (years) 100 Cv (Summer) 0.750
Region England and Wales Cv (Winter) 0.840
M5-60 (mm) 18.800 Shortest Storm (mins) 15
Ratio R 0.356 Longest Storm (mins) 10080
Summer Storms Yes Climate Change % +30

Time Area Diagram

Total Area (ha) 0.039

Time	(mins)	Area	Time	(mins)	Area	Time	(mins)	Area
From:	To:	(ha)	From:	To:	(ha)	From:	To:	(ha)
0	4	0.013	4	8	0.013	8	12	0.013

©1982-2019 Innovyze

Mason Clark Associates Ltd		Page 4
Church House		
44 Newland Park		
Kingston upon Hull, HU5 2DW		Micro
Date 15/10/2020 12:09	Designed by brandon.waddington	Drainage
File 2020.10.15 - Storage Re	Checked by	Dialilade
Innovvze	Source Control 2019.1	

Model Details

Storage is Online Cover Level (m) 13.500

Cellular Storage Structure

Invert Level (m) 12.400 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000

Depth	(m)	Area	(m²)	Inf.	Area	(m²)	Depth	(m)	Area	(m²)	Inf.	Area	(m²)
0.	000		16.0			0.0	0.	.801		0.0			0.0
0.	800		16.0			0.0							


Orifice Outflow Control


Diameter (m) 0.033 Discharge Coefficient 0.600 Invert Level (m) 12.400

APPENDIX G

Drainage Schematic Layout







Polypropylene Inspection Chamber (Depth 1.2 - 3m)

Polypropylene inspection chambers to BS 7158:2001 Kitemarked. min 450mm Ø to be Osmadrain Universal Inspection Chamber or similar approved Ductile cover and frame to BS EN 124: Class B125 Polypropylene inspection chamber Compacted selected as dug material 100mm bed of selected as dug material (well compacted) or granular material or 150mm concrete


Polypropylene Inspection Chamber (Depth less than 1.2m) in Untrafficked Areas

Scale 1:20

Class B125 in untrafficked areas and Class D400 in trafficked areas Class B engineering bricks set in class 1 mortar concrete collar Shuttering to external cap Restrictor cap 600mm to 350 mm 450mm dia shaft - max 3m installation depth Compacted backfill granular bedding material or selected as-dug - 300mm Deep sump bedding material

Ductile cover and frame to BS EN 124:

Polypropylene Inspection Chamber Catchpit



Typical Rodding Eye Detail

Surface construction BC+300 Min BC+300 Min BC+600 Max BC+600 Max

Drains with Flexible Bed & Surround

Type 'S' Applicable under roads/service yards where drains have more than 1200 cover (if adopted) or more than 900 cover

Applicable under footpaths verges and other non-trafficked areas where drains have more than 900 cover (if adopted) or (if not adopted) more than 600 cover (if not adopted)

construction 150mm reinforced concrete slab. min ST4 Less than with A393 mesh or as agreed with adopting 1200mm 100min Mechanical compaction of main backfill material should not be commenced until there is a total cover depth of 300mm above the crown of the Side fill material to be placed evenly on both sides of pipe taking care to work the material under the lower quadrant of the pipe ensuring the pipe is not lifted. Both Initial backfill sides of the trench should be filled Single size or graded gravel to WIS 4-08-02. See simultaneously to avoid horizontal table A2 for details. (Yorkshire Water prefer movement of the pipe. single size 10mm clean gravel. Formation level -Lower bedding Min.150mm Trench width = PIPEØ + 300mm

Type Z Concrete Protection


Type 'Z'

Applicable under roads/service yards where drains have less than 1200 cover or footpaths verges and other non-trafficked areas where drains have less than 600 cover


Bedding & Trench Details

Key		Granular M	aterial	
BC	Outside diameter of pipe.	Dia. of Drain	Aggregate	
Y	BC/6 OR 100mm under barrels and 50mm min. under sockets whichever is greater (400mm max.)	100mm	10mm single size	
	or BC/4 or 200mm under barrels and 150mm min.	150mm	10mm or 14mm single size or 5-20mm graded.	
Y	under sockets whichever is greater (400mm max.) For trenches in hard material.	225mm-525mm	10mm or 14mm single size or 5-20mm graded.	
	Earthworks outline.	Over 525mm	10, 14, 20 or 40mm	
	Granular material (see table)		single size or 5-20mm graded.	
	Selected clean excavated material to SfHW Clause 505 & 601. Class 1, 2, OR 3.	Note A No mechanical compaction within		
	Granular Type 1 material deposited in layers not exceeding 225mm unconsolidated thickness and then fully compacted.	300mm of crown of pipe. Note B Where drains are laid und refer to engineer for furth.	•	

TRENCH WIDTHS						
DIA OF DRAIN	WIDTH					
100	550					
150	600					
225	700					
300	750					
375	1020					
450	1150					
525	1200					
600	1350					
675	1450					
750	1500					
825	1600					
900	1900					
975	2000					
1050	2300					
1200	2300					
Over 1200	Dia+1000					



Scale 1:20



Typical Cellular Storage Section Detail

Drainage Notes

1. All private drainage works are to be constructed in accordance with the relevant provisions of BS EN 752 including by reference BS 8301, Building regulations part H and Sewers for Adoption 6th edition.

1. This drawing is subject to copyright and must not be reproduced, stored or transmitted in any form without

2. This drawing is not to be scaled. All dimensions are to be

3. This drawing is to be read in conjunction with all the

4. All dimensions are in millimetres and all levels are in

5. All work shall be carried out in accordance with Local

6. Mason Clark Associates are not responsible fo

Authority, Statutory Authority and Health & Safety

determining the appropriate fire period, fire boundary

conditions or the associated design of fire protection o

inherent fire resistance to any elements of structure,

including all frames, posts, beams, joists, roof members

and secondary structural elements such as lintels. Refer

to the Architect or Project Manager for this information.

relevant contract drawings and specifications.

checked on site by the contractor. Any discrepancies are

to be notified to Mason Clark Associates. Obtain

prior permission from Mason Clark Associates.


instructions prior to works commencing.

metres AOD unless noted otherwise.

- 2. The Contractor MUST confirm invert levels of existing points of connection prior to commencement of drainage
- 3. Manhole invert levels relate to the downstream pipe. Pipes at manholes to be laid soffit to soffit level.
- 4. Unless otherwise shown, foul pipes to be 100mm Ø laid at 1 in 40 minimum gradient unless one w.c. connected
- 5. Unless otherwise shown surface water pipes to be 150mm Ø laid at 1 in 100 minimum gradient.

where gradient may be 1 in 80 minimum.

- 6. Where cover to top of pipe barrel is less than 900mm in lightly trafficked areas and 600mm in non trafficked areas, pipe to have minimum 150mm ST4 concrete
- 7. Where cover to pipe barrel located beneath highways is less than 1200mm, pipes are to be protected with concrete surround (bed type Z) Grade C20 in accordance with sewers for adoption 6th edition, table
- 8. Manhole cover levels are where not shown are to be confirmed at later stage. Covers are to be fixed to a profile corresponding to the surrounding pavement surface and may be adjusted to suit actual site levels.
- 9. All pipework up to 300mm Ø to be standard strength vitrified clay to BS EN 295 (min crushing strength 40KN/m) or plastic to BS 4660:2000 and BS EN 1401-1:1998 and shall comply with the requirements of Sewers for Adoption 6th Edition.
- 10. Bedding to all pipework to be Class S granular bed & surround in accordance with BS882 or Class Z (see manhole schedule and/or details drawing).
- 11. All backfill above gravel surround in drainage trenches and under building slabs to be Type 1 stone compacted in layers not exceeding 225mm thick.
- 12. Manholes to be precast concrete to BS EN1917: 2002, Type B, in accordance with the requirements of Sewers for Adoption, 6th Edition unless noted otherwise.
- 13. Inspection chambers to be polypropylene, 450mm diameter, Hepworth range or similar & approved. Opening restricted to max 350mm where depth of chamber exceeds 1.2m.
- 14. All manholes covers and gully gratings located in trafficked areas to be ductile iron class D400. Covers located in non trafficked areas to be min class B125 unless noted otherwise on the drainage layout or manhole schedule.
- 15. Any external recessed cover required or internal manhole covers to be specified by the Architect.
- 16. Proprietary attenuation systems, cellular soakaways and petrol/oil interceptors to be installed in accordance with the manufacturers details and recommendations. including bedding and surround, membranes, protection and backfill requirements.
- 17. Position and details of rainwater pipes, and foul connections to be confirmed by Architect.
- 18. For above ground and internal drainage, vents, fittings and access points refer to Architects and/or M&E details.
- 19. Cover levels of private drainage chambers may be adjusted to suit actual site levels.
- 20. The contractor is responsible for identifying and locating all existing services and ensuring that the levels do not conflict with the proposed drainage system. If there are any such conflicts then the Engineer must be made aware immediately.
- 21. All existing redundant drainage systems are to be abandoned and grubbed up including redundant manholes and pipework. The voids are to be backfilled with as dug material or suitable fill material and compacted in layers.
- 22. Any live sewer connections found in any sewers that are to be abandoned are to be picked up and diverted.
- 23. The Contractor shall undertake a CCTV survey of the as constructed site drainage system on completion of the works. A copy shall be made available to Mason Clark Associates.



Drawing No: 18865-L-DR-201 Rev: P1



Hull (Registered Office)

Church House 44 Newland Park Hull HU5 2DW 01482 345797

www.masonclark.co.uk

consultants@masonclark.co.uk

Leeds

Unit E

Millshaw Business Living

Global Avenue Leeds LS11 8PR 0113 2779542

www.masonclark.co.uk

York

STRUCTURAL ENGINEERING

Heavy industrial development

Education and healthcare facilities

Access and maintenance gantries

Modular building design

Site and soils investigation

Sulphate attack specialists Confined spaces assessments

Blast design

Feasibility studies for development sites

Subsidence management and resolution

Temporary works design and specification

Partnership House Monks Cross Drive

Monks Cross

York YO32 9GZ

01904 438005

Residential and commercial building structures

Building Regulations and Planning Applications

www.masonclark.co.uk

CIVIL ENGINEERING

Bridge design, maintenance and construction

Wharfs, jetties and marine structures Highway design and maintenance

Retaining wall and slope stability solutions

Land remediation advice

Road and sewer design to adoptable standards

Section 38 and 104 Agreements Sewer requisitions and diversions Section 98 and 185 Agreements

Flood Risk Assessments

Coastal erosion flood breach analysis

Flood risk management / prevention schemes

Underground drainage design

Stormwater attenuation

PROJECT MANAGEMENT

SUDS

Ponds, lakes and balancing ponds

CONSERVATION ENGINEERING

Engineer Accredited in Building Conservation CARE

Registered Engineer

Heritage and conservation engineering

Listed Building refurbishment Historic Parks and Gardens Scheduled Ancient Monuments

Monitoring and investigations

Liaison with Local Conservation Officers

Buildings at Risk and Managed Ruins

BUILDING SURVEYING SERVICES

Design, Remedial Repair / Improvement Schemes

QUANTITY SURVEYING & CONTRACT ADVICE

Contract Administration

Building Surveys

CDM SERVICES

Professional Opinion Reports

Condition Surveys & Schedules of Condition

Measured Surveys Dilapidation Claims

Party Wall etc. Act Representation

Disabled Adaptations

Civil & Structural engineering disputes

Project Disputes

Health and Safety Regulations

EXPERT WITNESS SERVICES

3D LASER SCANNING AND DATA CAPTURE

Latest Generation 3D Laser Scanning

Measured Building Surveys Topographical Surveys

Monitoring Surveys

3D modelling (Revit, CAD, Inventor, Solidworks)

M & E Modelling

Volumetric / Level analysis

Scan to BIM

Scan data cloud hosting

Hi-Def HDR photographic surveys