

APPROVED


(refer to decision notice for conditions)

BEFORE STARTING WORK IT SHOULD BE UNDERSTOOD THAT THIS PLANNING PERMISSION DOES NOT CARRY WITH IT ANY PERMISSION WHICH MAY BE NECESSARY UNDER THE BUILDING(SCOTLAND) ACTS.

©This drawing and Design are Copyright
Do not scale from the Drawing
Check all dimensions on site

Rainwater pipes to be trapped and connected to new 100mm diam underground drain with rodding eyes at the end of the run and connected into the existing underground drain. Drainage at gradient to connect with existing and be bedded in appropriately.
100mm land drain with silt trap to be laid along rear of garage and connected into existing.
Gully fitted centrally to external hardstanding at garage. 50mm falls into gully from perimeter of slab and gully connected via new silt trap to existing drainage.
New inspection chamber to be fitted at junction of new drains and existing.

NOTES
Existing dilapidated garage and wash-house demolished with foundations grubbed up. New garage located such that new east (rear) and south (side) walls align with existing.



BLOCK PLAN 1:500
0 10 20 30 40

LOCATION PLAN 1:2500
(TITLE PLAN: REN 152
OS LICENCE: 100041182)

0 10 20 30 40 60 80 100 120 m

A SCALE AS REFERRED 5/15

glgLang@rchitecture
DESIGN-PLANNING-INTERIORS
SUSTAINABILITY-CONSERVATION
Beech Studio, 10 Berryhill Road,
Glasgow, G46 7NJ
Tel: 0141 621 2050
E: mail@glgdesign.com

JOB
**HEATHMOUNT
KILMACOLM
ALTERATIONS**

DRAWING
**LOCATION PLAN &
BLOCK PLAN**

Scale: 1:2500 & 1:500 Date: April 2015
Drg No. 15-12/01 A