

Bickleigh House

Lime plaster specification for internal walls

1211/BIC/DET09

14/12/2020

Specification - Lath walls

Primary coat

The primary coat is a haired slaked lime render pushed through to the laths to give adequate key. It is applied 10-12mm thickness and scarified with a scratch coat to give adequate key.

Second coat

The second coat is coarse slaked lime render applied at 6-8mm, flattened with a wooden float.

Third coat

The third coat is made up of a 2mm coat of 3:2 fine lime plaster. This is then covered with a 1mm coat of fine lime plaster and polished smooth.

Specification 3 parts 0-4mm sand, 1 part slaked lime putty and 2kg horse hair per ton