

EXISTING TREE PLANTING TO PATHWAY/TRAIL PROVIDING SCREENING TO PROPOSED DEVELOPMENT WORKS

2Nr *Corylus avellana*

225Nr *Carpinus betulus* 3per m.
MAINTAIN AS BOUNDARY HEDGE.

3Nr *Viburnum lantana*

60Nr Shrub / Scrub Mix

2Nr Ac

50Nr Shrub / Scrub mix

2Nr Bu

60Nr Shrub / Scrub Mix

2Nr Ca

50Nr Shrub / Scrub MIX

1Nr TP

4Nr Bu

60Nr Shrub / Scrub MIX

2Nr Ac

2Nr TP

EARTH MOUND

1Nr Cm

150Nr Shrub / Scrub mix

50Nr Shrub / Scrub MIX

150Nr Shrub / Scrub Mix

Plant Schedule

Trees / Shrubs			No' Req.
Ac - Acer campestre	10 - 12 cm	RB	4
Bu - Betula utilis	10 - 12 cm	RB	6
Ca - Corylus avellana	10 - 12 cm	RB	2
Cm - Crataegus monogyna	10 - 12 cm	RB	1
Tp - Thuja plicata	1.5 - 1.8 m	RB	3
<i>Corylus avellana</i>	1.2 - 1.5 m	15 ltr	2
<i>Pyracantha 'Orange Glow'</i>	60 - 80 cm	3 ltr	50
<i>Pyracantha 'Saphyr Red'</i>	60 - 80 cm	3 ltr	50
<i>Pyracantha 'Saphyr Yellow'</i>	60 - 80 cm	3 ltr	50
<i>Viburnum lantana</i>	1.2 - 1.5 m	15 ltr	3
Boundary Hedge: 3 plants per m			
<i>Carpinus betulus</i>	1+2 / 60 - 80	BR	225
Shrub / Scrub Mix: 630m2 planted at 1m c/s.			600
<i>Comus sanguinea</i>	30%	1+1 / 40-60	180
<i>Corylus avellana</i>	20%	1+1 / 40-60	120
<i>Griselinia littoralis</i>	10%	3 ltr / 40-60	60
<i>Ulex europaeus</i>	10%	2 ltr / 40-60	60
<i>Viburnum lantana</i>	20%	1+1 / 40-60	120
<i>Viburnum tinus</i>	10%	2 ltr / 40-60	60

ALLOW FOR RABBIT GUARDS TO ALL PLANTING

EXCAVATED SOIL REUSED TO FORM MOUNDING TO RAISE LEVELS & ASSIST IN SCREENING. SOW WITH WILDFLOWER MIX

ALL GRASSED AREAS ALLOWED TO NATURALISE & DEVELOP MORE VARIED, NATIVE FLORA TO ENHANCE ECOLOGICAL VALUES.

150Nr Mixed *Pyracantha* spp. planted at 1 per m²



COMPANY OF GARDENERS

Rowlings Farm - Glamping Pods
Planting Details.

18 January 2021 Dwg No: 252 / 003

Steve Seed, BA (Hons), Dip LA (Dist), Grad Dip UD, CMLL
South Street, Cottingham, HU16 4AT.
info@companyofgardeners.co.uk