



Specification for two lane enclosed 'tp365' system

Overall two lane dimensions: 33m x 7.3m
'tp1' premium grade wilton woven synthetic playing surface carpets
per lane: 27m x 3.65m green with blue borders
Optional: single tone green, NPC with green or blue borders
Optional: training aid - contrasting stump lines
'tp5' premium grade tufted run up carpet per lane: 6m x 3.65m single
tone green

Shock pads: per lane

'tp2' batting area: pace modifying shock pads for the pitching area
19m x 3.4m
'tp3' bowling area and run-up: load absorbing shock pad 14m x 3.6m

Steelwork system dimensions: per lane

Height: 4m
Lane length: 25.55m
Overall length 33m
Width: 3.6 - 3.65m
48mm diameter galvanised steel tubes set in a 52mm diameter socket.
Optional: powder coated steelwork green or black
Optional: Pedestrian gate with latch

Netting systems

25.55m x 4m HD Protection tunnels: exclusive total-play design one
seamless piece of total-play's 'HD' netting secured with PVC
encapsulated tension wire
6m x 4m HD panel sidewalls

4m high white bowler netting
Single batting curtains (white mesh) 2m x 7.3m
Optional: green or black netting
Optional: additional 'double' or 'wrap' batting curtains
Optional: total-play's 'HD' netting in walled panel design
Optional: protection skirt in green or black (PVC): protects the bottom section of netting, either
500m or 1m high.

Security fence

All systems can be built with perimeter security fencing and gates.
design options include gate width, fence height, colour and type of
perimeter safety path.

