

Date 31/07/12

Network Technical Data Sheet – Avipoint

Product	P14	P20	P32	G20	P14	P20	P32	G20
Product Code	AVI110	AVI120	AVI130	AVI140	AVI116	AVI126	AVI136	AVI146
Base Material	UV protected clear Polycarbonate							
Wire Material	High Tensile Austenitic Stainless Steel BS 1.4310 according to BSEN10270-3 2001, AISI 301, UNS S30100 301/302 Stainless Steel Spring Temper				High Tensile Austenitic Stainless Steel BS 1.4401 according to BSEN10270-3 2001, AISI 316, UNS S31600 316 Stainless Steel Spring Temper			
Wire Gauge	1.42 mm ± 0.02mm							
Wire Tensile Strength	Minimum 1500 N/mm ²							
Strip Length	333 mm							
Spike Height (Inner Spikes)	115mm	128 mm	139mm	166mm	115mm	128 mm	139mm	166mm
Spike Tip Spread at Top	50mm	140mm	200mm	175mm	50mm	140mm	200mm	175mm
Strip Weight	34g	54g	89g	64mm	34g	54g	89g	64mm
Base Width	9-20mm	15-45mm	15-45mm	15-45mm	9-20mm	15-45mm	15-45mm	15-45mm
Snap Line Interval	48mm	33mm	21mm	33mm	48mm	33mm	21mm	33mm