



# BARN 60 METRES EAST OF ONEHOUSE HALL

## Overview

Heritage Category:  
Listed Building

Grade:  
II

List Entry Number:  
1198316

Date first listed:  
24-Jun-1986

Statutory Address:  
BARN 60 METRES EAST OF ONEHOUSE HALL, LOWER ROAD

# Map



© Crown Copyright and database right 2021. All rights reserved. Ordnance Survey Licence number 100024900.

© British Crown and SeaZone Solutions Limited 2021. All rights reserved. Licence number 102006.006.

Use of this data is subject to **Terms and Conditions**

(<https://historicengland.org.uk/terms/website-terms-conditions/>).

The above map is for quick reference purposes only and may not be to scale. For a copy of the full scale map, please see the attached PDF - **1198316.pdf**

([http://mapservices.HistoricEngland.org.uk/printwebservicehle/StatutoryPrint.svc/184027/HLE\\_A4L\\_Grade|HLE\\_A3L\\_Grade.pdf](http://mapservices.HistoricEngland.org.uk/printwebservicehle/StatutoryPrint.svc/184027/HLE_A4L_Grade|HLE_A3L_Grade.pdf))

The PDF will be generated from our live systems and may take a few minutes to download depending on how busy our servers are. We apologise for this delay.

This copy shows the entry on 19-Feb-2021 at 14:11:30.

## Location

Statutory Address:

BARN 60 METRES EAST OF ONEHOUSE HALL, LOWER ROAD

The building or site itself may lie within the boundary of more than one authority.

County:

Suffolk

District:

Mid Suffolk (District Authority)

Parish:  
Onehouse

National Grid Reference:  
TM 01800 59187

## Details

ONEHOUSE LOWER ROAD TM 05 NW

2/148 Barn, 60m east of Onehouse Hall 24.6.86

GV II

Barn, early C16. Originally of 7 long bays; major remodelling of bays 6 and 7 at west end c.1600; a 2-bay neat-house (cow shed) or stable added to west in late C17. Timber-framed and weatherboarded. Aluminium sheeted roof, formerly thatched. Two sets of boarded barn doors, renewed late C20, in bays 3 and 6 (south side). The C16 structure is of good quality: massive close studding with long tension bracing, and a middle rail in the north wall only. Tie-beam braces all replaced by C19 knees. Altered, coupled-rafter roof. Circa 1600, extra trusses and a new windbraced clasped purlin roof were provided in bays 5,6 and 7, and the original roof, formerly hipped, was remodelled over the other bays. The neat-house has close studding and once had an upper floor; C20 casements.

Listing NGR: TM0180059187

## Legacy

The contents of this record have been generated from a legacy data system.

Legacy System number:

279923

Legacy System:

LBS

## Legal

This building is listed under the Planning (Listed Buildings and Conservation Areas) Act 1990 as amended for its special architectural or historic interest.

End of official listing

Don't have an account? Register [here](https://account.historicengland.org.uk/sign-in) (<https://account.historicengland.org.uk/sign-in>)