

Conservation Roof Windows

For traditional buildings



ON WINDOWS
AND FLASHINGS



CONSERVATION ROOF WINDOWS

When planning details that a window of traditional appearance is required, Conservation Roof Windows should be considered. All our Conservation Roof Windows have the technically superior features of a VELUX Roof Window in a traditional black conservation style. And, no matter what type of glazing you choose, you'll have the added benefit of energy efficiency and all the features you'd expect.

- Available in either Centre-Pivot or Top-Hung.
- Black external profiles and glazing bar. RAL colour 9005.
- Recessed installation for slate and tiled roofs.
- Other sizes and glazing options available – please contact VELUX for more details.
- Top-Hung Windows listed below are suitable for emergency escape.

CENTRE-PIVOT



Recessed into slate	20°–90°
Plain tiles	25°–90°
Tiles	15°–90°
Recessed into tiles	20°–90°

TOP-HUNG



Recessed into slate	20°–55°
Plain tiles	25°–55°
Tiles	15°–55°
Recessed into tiles	20°–55°

For roof pitches of 55°–75°, please specify special springs when ordering.



Flashing,
Insulation Collar
and Underfelt
Collar included in
all Conservation
Packages

Conservation Roof Windows Prices excluding VAT from 1st Feb 2014

(Other sizes of Conservation Roof Windows are available subject to lead times.)

External frame size (nominal w x h) cm

Code	Description	CK04	CK06	FK06	MK06	MK08	UK04
------	-------------	------	------	------	------	------	------

Packages include: GGL Centre-Pivot or GPL Top-Hung Roof Window with glazing bar, flashing, Insulation Collar (BDX) and Underfelt Collar (BFX).

Centre-Pivot Roof Windows, pine. Toughened outer pane (–50). U-value 1.3 W/m²K.

GGL SD5N1	GGL 3550 Roof Window + EDN Recessed Flashing for slate up to 8mm thick (min 20° roof pitch)	£416	£432	£468	£531	£571	£690
GGL SD5P1	GGL 3550 Roof Window + EDP Flashing for plain tiles up to 15mm thick (min 25° roof pitch)	£375	£391	£422	£484	£520	£633
GGL SD5W1	GGL 3550 Roof Window + EDW Flashing for tiles up to 120mm in profile (min 15° roof pitch)	£391	£407	£440	£502	£538	£657
GGL SD5J1	GGL 3550 Roof Window + EDJ Recessed Flashing for tiles up to 90mm in profile (min 20° roof pitch)	£416	£432	£468	£531	£571	£690

Top-Hung Roof Windows, pine. Toughened outer pane (–50). Suitable for emergency escape. U-value 1.3 W/m²K.

GPL SD5N1	GPL 3550 Roof Window + EDN Recessed Flashing for slate up to 8mm thick (min 20° roof pitch)	-	-	-	-	£687	-
GPL SD5P1	GPL 3550 Roof Window + EDP Flashing for plain tiles up to 15mm thick (min 25° roof pitch)	-	-	-	-	£636	-
GPL SD5W1	GPL 3550 Roof Window + EDW Flashing for tiles up to 120mm in profile (min 15° roof pitch)	-	-	-	-	£654	-
GPL SD5J1	GPL 3550 Roof Window + EDJ Recessed Flashing for tiles up to 90mm in profile (min 20° roof pitch)	-	-	-	-	£687	-

Optional glazing bars for standard windows	CK02	CK04	MK04	UK04	CK06	FK06	MK06	SK06	MK08	PK08	UK08	PK10
2 glazing bars for SK06, UK04 & UK08	ZGA WK02 0024 £20	ZGA WK04 0024 £22			ZGA WK06 0024 £24				ZGA WK08 0024 £26		ZGA WK10 0024 £28	