

Project: _____

Location _____

Date: _____



LIGHTWAY 5 - OUTDOOR OPAL SHORT ROTATION ARM

The Lightway 5 outdoor opal is developed for homogenous lighting in harsh environments. This IP65 element bene fits from a wide variety of outputs. The diffuser offers powerful lighting and excellent light transmission with high diffusion.

- Superior optical transmission with no visible LED hotspots.
- Wide, even levels of illumination.
- High angle distribution to illuminate vertical & horizontal surfaces.
- Great color mixing capability.
- Integrates with any architecture.



Product Code: L5 O S1 X AO XX PR L5 D 65 BS 90 BI

Luminaire

Product Type:	Ambient
Application:	Opal Diffuser
Body Material:	Extruded aluminium
Body finish:	Black Smooth

Installation

Environment:	Outdoor
Surface Type:	Concrete, Metal, Stone, Wood
Mounting:	Short rotation arm
Overall Dimensions with Accessories (mm):	902 * 80 * 107
Weight (Kg):	3

Light Source

Light Source:	Mid Power LED
Led Load:	42 W/m
Connected Load (typical):	49.41 W/m
Lifetime:	50000 Hrs

Optics

Beam Angle:	N/A
Optic Type:	PMMA Opal Lens
Surface diffuser:	Acrylic Opal Diffusing Lens (Purple)

Electrical equipment

Control Gear:	Built-in constant current Driver
Mains Voltage:	220-240 VAC 50/60 Hz
Control Gear Efficacy:	> 85%
Control:	Built-in driver, DALI

