



1. **Dedband Walls:** Carefully remove and rub back non-original plaster marked red to reveal original brick.
2. Carefully strip out non-original block partition walls marked in red
3. Part of the internal and perimeter walls have a ceramic tiled finish. These walls are to be removed and replaced with brickwork cleaned and where necessary protected by internal steel frame lining
4. Carefully strip-out non-original non-structural block wall
5. **Historic Windows:** Carefully, ease and overhaul all non-original windows and repair with subject dense only.
6. **Dedband Doors:** Carefully ease and overhaul retained non-original doors
7. Non-original and Non-tinted Ceiling: Suspended ceiling are present to areas indicated red. They are non-original of low quality, asbestos containing material and with no historic or design value. It is proposed to remove them in all places

Revisions	Comments	Date
Client		12/11/2000
M:One Studios		
Project North Block, Chatham Mill		
Application Nos - 12875/FO/2000 & 12875/O/2000		
	Drawn PJK	
	Approved ??	
	Scale 1:100@A3	
Drawing title As Existing Floor Plan	Job No. 10059	
	Dwg No. 1 (v2)	