ARBORICULTURAL REPORT

CONTENTS:

- 1. INTRODUCTION 2. ARBORICULTURAL APPRAISAL
- 3. PROPOSED TREE WORK
- 4. ARBORICULTURAL IMPLICATIONS & IMPACT ASSESSMENT 5. TREE PROTECTION

1. INTRODUCTION

Background: LSDP were appointed to prepare an Arboricultural Survey & Report to inform the design process and satisfy Local Authority requirements in respect to the proposed infilling on a redundant pond / drainage basin and formation of a meadow landscape area on land adjacent to Bury Road, Hall Farm, Thurlow. The report is based on survey information collected in August 2020.

The Site: The site comprises a redundant pond / drainage basin, which is bordered to the north by Bury Road; to the east, by a woodland belt and adjacent paddocks; to the south, by domestic curtilage and paddocks; and to the west, by an access track. The basin remains dry for most of the year, but becomes partially flooded periodically during wet periods. The base of the basin is covered with a layer of silt and stagnant mud, with some scrub encroachment around the dryer parts at the eastern end.

2. ARBORICULTURAL APPRAISAL

Generally: The sides of the basin have been left unmanaged and now host stands of naturally generated trees, predominantly sycamore and ash, together with a few larger trees including beech, lime, horse chestnut and white willow. These larger trees appear to have been planted and predate the naturally generated trees. A mixed species hedgerow runs along the top of the northern bank, bordering Bury Road; the hedgerow continues beyond the site to the east; it is managed at a low height, but is sparse in places, due to shading from the naturally generated trees.

The hedgerow and the larger trees are traditional landscape elements that relate to the estate landscape surroundings and regarding BS5837:2012, should be considered as 'A2/3' or 'B2/3' Category (High, or moderate landscape / cultural value). The naturally generated sycamore and ash are of no special arboricultural, landscape, or cultural merit and should be considered as 'C2' category (low landscape value).

3. PROPOSED TREE WORK

It is proposed to clear most of the naturally generated trees (predominantly sycamore and ash) from the banks of the basin, so that the larger, older trees can remain as individual specimens, allowing the area to have a more 'managed' appearance, in keeping with the Estate Landscape surroundings.

4. ARBORICULTURAL IMPLICATIONS & IMPACT ASSESSMENT

Development Proposal: It is proposed to infill the basin with imported soil and to form a wildflower meadow area, together with a wildlife pond and watercourse to fulfil drainage requirements. The overall intentions are to augment local landscape character by changing the appearance of the area from overgrown / unkempt to managed estate land, in keeping with the estate landscape surroundings. An additional objective is to enhance the ecological value of the area by providing a range of new grassland and wetland habitat around the retained specimen trees.

Impact of Groundwork on Tree Roots: Most of the northern and eastern banks of the basin will be retained and will form the northern bank of the proposed watercourse and northern / eastern bank of the proposed pond. Parts of the southern bank will also be retained around the bases of trees to be retained. The remainder of the basin will be filled. The base of the basin is covered with silt and stagnant mud and being seasonally inundated, results in anaerobic conditions, which are not ideal for root growth. It is considered that filling the basin with soil material will not have a significant adverse impact on the rooting environment of the adjacent trees, particulalry where the sections of bank upon which they are located are left uncovered; i'e' allowing gaseous exchange to occur at the existing surface level. Elsewhere, where filling is required that will cover parts of the bank adjacent to retained trees, a filter layer of inert stone or rubble material shall be laid over the bank beneath the fill material; the filter layer shall extend to the top of the fill material and separated from it with a geomembrane. This will allow gaseous exchange to continue and ensure the fill material does not have a significant adverse impact on the existing rooting environment.

The proposed watercourse will require some limited excavation toward the western end of the existing basin and will also require ground modelling. Excavation shall be carried out by hand and infilling shall be done by machine, positioned away from the trees. All such works shall be carried out under the supervision of an arboriculturist.

5. TREE PROTECTION

Generally

Before any machinery or materials are bought onto site Protective Barriers shall be installed where shown on the drawing. These shall be retained whilst the basin is filled and shall only be removed during supervised works. The timing of which shall be agreed in consultation with the ground works contractor and arboriculturist, prior to commencement of works.

All works shall be carried out in accordance with a site specific arboricultral method statement, which shall also be completed by the arboriculturist, in consultation with the groundwork contractor, prior to commencement of works.



Lime (T15 - to be retained)

 \sim White willow (T77 - to be retained)



Sy

Sy

 $\sim\sim\sim\sim$

1.6m Ht. Mixed Hedge

White willow(T40 - to be retained)

Group of sycamore and Norway maple on NW corner of site (T0 & 11 to be retained)

Pond bank to be cleared of naturally generated / suppressed trees, predominantly sycamore, Norway maple and ash + occasional birch and horse chestnut (T36-39, 75,76 & 78-82)

40 41 V

1.8m Ht. Panel (Hurdle

BURY ROAD

..3m Ht. Post & Rail Fence

(V2

×RGL 84.40



OF



-Hedge to be retained







Basin to be filled with imported soil; finished level to match existing adjacent areas Proposed ditch bed formed with imported soil and by localised excavation. Fill material to be deposited by machine sited outside of area (to prevent compcation). Excavation work to be carried out by hand (To minimise root disturbance)





	Tree Schedule						
No.	Species	Spread	Diameter	Height	Bole	Remark	
1	Oak	19.00	1.30	25.00	Single Bole		
2	Maple	13.00	0.60	20.00	Single Bole		
3	Acer	8.00	0.20	12.00	Single Bole		
4	Acer	8.00	0.20	12.00	Single Bole		
5	Acer	8.00	0.50	12.00	Multi Bole		
6	Acer	8.00	0.30	8.00	Multi Bole		
/	Ash	12.00	0.40	15.00	Single Bole		
8	Acer	14.00	1.00	15.00			
9	Asn	8.00	0.40	19.00	Single Bole		
10	Acer	14.00	1.00	20.00	Single Bole		
12	Beech	15.00	0.75	16.00	Single Bole		
13	Beech	13.00	0.45	13.00	Single Bole		
14	Ash	5.50	0.40	7.00	Single Bole		
15	Lime	10.00	0.70	12.00	Single Bole		
16	Acer	11.00	0.60	8.00	Multi Bole		
17	Acer	10.00	0.45	12.00	Single Bole		
18	Ash	10.00	0.35	14.00	Single Bole		
19	Beech	18.00	1.10	20.00	Single Bole		
20	Acer	12.00	0.80	12.00	Multi Bole		
21	Acer	8.00	0.50	10.00	Multi Bole		
22	Acer	12.00	0.80	14.00	Multi Bole		
23	Ash	7.00	0.30	15.00	Single Bole		
24	Acer	14.00	0.60	15.00	Single Bole		
20	Acei	5.00	0.50	13.00	Single Bole		
20	Acer	14 00	0.00	14 00	Multi Rolo		
28	Ash	14.00	0.50	15.00	Multi Bole		
29	Acer	7.00	0.35	15.00	Single Bole		
30	Acer	14.00	1.00	15.00	Multi Bole		
31	Acer	12.00	0.60	15.00	Multi Bole		
32	Acer	8.00	0.35	15.00	Single Bole		
33	Acer	6.00	0.25	14.00	Single Bole		
34	Ash	8.00	0.45	18.00	Single Bole		
35	Acer	5.00	0.20	12.00	Single Bole		
36	S.Birch	2.00	0.50	8.00	Single Bole	Dead	
37	Acer	9.00	0.25	8.00	Single Bole		
38	Acer	9.00	0.40	12.00	Single Bole		
39		11.00	0.40	12.00	Single Bole		
40	Willow	12.00	0.70	12.00	Single Bole	Leaning	
42	Willow	12.00	0.70	6.00	Single Bole	Fallen	
43	Acer	8.00	0.25	12.00	Single Bole	1 anorr	
44	Acer	12.00	0.35	14.00	Single Bole		
45	H.Chestnut	8.00	0.50	14.00	Multi Bole		
46	H.Chestnut	15.00	1.00	18.00	Multi Bole		
47	Acer	12.00	0.90	18.00	Multi Bole		
48	Acer	12.00	0.90	18.00	Multi Bole		
49	Acer	10.00	0.40	16.00	Single Bole		
50	Acer	12.00	0.60	12.00	Multi Bole		
51	Asn	14.00	0.55	10.00	Single Bole		
52	Acer	14.00	0.80	15.00			
54	Acer	6.00	0.25	15.00	Single Bole		
55	Ash	6.00	0.30	14.00	Single Bole		
56	Acer	6.00	0.25	14.00	Single Bole		
57	Acer	8.00	0.40	18.00	Single Bole		
58	Acer	14.00	0.90	12.00	Multi Bole		
59	Acer	10.00	0.35	14.00	Single Bole		
60	Ash	8.00	0.35	15.00	Single Bole		
61	Acer	12.00	0.40	15.00	Single Bole		
62	Acer	6.00	0.25	15.00	Single Bole		
63	Rooch	12.00	0.40	15.00	Single Bole		
04 65	Reach	12.00	0.00	15.00	Single Bolo		
66	Ash	15.00	0.75	18.00	Single Bole		
67	Acer	7.00	0.35	15.00	Single Bole		
68	Lime	12.00	0.80	20.00	Single Bole		
69	H.Chestnut	15.00	0.80	20.00	Single Bole		
70	Lime	8.00	0.60	20.00	Single Bole		
71	Acer	8.00	0.35	20.00	Single Bole		
72	Acer	10.00	0.35	20.00	Single Bole		
73	Ash	8.00	0.35	20.00	Single Bole		
74	Ash	7.00	0.25	20.00	Single Bole		
75	H.Chestnut	4.00	0.25	6.00	Single Bole		
/6 		12.00	0.35	15.00	Single Bole		
// 70		7 00	1.40 0.25	20.00 12.00	Single Bolo		
79	Acer	7.00	0.20	10.00	Single Bole		
80	Acer	7.00	0.20	10.00	Single Bole		
81	Ash	8.00	0.30	18.00	Single Bole		
82	Ash	8.00	0.35	18.00	Single Bole		
83	Acer	8.00	0.30	14.00	Single Bole		
84	Ash	12.00	0.60	20.00	Single Bole		
85	Beech	15.00	0.80	20.00	Single Bole		
86	Acer	12.00	0.60	20.00	Single Bole		
87	Ash	12.00	0.50	20.00	Single Bole		
88	Acer	8.00	0.25	18.00	Single Bole		
89		14.00	0.25	18.00	Single Bole		
90	Acor	14.00	0.70	20.00	Single Bole		
31		12.00	0.50	20.00			

dmaab	nonolo

monochrome copy should not be relied upon.

Revisions :

The original of this drawing was produced in colour - a

Land & Sculpture Design Partnership LANDSCAPE ARCHITECTURE · SCULPTURE · ARBORICULTURE

CLIENT: Thurlow Estate SITE : Former Pond - Bury Road, Thurlow DRG : Proposed vegetation clearance DRN BY : GH SCALE : 1:200 @ A0 DATE : February 2021 No : LSDP 1408-011

OCTAGON HOUSE · THE WATER RUN · HITCHAM · IPSWICH · 1P7 7LN T: 01449 740272 · E: LSDP@btinternet.com