

Supa-Trac Temporary Car Parking and Pedestrian Flooring



Supa-Trac ground covering is a unique product, incredibly durable and flexible. Supa-Trac creates a firm surface for walkways, roadways, pitch covers, temporary buildings and structures. Even Heli-pads and Car parks! Edging ramps give easy vehicle access and eliminate trip hazards. Supa-Trac supports vehicles up to 2,500kg* and static weights far greater. Supa-Trac has been used successfully in over 50 major UK sports stadiums & many more throughout the world.



Supa-Trac has been extensively proven in the domestic, construction, and events industries and is used daily by leading military forces, including the British and US. Supa-Trac was developed with the user in mind, making it one of the most straight forward temporary flooring systems available. The “T-peg” design allows rapid deployment, with the minimum of manpower and no specialist tools.



Supa-Trac

Temporary Car Parking and Pedestrian Flooring



Technical Information

Material:	PPCP
Panel size:	920mm x 230mm
Panel area:	0.21 m ²
Panel thickness:	34mm
Panel weight:	2025g (9.7kg per m ²)

Operating conditions

Ambient temperature range: -49 > +50 deg C

Max Gross vehicle weight: 2,500kg*

Max static load: 80,000kg per m²

Suitable surfaces: Turf, soil, sand, gravel, snow, grass..

Operating parameters

Self draining. Inert and non-conductive.

Anti slip surface.

Resistant to solvents and non-corroding.

Resistant to UV damage.

Manually deployed and can be laid in straight runs or pads.

Deployment of 40m² per hour per man.

*Ground Dependent

Cap Trac, The Stables, Loke Farm, Weston Longville, Norfolk, NR9 5LG

Tel. 01603 880448 Email: info@captrac.co.uk

www.captrac.co.uk