

Tag	Species	Ht (m)	Dia (mm)	Max. Crown Radius (m)	Age Class	Condition	Comments	Recommendation	Timescale
277	Beech	22	800	9	Mature	Dead	Recently died. Retains branch structure overhanging driveway.	Remove	Within 3 months.
278	Beech	24	800	9	Mature	Fair	Dense crown with general bias away from house and driveway. Large, decaying wound on lower trunk with good wound wood formation. Will be exposed following removal of neighbouring dead tree.		
279	Western hemlock	22	600	6	Mature	Fair	Restricted spread overhanging path and stream. Sparse with some browning of foliage. Resinous bleeding from base. Bias towards driveway.		
280 Group	Western hemlock	15	Up to 450	4	Semi mature	Fair	Group of 6 closely spaced individuals on embankment between stream and house. Younger trees suppressed by dense upper canopy.		
281	Yew	12	600	8	Mature	Fair	Low spreading crown overhanging path.		
282 Group	Sycamore, ash, beech, Wych elm, rhododendron	Up to 18	Up to 500		Semi mature to young	Fair to poor	Dense areas of trees on steep embankment. Taller trees form closed canopy with dense, young, predominantly ash regeneration beneath. Edge trees within falling distance house and garden. Gap in canopy where septic tank outflow is located.	To discourage the development of an impenetrable ticket, thinning to remove rhododendron and overcrowded trees could be undertaken.	Within 12 months
283	Beech	19	750	9	Mature	Fair	Dense crown overhanging car parking. Minor tip thinning. Growing from low, collapsing boundary wall. Minor deadwood and stubs.	Crown clean.	Within 6 months
284	Low's fir	35	1200	6	Mature	Fair	Very large tree growing adjacent to stream just beyond site boundary. Top within falling distance of garden. Straight trunk with dead and suppressed lower branches. Top remains dense.		
285	Western red cedar	30	1100	6	Mature	Fair	Very large tree growing adjacent to stream just beyond site boundary. Overhanging track. Top within falling distance of garden. Tight fork at 6m forming 2 co-dominant leaders. Relatively sparse.		

Tag	Species	Ht (m)	Dia (mm)	Max. Crown Radius (m)	Age Class	Condition	Comments	Recommendation	Timescale
286	Western hemlock	30	1100	7	Mature	Fair	Very large tree growing adjacent to stream just beyond site boundary. Top within falling distance of garden. Tight fork at 8m forming 2 co-dominant leaders. Dense crown to ground level. Large deadwood and hanging branch pose little threat.		
287	Sycamore	18	550	6	Semi mature	Fair	Restricted spread overhanging path at property boundary. Vigorous growth.		
288	Grand fir	26	650	4	Mature	Fair	Within closely spaced group of 6 on embankment between garden and track. Restricted spread with bias away from garden.		
289	Grand fir	26	650	5	Mature	Fair	Within closely spaced group of 6 on embankment between garden and track. Restricted spread with bias towards garden.		
290	Grand fir	10	600	4	Mature	Poor	Within closely spaced group of 6 on embankment between garden and track. Top has snapped at tight forks at 10m. Lower branches remain vigorous.		
291	Grand fir	9	400	2	Semi mature	Dead	Within closely spaced group of 6 on embankment between garden and track. Top has failed at tight forks. Standing dead trunk provides wildlife habitat.		
292	Grand fir	25	750	6	Mature	Fair	Within closely spaced group of 6 on embankment between garden and track. Restricted spread with bias towards garden.		
293	Grand fir	23	550	5	Mature	Fair	Within closely spaced group of 6 on embankment between garden and track. Restricted spread with bias away from garden.		
294	Grand fir	26	700	5	Mature	Poor	One of pair on embankment between garden and track. Lesser form in upper crown. Tips overhanging garden. Broken, hanging branch in lower crown.	Undertake drone aerial inspection of fork union in upper crown.	Within 6 months

Tag	Species	Ht (m)	Dia (mm)	Max. Crown Radius (m)	Age Class	Condition	Comments	Recommendation	Timescale
295	Grand fir	20	800	6	Mature	Fair	One of pair on embankment between garden and track. Dense crown from straight trunk.		
296	Douglas fir	28	1100	9	Mature	Fair	Tall and straight with sparse crown. Moderate deadwood and hanging branches. Growing from stone wall just beyond site boundary. Root spread restricted and of lesser form. Bushy yew at base.		
297	Californian red fir	32	1200	7	Mature	Fair	Very tall tree with dense crown to ground level. Within falling distance of garden. Base is well tapered. Neighbouring tree has historically uprooted.	Undertake drone aerial inspection of upper crown due to proximity to garden and house.	Within 6 months
298	Californian red fir	30	1050	6	Mature	Fair	Very tall tree with restricted spread between similar neighbours. Few lower branches. Within falling distance of garden. Supporting partially collapsed semi mature tree near base.		
299	Californian red fir	30	1050	6	Mature	Fair	Very tall tree with restricted spread between similar neighbours. Few lower branches. Within falling distance of garden.		
300	Californian red fir	32	1150	8	Mature	Fair	Very tall tree with restricted spread between similar neighbours. Dense upper crown. Within falling distance of garden.		
301	Californian red fir	33	1150	6	Mature	Fair	Very tall tree within falling distance of garden. Dense upper crown. Rhododendron and fallen trees make access to base difficult. Smaller spruce at base has bias towards woodland area.	Remove smaller spruce at base. Undertake drone aerial inspection of upper crown due to proximity to garden and house.	Within 6 months
302	Western hemlock	26	650	6	Mature	Fair	Tall and straight at woodland edge. Within falling distance of garden. Tight fork at base forming minor stem. Small hemlock at base. Nearby trees have historically uprooted.		
303	Western hemlock	28	1100	8	Mature	Fair	Tall with tight fork near base forming minor stem. Minor deadwood in lower crown. Dense upper crown. Within falling distance of garden.		

Tag	Species	Ht (m)	Dia (mm)	Max. Crown Radius (m)	Age Class	Condition	Comments	Recommendation	Timescale
304 Group	Western hemlock	Up to 28	Up to 750		Mature	Fair	Group of 4 closely spaced individuals within falling distance of garden. Tall and straight with dense upper crowns.		
305	Oriental spruce	19	750	5	Mature	Fair	Dense conical form near edge of garden. Lowest branches are suppressed. Self-seeded sycamore at base beginning to interfere with form.	Remove 3 self seeded sycamores nearest base and suppressing lower crown.	Within 6 months
306	Douglas fir	33	1200	9	Mature	Fair	Very large trunk with spreading crown next to driveway and within falling distance of garden. Moderate deadwood stubs and hanging branches. Dense rhododendrons developing around base.	Remove rhododendron and 4 self seeded sycamore from around base.	Within 6 months
307	Cedar of Lebanon	22	1050:700	10	Mature	Fair	Spreading crown from two co-dominant stem. Between driveway and garden. Moderate deadwood and stubs throughout.		
308	Oriental spruce	20	900	5	Mature	Fair	Dense crown to ground level. Between garden and driveway.		
309	Oak	20	950	10	Mature	Fair	Dense, spreading crown between driveway and garden. Moderate deadwood throughout.		
310	Western hemlock	19	500:450	7	Early mature	Fair	Twin stems from ground level. Bias towards and tips overhanging garden. Moderate deadwood throughout.		
311	Monkey puzzle	16	700	5	Mature	Fair	Straight trunk with no lower branches. Dense upper crown. Overhanging driveway and garden.		
312	Douglas fir	25	750	6	Mature	Fair	Restricted spread overhanging driveway. Dense with moderate deadwood.		

Tag	Species	Ht (m)	Dia (mm)	Max. Crown Radius (m)	Age Class	Condition	Comments	Recommendation	Timescale
313	Douglas fir	25	750	7	Mature	Fair	Restricted spread overhanging driveway. Moderate deadwood and dense upper crown.		
314	Oak	16	450	5	Early mature	Fair	Restricted spread within dense group. Poorly formed semi mature Douglas fir crossing lower trunk.	Remove semi mature Douglas fir crossing lower trunk.	Within 6 months
315	Oak	20	750	10	Mature	Fair	Spreading crown overhanging driveway. Bias away from garden. Moderate deadwood throughout.	Remove broken hanging branch above driveway supported in lower crown of adjacent holly.	Within 3 months
316	Beech	21	850	10	Mature	Fair	Dense spreading crown overhanging garden. Large wound on lower trunk with decay fungus on surface. Good wound wood formation occurring. Moderate deadwood, stubs and cavities higher on trunk.	Crown clean.	Within 6 months
317	Beech	20	700	9	Mature	Fair	Dense crown overhanging driveway. Sprouting from pruning wounds. Root spread appears restricted by driveway.		
318 Group	Silver birch, sycamore, cypress, umbrella pine, rhododendron	Up to 18	Up to 600		Mature to semi-mature	Fair	Woodland edge trees overhanging garden of Beechgrove. Rhododendron has been cleared in places. Includes birch on lawn.		