

Soakaway Testing at Denby House Farm

Date of Test 5th January 2017.

Size of trench = 2m x 0.5m x 1m depth.

The photograph below show the underlying porous nature of the site being chalk.

1.1 cubic meters of water was discharged into the test hole three times. It took 8 minutes for 1.1 cubic meters of water to discharge from the IBC.

On all three occasions, the water had completely percolated within 3 minutes of the completion of discharge.





The above photo shows the test hole being filled.



The above photo shows the test hole depth immediately following the completion of discharge of 1.1 cubic meters of water.