



T60 innovatively combines the design and look of traditional hot rolled Crittall steel window and door profiles with contemporary materials to deliver an enhanced thermal barrier system. The cold formed steel profiles retain the narrow sightlines and iconic profile providing maximum natural light and excellent thermal performance.

Features and Benefits

- Shaped windows and doors including arches and rakes
- Fully welded, seamless frame construction
- Slim profiles maximise glass area
- Factory applied architectural grade polyester powder coating
- Excellent thermal performance
- High acoustic attenuation
- Range of profiled beads for internal or external double and triple glazing
- Side, top and bottom hung windows together with single and double leaf doors
- Hardware designed for heritage and contemporary projects

Quick View	
Material	Steel, cold rolled
Glass Thickness	Up to 45 / 1-3/4" *
Suitability	All market sectors & building styles
Finish	Full range of RAL/BS colours
Thermal	As low as U value 0.8 W/m <sup>2</sup> K / 0.14 BTU
Acoustic	Up to Rw46dB
Air Permeability	Up to 600 Pa / 12.48 PSF
Water Tightness	Up to 600 / 12.53 PSF
Wind Resistance	Up to 2000 / 41.77 PSF
Quality Management	ISO 9001

\* Depending on configuration

VISION | INNOVATION | SOLUTIONS

t: +44 (0) 1376 530 800 e: [hq@crittall-windows.co.uk](mailto:hq@crittall-windows.co.uk)  
Crittall Windows Limited, Francis House, Freebournes Road, Witham, Essex, CM8 3UN