



- LEGEND**
- CUT CONTOURS AT 0.10m CENTRES
 - ZERO CONTOURS
 - FILL CONTOURS AT 0.10m CENTRES

CUT & FILL BASED ON PALS SURVEY AND HGA DESIGN FORMATION
 TOPSOIL (AVERAGE DEPTH = 0.50m) TOTAL TOPSOIL VOLUME 16476.64m³
 CUT & FILL AFTER TOPSOIL STRIP TO ACHIEVE FORMATION
 (FORMATION LEVEL = FINISHED GROUND LEVEL -0.45m)

TOTAL	
• CUT =	7601.8 x 7.5% (BULKING) = 8171.935 m ³
• FILL =	8490.8 m ³
• FALL =	318.865 m ³

Revisions	Date	Drn.
B LAYOUT REVISED	05.06.20	IM
C LAYOUT REVISED	19.02.21	IM

Revisions	Date	Drn.
B LAYOUT REVISED	05.06.20	IM
C LAYOUT REVISED	19.02.21	IM

HIGHLAND HOUSING ALLIANCE

APPROVAL DRAWING

consulting engineers
hga
 HGA(UK) Ltd
 Darach House
 Stonefield Business Park
 Inverness IV2 7PA
 T: 01463 221717
 F: 01463 224275
 email: hga@hgagroup.co.uk

St ANDREWS ROAD DINGWALL

CUT & FILL		
Drawn: IM	Ch'd	Scale: 1:500
Date: May 2020	Date:	DO NOT SCALE
Drawing No. 3547:115	Revision	C