

Details

FOWEY

868/0/10168 NORTH STREET 29-NOV-02 30

GV II

House. Circa 1830s; altered and extended C20. Local stone rubble. Slate roof with hipped and gabled ends. Lateral stack at rear with brick shaft. PLAN: 3-bay house with central entrance at the front; backing onto road and built over cellar with access at front from lower level yard on harbour side. EXTERIOR: 2 storeys and cellar. Symmetrical 3-bay east front facing harbour with C19 19-pane sashes, centre first floor 12-pane sash, with cambered red brick arches and slate cills; central doorway with similar arch and C20 6-panel door; narrow terrace in front with iron railings, over cellar with stone rubble piers supporting terrace and with central doorway; rendered bay on left [south] said to be remodelling of former outbuilding with lower roof level and canted bay window at front. Rear [west] facing North Street has small sashes under eaves and original 12-pane sash on left. INTERIOR altered, but retains panelled shutter to first floor rear window and 2-panel door in same room. A good example of a small late Georgian house with a 3-bay front facing the harbour.