All dimensions to be checked on site.
Discrepancies, ambiguities and / or omissions between this drawing and information given elsewhere must be reported immediately to head office for clarification before proceeding.

0 5 10 15 20 25
metres

## Legend

- Site Boundary
- Amenity Grass using EG22 Strong Lawn Grass Mix by Emorsgate Seeds or similar, sown at the recommended rate of 25g/m²
- Meadow Mix using MG5 Meadow Mix by Scotia Seeds or similar, sown at the recommended rate of 3g/m²
- Seeding to sides of swales and basins using E16 Landscape and Embankment Mix by Barenbrug Ltd or similar, sown at the recommended rate of 25-50g/m²
- Proposed Trees - 1000x1000x1000mm topsoil
- Woodland Edge Mix - 450mm topsoil laid on 400mm subsoil
- Woodland Planting 450mm topsoil laid on 400mm subsoil
- Princes Loch - Water Body
- Proposed Submerged Aquatic Mix Refer to planting plans and schedule
- Proposed Marginal Planting Refer to planting plans and schedule
- Proposed top and bottom of landform

**Bird Breeding Season and Vegetation Removal**

It is recommended that vegetation which needs to be removed is done prior to the bird breeding season. [1st March - 31st August] If this is not possible within this period, the vegetation removal should be carried out under the supervision of an Ecologist.

If birds are found to be breeding in the vegetation which needs to be removed then vegetation removal in the area surrounding the nest must be delayed until the eggs have hatched and the young birds have left the nest.

Tordene
Garage

Woodland Planting (Area 2)
31No. A gl
31No. B pe
31No. I a
31No. P av
62No. B pe
62No. C av
62No. P av
125No. P sy
187No. Q pe

Woodland Edge Mix (Area 2)
25No. P av
37No. P av
37No. P sp
37No. R can
49No. C av
62No. C mon

Woodland Planting (Area 4)
94No. A gl
94No. B pe
94No. I a
94No. P av
189No. B pe
189No. C av
189No. P av
378No. P sy
567No. Q pe

Woodland Edge Mix (Area 5)
14No. P av
21No. P av
21No. P sp
21No. R can
27No. C av
34No. C mon

Woodland Planting (Area 5)
8No. A gl
8No. B pe
8No. I a
8No. P av
16No. B pe
16No. C av
16No. P av
33No. P sy
49No. Q pe

Woodland Edge Mix (Area 4)
33No. P av
49No. P av
49No. P sp
49No. R can
65No. C av
81No. C mon

Woodland Planting (Area 3)
17No. A gl
17No. B pe
17No. I a
17No. P av
33No. B pe
33No. C av
33No. P av
67No. P sy
100No. Q pe

Woodland Edge Mix (Area 3)
4No. P av
7No. P av
7No. P sp
7No. R can
9No. C av
11No. C mon

Marginal Planting (Area 3)
3095No. C ot
3095No. C pa
3095No. I p
3095No. L sa
3095No. S er

Submerged Aquatic Mix (Area 5)
513No. CL
513No. POTCR

Submerged Aquatic Mix (Area 4)
432No. CL
432No. POTCR

6A
6B
7A

| | | | | | |
|---|---|---|---|---|---|
| Path Removed | S4 | P04 | DWR | EMC | 26/01/21 |
| Site boundary amended | S4 | P03 | DWR | EMC | 15/01/21 |
| Issued for Planning | S4 | P02 | DWR | EMC | 17/12/20 |
| Issued for Planning | S4 | P01 | DWR | EMC | 15/12/20 |
| Revision | Status | Rev | Author | Apvd | Date |


**newcastle:**
studio 7 & 8, The Kiln, Knutts Yard, Walker Road, NE6 2HL
t: +44 (0)191 281 3775
**london:**
the fisheries, 1 mentmore terrace, london, e8 3pn. t: +44 (0)203 479 2649
**glasgow:**
177 w george st, glasgow metropolitan area g2 2lb. t: +44 (0)141 303 1465
w: www.oobe.co.uk e: info@oobe.co.uk


| | |
|---|---|
| Client | Hargreaves Services (Blindwells) Ltd |
| Project | Blindwells Phase 2 |
| Title | Planting Plan Sheet 2 |
| Dwg. No. | 5301- OOB- 02- 00- DR- L- 0004 |
| Revision | P04 |
| Scale | 1 : 500 @ A0 |
| Date | December 2020 |

PLANNING