

VELUX conservation roof windows

For traditional buildings



When planning dictates that a window of traditional external appearance is required, conservation roof windows should be considered. All of our conservation roof windows have the same technical features of a VELUX roof window, but in a traditional black conservation style.

- Available in either centre-pivot or top-hung.
- Black external profiles and glazing bar. RAL 9005.
- Recessed installation for slate and tiled roofs.
- Top-hung roof windows listed below are suitable for emergency escape.
- Other sizes and glazing options available – contact us for further information.



Conservation packages include:

- Roof windows with laminated glazing as standard for safety.
- Recessed flashings available for a more streamlined external appearance.
- Insulation collar and underfelt collar provided for a weathertight and energy efficient installation.

Optional glazing bars for standard VELUX roof windows



The requirements from conservation officers throughout the country differ and the black finish featured within our conservation roof window packages may not be required in your area.

Consult your local conservation officer and find out if you can create a traditional appearance by adding a glazing bar to a standard VELUX roof window with grey exterior. This will allow you to take advantage of all roof window styles and sizes, available (except triple glazed roof windows).

Grey glazing bars are also available for standard VELUX roof windows

Recessed flashing



As well as the addition of a glazing bar, your local conservation officer may request that your roof window be installed deeper into the roof than can be achieved with a standard installation. To do this you should select a recessed flashing kit, which will provide a sleek, streamlined finish as less of the roof window protrudes above the roofline. Recessed flashings are also available with insulation and underfelt collars and are recommended for optimum energy efficiency.

Our full range of recessed flashings are available as part of our conservation roof window packages and help you comply with local conservation requirements.

To create your grey conservation package:

- Select your preferred VELUX roof window. This includes white painted, white polyurethane, pine and all operating methods (pages 20-25).
- Choose a flashing kit suitable for your specific roof pitch and roofing material – a recessed flashing kit is recommended (pages 50-51).
- Use VELUX installation products for optimum energy efficiency (pages 48-49).

• Add one or more conservation glazing bars in the corresponding size to your roof windows.

Grey glazing bar to match grey exterior (nearest RAL 7043) finish of standard VELUX roof windows.

We recommend the use of two glazing bars for our wider roof windows such as SK06, UK04 and UK08.



Optional glazing bars for standard windows	CK02	CK04	MK04	UK04	CK06	FK06	MK06	SK06	MK08	PK08	UK08	PK10
▶ 2 glazing bars for UK04-SK06 & UK08	ZGA WK02 0024	ZGA WK04 0024	ZGA WK04 0024	ZGA WK04 0024	ZGA WK06 0024	ZGA WK06 0024	ZGA WK06 0024	ZGA WK06 0024	ZGA WK08 0024	ZGA WK08 0024	ZGA WK08 0024	ZGA WK10 0024
	£20	£22	£22	£22	£24	£24	£24	£24	£26	£26	£26	£28

- ▶ Glazing bars are not available for –66 and –62 triple glazing variants.
- ▶ Prices above are for 1 glazing bar only.
- ▶ All glazing bars have a delivery time of 2 days.
- ▶ Delivery time is in working days from receipt of orders placed before 4pm (UK) and 3pm (NI).

Conservation roof windows

External frame size (nominal w x h) cm

Code	Description	55 x 98	55 x 118	66 x 118	78 x 118	78 x 110	131 x 98
Centre-pivot white painted		CK04	CK06	FK06	MK06	MK08	UK04
GGI SD5N2 L-value 1.3 W/m ² K	GGI 2570 roof window + EDI recessed flashing for slate up to 8mm thick (min 20° roof pitch)	£438	£455	£495	£558	£601	£726
GGI SD5P2 L-value 1.3 W/m ² K	GGI 2570 roof window + EDP flashing for plain tiles up to 14mm thick (min 25° roof pitch)	£400	£416	£453	£514	£554	£673
GGI SD5W2 L-value 1.3 W/m ² K	GGI 2570 roof window + EDW flashing for tiles up to 120mm in profile (min 15° roof pitch)	£400	£416	£453	£514	£554	£673
GGI SD5J2 L-value 1.3 W/m ² K	GGI 2570 roof window + EDJ recessed flashing for tiles up to 90mm in profile (min 20° roof pitch)	£438	£455	£495	£558	£601	£726
Top-hung white painted. For roof pitches of 55-75° please specify special springs when ordering.							
GPL SD5N2 L-value 1.3 W/m ² K	GPL 2570 roof window + EDN recessed flashing for slate up to 8mm thick (min 20° roof pitch)	-	-	-	-	-	£725
GPL SD5P2 L-value 1.3 W/m ² K	GPL 2570 roof window + EDP flashing for plain tiles up to 14mm thick (min 25° roof pitch)	-	-	-	-	-	£678
GPL SD5W2 L-value 1.3 W/m ² K	GPL 2570 roof window + EDW flashing for tiles up to 120mm in profile (min 15° roof pitch)	-	-	-	-	-	£678
GPL SD5J2 L-value 1.3 W/m ² K	GPL 2570 roof window + EDJ recessed flashing for tiles up to 90mm in profile (min 20° roof pitch)	-	-	-	-	-	£725

- ▶ All roof windows have a delivery time of 2 days.
- ▶ Delivery time is in working days from receipt of orders placed before 4pm (UK) and 3pm (NI).