



Main Entrance Foyer, Stairs 10 & Stair 11	Item	Area	Specification	Product	Colour/ref.	Light Reflectance Value (LRV)	Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Entrance lobby	Entrance mat M50/171	Zeno Protect Super	Colour 370 Basalt	LRV 2.7	Agreed 16/10/19	Gradus SFBR37/AFT3912 ramped transition strip as required. Finish brushed stainless steel.
	Flooring	Stairs & circulation	Linoleum	Tarkett Veneto Sicuro xR R10	Silk 625	LRV 31		Main body to circulation routes set with 50mm nosing to stair treads
	Flooring	Stairs & Circulation Feature Inlay	Linoleum	Tarkett Veneto Sicuro xR R10	Chocolate 632 with chocolate seams	LRV 9		80mm border to reflect historic terrazzo detailing to lower circle bar only. 50mm nosing to be formed on stair treads.
	Flooring	Stair nosing's to stairs with linoleum	Stairrods UK Ltd LVT Nosing	Stairrods UK Ltd LVT Full Bull Nosing	Polished Nickel			Nosing formed in polish nickel with 50mm chocolate linoleum strip on treads only
	Flooring	Foyer (generally)	Existing terrazzo and/or new terrazzo to match existing as M41/120	To match existing	To match existing		Agreed 16/10/19	
	Wall finish	Foyer	Laminate panelling K13/125	Contractors choice	Formica Macchiato F6932	LRV 15.8		Refer to Space A(42) series drawings for locations, heights and details
	Wall finish	Stairs 10 & 11 (above panelling)	Paint M60/115	Refer to Theatresearch specification & schedule	Green NCS S 1040 G	LRV 50		Refer to Theatre search historic paint schedule.
	Wall finish	Above panelling	Paint M60/115	Refer to Theatresearch specification & schedule	Green NCS S 1040 G	LRV 50		
	Wall finish	Stairs 10 & 11 (Existing balustrade to stair well)	Paint M60/115	Refer to Theatresearch specification & schedule	Varies (Green, Yellow & Lighter Yellow)	Varies		Refer to Theatre search historic paint schedule & sample panel on-site
	Wall finish	Stairs 10 & 11 (Existing balustrade to stair well & existing skirtings)	Paint M60/115	Refer to Theatresearch specification & schedule	Dark Brown NCS S 5040Y10R	LRV 14		Derogation agreed with Building Control in light of historic context
	Ceiling	Foyer	Paint M60/115	Refer to Theatresearch specification & schedule	Various (Green, Yellow & Lighter Yellow)	Varies		Refer to theatre search historic paint schedule.
	Ceiling	Stairs 10 & 11 (ceilings and stair soffits)	Paint M60/115	Refer to Theatresearch specification & schedule	Lighter Yellow NCS S 0530Y10R	LRV 77		Refer to Theatre search historic paint schedule.
	Doors	FOH	Laminate	Contractors choice	Formica Macchiato F6932	LRV 15.8		Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	FOH	Paint M60/130	Refer to Theatresearch specification & schedule	Light Grey NCS S 2002 Y50R	LRV 55		
	Skirting	Foyer	Hardwood P20/125	Contractors choice	Walnut	LRV 15.8	Agreed 16/10/19	Derogation agreed with Building Control in light of historic context

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Emergency Exit Stairs 7, 8, 9	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Stair risers & treads	Epoxy Floor Paint M60/182	Armstead Floor Paint	RAL 8011 Nut Brown	LRV 5		Theatresearch confirmed 04.11.2020
	Flooring	Contrasting nosings	Epoxy Floor Paint M60/182	Armstead Floor Paint	White			
	Wall finish	Stair walls up to dado height	Paint M60/115	Refer to Theatresearch specification & schedule	Green NCS S 1040 G	LRV 50		Paint colour up to dado height only. Refer to Theatresearch specification & schedule
	Wall finish	Dado quirk (existing or new to replicate existing)	Refer to Theatresearch specification & schedule	Refer to Theatresearch specification & schedule	Black	N/A		Reveal formed in plaster to match original where original has been lost
	Wall finish	Stair walls above dado height	Paint M60/115	Refer to Theatresearch specification & schedule	Cream NCS S 1015Y	LRV 71		Paint colour above dado height only. Refer to Theatresearch specification & schedule
	Skirtings	Stair stringers and skirtings	Refer to Theatresearch specification & schedule	Refer to Theatresearch specification & schedule	Dark Brown NCS S 5040Y10R	LRV 14		
	Ceiling	Ceilings above exit stairs	Paint M60/110	Refer to Theatresearch specification & schedule	Gardenia BS10B15	LRV 72		

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Emergency Exit Stair 12	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Stair risers & treads	Vinyl sheet M50/151	Gerflor Taralay Impression Control	0543 Cemento Brescia	LRV 34	To be agreed	NOTE: Stair 12 is of a timber construction
	Nosing	Gradus as M50/751	EAR1140	Aluminium nosing with coloured insert on tread	Jet (Black) insert	LRV 4		
	Wall finish	Stair walls up to dado height	Paint M60/115	Refer to Theatresearch specification & schedule	Green NCS S 1040 G	LRV 50	To be agreed	Paint colour up to dado height only. Refer to Theatresearch specification & schedule
	Wall finish	Dado quirk (existing or new to replicate existing)	Refer to Theatresearch specification & schedule	Refer to Theatresearch specification & schedule	Black	N/A	To be agreed	Reveal formed in plaster to match original where original has been lost
	Wall finish	Stair walls above dado height	Paint M60/115	Refer to Theatresearch specification & schedule	Cream NCS S 1015Y	LRV 71	To be agreed	Paint colour above dado height only. Refer to Theatresearch specification & schedule
	Skirtings	Stair stringers and skirtings	Refer to Theatresearch specification & schedule	Refer to Theatresearch specification & schedule	Dark Brown NCS S 5040Y10R	LRV 14	To be agreed	Confirmation required of finishes. Stair has vinyl finish in lieu of paint. SBC / Theatresearch / ATG to confirm colour choice is acceptable for vinyl.
	Ceiling	Ceilings above exit stairs	Paint M60/110	Refer to Theatresearch specification & schedule	Gardenia BS10B15	LRV 72	To be agreed	

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Stair 01 (153 to Globe Stalls)	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Stairs & circulation	Linoleum	Tarkett Veneto Sicuro xF R10	Silk 625 & Chocolate 632	LRV 31		50mm nosing on treads only formed in Chocolate 632 with weld to match Chocolate
	Flooring	Stair nosing's to stairs with linoleum	Stairrods Uk Ltd LVT Nosing	Stairrods Uk Ltd LVT Full Bull Nosing	Polished Nickel			Derogation agreed with Building Control in light of historic context
	Wall finish	Below dado quirk	Paint M60/115	Refer to Theatresearch specification & schedule	Green NCS S 1040 G	LRV 50		
	Wall finish	Dado quirk (existing & re-created)	Paint M60/115	Refer to Theatresearch specification & schedule	Black	N/A		Dado quirk to be made good or repaired to walls that do not receive dry lining
	Wall finish	Above Dado Quirk	Paint M60/115	Refer to Theatresearch specification & schedule	Lighter Yellow NCS S 0530Y10R	LRV 77		
	Wall finish	To existing stucco skirting's & new timber skirtings as P20/125	Paint M60/115	Refer to Theatresearch specification & schedule	Dark Brown NCS S 5040Y10R	LRV 14		Constrast achieved between skirting and wall.
	Wall finish	Wall finish - half height wall at entrance level & feature wall within stair well	Paint M60/115	Refer to Theatresearch specification & schedule	Green NCS S 1040 G	LRV 50		
	Ceiling	Ceilings and upstands to light well	Paint M60/110	Refer to Theatresearch specification & schedule	Gardenia BS10B15	LRV 72		
	Doors	FOH doors	Laminate	Formica	Formica Macchiato F6932	LRV 15.8		Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002. Contrast achieved between wall and door.
	Door frames & architraves	FOH	Paint M60/130	Refer to Theatresearch specification & schedule	Light Grey NCS S 2002 Y50R	LRV 55		

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Stair 05 & adj circulation (Annexe - BOH)	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	
	Flooring	Stair risers & treads	Epoxy Floor Paint M60/182	Dulux Trade Floor Shield	RAL 7024	LRV 7		
	Flooring	Nosing's to stairs	M50/752	Quantum SF125 R	Polar Grey	LRV 49		To contractors proposal
	Wall finish	Walls to stair and adjacent lobbies / circulation	Paint M60/115	Dulux Diamond Eggshell	Grey NCS S 2002 Y50R	LRV 55		Client change 23.10.2020
	Ceiling	Ceilings generally	Paint M60/110	Dulux Trade Vinyl Matt	White 50YR 83/003	LRV 83		
	Skirting	MDF as P20/200	M60/130	Dulux Trade Gloss or Satin	White 50YR 83/003	LRV 83		
	Doors	BOH Doors	Laminate faced doorsets	Formica	F8859 Vintage Brush	LRV 25	Agreed 16/10/19	
	Door frames & architraves	BOH Doors	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Stair 25 (153 Bar / Kitchen)	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Glass wash, cellar lobby and stair	Slip resistant vinyl sheet M50/150 type 02A	Forbo Flooring Surestep R11	Charcoal 171992 R11	LRV 6	Agreed 16/10/19	
	Flooring	Nosing's to stairs	M50/751	Gradus EAR1140	Glacier	LRV 42.9		
	Flooring	Capping to coved skirting	M50/744	Gradus HCS48	Black	LRV 4.62		
	Wall finish	Glass wash, cellar lobby and stair	Paint M60/115	Dulux Diamond Eggshell	White 50YR 83/003	LRV 83		
	Ceiling	Glass wash, cellar lobby and stair	Paint M60/110	Dulux Trade Vinyl Matt	White 50YR 83/003	LRV 83		
	Doors	BOH Doors	Laminate faced doorsets	Formica	F8859 Vintage Brush	LRV 25	Agreed 16/10/19	
	Door frames & architraves	BOH Doors	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Stair 19 (153 / Debenhams escape stair)	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Stair risers & treads	Epoxy Floor Paint M60/182	Dulux Trade Floor Shield	RAL 7024	LRV 7		
	Flooring	Nosing's to stairs	M50/751	Gradus EAR1140	Glacier	LRV 42.9		
	Wall finish	Walls to stair and adjacent lobbies / circulation	Paint M60/115	Dulux Diamond Eggshell	White 50YR 83/003	LRV 83		
	Ceiling	Ceilings generally	Paint M60/110	Dulux Trade Vinyl Matt	White 50YR 83/003	LRV 83		
	Skirting	MDF as P20/200	M60/130	Dulux Trade Gloss or Satin	To match wall	LRV 83		
	Doors	BOH Doors	Laminate faced doorsets	Formica	F8859 Vintage Brush	LRV 25		
	Door frames & architraves	BOH Doors	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Stairs 22 & 23	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Stair risers, treads and circulation	Epoxy Floor Paint M60/182	Dulux Trade Floor Shield	RAL 7024	LRV 7		
	Flooring	Nosing's to stairs	M50/751	Gradus EAR1140	Glacier	LRV 42.9		
	Wall finish	Walls to stair and adjacent lobbies / circulation	Paint M60/115	Dulux Diamond Eggshell	White 50YR 83/003	LRV 83		
	Ceiling	Ceilings generally	Paint M60/110	Dulux Trade Vinyl Matt	White 50YR 83/003	LRV 83		
	Skirting	MDF as P20/200	M60/130	Dulux Trade Gloss or Satin	RAL 7024	LRV 7		
	Doors	BOH Doors	Laminate faced doorsets	Formica	F8859 Vintage Brush	LRV 25		
	Door frames & architraves	BOH Doors	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Transition Zone	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Whole floor	Resin M12/110	Vebrospeed Quartz	Dark Grey 703 equivalent	LRV 11.86	Agreed 16/10/19	Confirmed as part of CE59488. Refer to drawing K00186-SPACE-ZZ-00-DR-A-70-1001
	Wall finish	Walls	Paint M60/115	Dulux Diamond Eggshell	Off-white 00YY 63/024	LRV 63		Confirmed as part of CE59488. Refer to drawing K00186-SPACE-ZZ-00-DR-A-70-1001
	Wall finish	Columns	Intumescent paint M61/110	Contacto to advise top coat compatible with intumescent paint system	Off-white 00YY 63/024	LRV 63		Confirmed as part of CE59488. Refer to drawing K00186-SPACE-ZZ-00-DR-A-70-1001
	Wall finish	Walls	Paint M60/115	Dulux Diamond Eggshell	Deep Rust 30YR 14/365	LRV 14		
	Wall finish	Skirtings & Architraves	Paint as M60/130 to match wall. Skirtings as P20/130	Dulux Trade Satin	Colour to match walls		Agreed 05/08/20	ATG confirmed satin 01.12.2020 (verbal instruction on-site)
	Ceiling	Perforated plasterboards and plasterboard margins	Paint M60/110	Dulux Trade Vinyl Matt	White to match RAL 9010	LRV 84		Confirmed as part of CE59488. Refer to drawing K00186-SPACE-ZZ-00-DR-A-70-1001
	Doors	FOH Doors	Laminate	Formica Laminate	Formica Macchiato F6932	LRV 15.8		Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	FOH Doors	Paint M60/130	Refer to Theatresearch specification & schedule	Light Grey NCS S 2002 Y50R	LRV 55		

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Cloaks Area	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Cloak room flooring inc coved skirting	Linoleum	Tarkett Veneto Sicuro xF R10	Silk 625	LRV 31		
	Wall finish	Walls	Paint M60/115	Dulux Diamond Eggshell	Off-white 00YY 63/024	LRV 63		
	Ceiling	Painted plasterboard	Paint M60/110	Dulux Trade Vinyl Matt	White to match RAL 9010	LRV 84		
	Doors	FOH Bifold	Laminate	Formica Laminate	Formica Macchiato F6932	LRV 15.8		Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	FOH Doors	Paint M60/130	Refer to Theatresearch specification & schedule	Light Grey NCS S 2002 Y50R	LRV 55		
	Doors	BOH	Laminate L20/411, 412, 413	Formica Laminate	Vintage Brush F8859	LRV 25	Agreed 16/10/19	Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	BOH Doors	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



First Aid Room	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	First aid room flooring inc coved skirting	Slip resistant vinyl M50/152	Tarkett standard plus	Dark Stone Grey 0499	LRV 19.1	Agreed 16/10/19	
	Flooring	Capping to coved skirting	M50/744	Gradus HCS48	Granite	LRV 10.44		
	Wall finish	Walls	Paint M60/115	Dulux Diamond Eggshell	Off-white 00YY 63/024	LRV 63	Agreed 05/08/20	
	Ceiling	Painted plasterboard	Paint M60/110	Dulux Trade Vinyl Matt	White to match RAL 9010	LRV 84	Agreed 05/08/20	
	Cabinets	Fixed storage with work surface over	contractors choice	Contractors choice, high gloss flat slab	White			
	Counter top	Counter top over fixed storage with inset stainless steel sink	Laminate with post formed edge	Howdens 38mm bullnose	Light stone WOK0160			
	Doors	BOH	Laminate L20/411, 412, 413	Formica Laminate	Vintage Brush F8859	LRV 25		
	Door frames & architraves	BOH Doors	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Display Areas adj to First Aid	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Display area floor inc coved skirting	Linoleum	Tarkett Veneto Sicuro x ² R10	Silk 625	LRV 31	To be agreed	SBC / ATG to confirm colour choice
	Wall finish	Walls	Paint M60/115	Dulux diamond eggshell, matt or satin	Off-white 00YY 63/024	LRV 63		
	Skirting	MDF as P20/200	M60/130	Dulux Trade Gloss or Satin	White 00YR 63/024	LRV 83		
	Ceiling	Display area ceiling	Paint M60/110	Dulux Trade Vinyl Matt	White to match RAL 9010	LRV 84		
	Doors	BOH	Laminate L20/411, 412, 413	Formica Laminate	Vintage Brush F8859	LRV 25		
	Door frames & architraves	BOH Doors	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Display Area adj to 153 Transition	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Display area floor inc coved skirting	Linoleum	Tarkett Veneto Sicuro x ² R10	Silk 625	LRV 31	To be agreed	SBC to advise preference for AMP finish or alternative
	Skirting	All walls	P20/200	Contractors choice	Off-white 00YY 63/024	LRV 63		TBA - to suit floor finish
	Wall finish	Walls	Paint M60/115	Dulux diamond eggshell, matt or satin	Off-white 00YY 63/024	LRV 63	Agreed 05/08/20	
	Ceiling	Display area ceiling	Paint M60/110	Dulux Trade Vinyl Matt	White to match RAL 9010	LRV 84	Agreed 05/08/20	
	Doors	BOH	Laminate L20/411, 412, 413	Formica Laminate	Vintage Brush F8859	LRV 25		
	Door frames & architraves	BOH Doors	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Cellar(s)	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Cellar floor	Epoxy paint M60/182	Dulux trade floorshield	RAL 7024		Agreed 29/07/2020	
	Wall finish	Cellar walls	Paint M60/115	Dulux diamond eggshell	White to match RAL 9010	LRV 84		
	Skirting	All walls	Paint as M60/130 to match wall. Skirtings as P20/200	Dulux Trade Gloss or Satin	White to match RAL 9010	LRV 84		
	Ceiling	No ceiling - spray insulation	Self finished					
	Doors	BOH	Laminate L20/411, 412, 413	Formica Laminate	Vintage Brush F8859	LRV 25		
	Door frames & architraves	BOH Doors	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)



"Link" Ground Floor 153	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Main bar/ performance space/ circulation	Resin M12/110	Vebrospeed Quartz	Light Grey 701 equivalent	LRV 34.5	Agreed 16/10/19	
	Flooring	Entrance lobby	Entrance mat M50/171	Zeno Protect Super	Colour 370 Basalt	LRV 2.7	Agreed 16/10/19	Gradus SFB37/AFT3912 ramped transition strip as required. Finish brushed stainless steel.
	Flooring	Behind Bar (inc. covered skirting)	Slip resistant vinyl sheet M50/150 type 02A	Forbo Flooring Surestep R11	Charcoal 171992 R11	LRV 6	Agreed 16/10/19	
	Flooring	Capping to covered skirting	M50/744	Gradus HCS48	Black	LRV 4.62		
	Flooring	Steps to WC lobby & stair 1	Linoleum	Tarkett Veneto Sicuro xF R10	Silk 625	LRV 31		
	Flooring	Stair nosing to WC lobby & stair 1 steps	Gradus A20 as M50/754	Gradus trims rejected to Lino stairs.	Coffee insert	LRV 6		Bespoke curved nosing to suit radius of stair
	Wall finish	Painted walls	Paint M60/115	Dulux Diamond Eggshell	Off-white 00YY 63/024	LRV 63	TBC	Finish as per instruction CE59488
	Wall finish	Columns	Paint M60/115	Dulux Diamond Eggshell	Off-white 00YY 63/024	LRV 63	TBC	Finish as per instruction CE59488
	Wall finish	Painted walls	Paint M60/115	Dulux Diamond Eggshell	Deep Rust 30YR 14/365	LRV 14	TBC	
	Wall finish	Bar walls	As F10/230 or as existing	Exposed masonry	New or cleaned existing	N/A	TBC	
	Wall finish	Behind banquette	N/A	Reclaimed roof boards	Stain (TBC)	N/A	TBC	Existing roof boards from Globe to be reclaimed, de-nailed, edges made good and regularised to ensure consistent face size for re-use.
	Wall finish	Staircase 26	Paint M60/115	Dulux Diamond Eggshell	Green 30GG 16/137	LRV 16	TBC	
	Wall finish	Painted walls	N/A	Reclaimed roof boards		N/A	TBC	Existing roof boards from Globe to be reclaimed, de-nailed, edges made good and regularised to ensure consistent face size for re-use.
	Wall finish	Performance area	Paint M60/115	Dulux Diamond Eggshell	Black RAL 9017	LRV 2	TBC	Refer to drawings. Wall colour varies. Client change 18.11.2020
	Ceiling	Link bar & circulation	Paint M60/115	Dulux Trade Vinyl Matt	Graphite grey to match RAL 7024	LRV 7	TBC	
	Ceiling	Link bar & performance area	Paint M60/TBC	Contractor choice / paint system compatible with intumescent coatings, galvanised metalwork etc.	Black RAL 9017	LRV 2	TBC	Sprayed soffit, beams and services as instructed CE59488
	Ceiling	Link bar/performance area	Wood wool boards	Contractor choice / paint system compatible with intumescent coatings, galvanised metalwork etc.	Black RAL 9017	LRV 2	TBC	
	Ceiling	Performance area	Paint M60/115	Dulux Diamond Eggshell	Graphite grey to match RAL 7024 / Black RAL 9017 to performance area.	LRV 7	TBC	Refer to drawings. Wall colour varies. Client change 18.11.2020
	Skirting	All public bar areas	Reclaimed roof boards	N/A	Stain colour TBC (if required)	N/A	TBC	Existing roof boards from Globe to be reclaimed, de-nailed, edges made good and regularised to ensure consistent face size for re-use. Sample required to determine is stain required.
	Doors	FOH	Laminate L20/411, 412, 413	Formica Laminate	Steel Metal F5583 or Macchiatto F6932 (Stair 1)	LRV 22.9 / LRV 15.8		
	Door frames & architraves	FOH	Paint M60/130	Dulux Trade Satin	RAL 7024 to Steel Metal Doors	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)
	Door frames & architraves	FOH	Paint M60/130	Dulux Trade Satin	Light Grey NCS S 2002 Y50R to Macchiatto doors	LRV 55		ATG confirmed satin 01.12.2020 (verbal instruction on-site)
	Bar counter and back bar	VIP Bar	By others	By others	By others	N/A	By others	Refer to Gastronorth design and specification

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



VIP / Hospitality 153 First Floor	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Behind Bar	Slip resistant vinyl sheet M50/150 type 02A	Forbo Flooring Surestep R11	Charcoal 171992 R11	LRV 6	Agreed 05/08/20	As instructed as part of CE59488
	Flooring	Capping to coved skirting	M50/744	Gradus HCS48	Black	LRV 4.62		
	Flooring	VIP Bar	M50/111	Amico Signature	Wild Walnut AR0W7620	LRV 10	Agreed 05/08/20	As instructed as part of CE59488. 3x straight plank border to perimeter of room. Main body of floor made in herringbone pattern. Refer to drg 01-70-000
	Wall finish	VIP Bar	M52/TBC	Tektura	Labyrinth 2865	N/A	Agreed 05/08/20	As instructed as part of CE59488
	Wall finish	VIP bar & columns	Paint M60/115	Dulux Diamond Eggshell	Green 30GG 16/137	LRV 16	Agreed 05/08/20	As instructed as part of CE59488
	Wall finish	VIP bar wall panelling	M60/155	Dulux Diamond Eggshell	Green 30GG 16/137	LRV 16	Agreed 05/08/20	As instructed as part of CE59488
	Skirting and architrave	VIP Bar	MDF as P20/200 painted as M60/130	Dulux Trade Satin	Off white to match RAL 9010	LRV 84	Agreed 05/08/20	As instructed as part of CE59488
	Ceiling	Painted Plasterboard	Paint M60/110		White to match RAL 9010	LRV 84	Agreed 05/08/20	As instructed as part of CE59488
	Doors	FOH doors	Laminate	Formica	Formica Macchiato F6932	LRV 15.8		Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002. Contrast achieved between wall and door.
	Bar counter and back bar	VIP Bar	By others	By others	By others	N/A	Agreed 05/08/20	Refer to Gastronorth design and specification

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Lift 01 / VIP/ Circle (ramp)	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Stairs & circulation spaces	Linoleum	Tarkett Veneto Sicuro xF R10	Silk 625	LRV 31		Border tile to circulation spaces
	Flooring	Bar and ramp landings feature Inlay	Linoleum	Tarkett Veneto Sicuro xF R10	Chocolate 632 with chocolate seams	LRV 9		80mm border to reflect historic terrazzo detailing. Seams to be chocolate to match.
	Walls	Walls generally	Paint as Paint M60/115	Dulux Diamond Eggshell	Off-white 00YY 63/024	LRV 63	Agreed 05/08/20	
	Skirting	To all circulation areas	Hardwood as P20/130	Contractors choice	Walnut	LRV 15.8		
	Ceiling	Solid and perforated plasterboard	Paint as Paint M60/110	Dulux Trade Vinyl Matt	White		Agreed 05/08/20	
	Doors	FOH circulation	Laminate	Formica	Formica Macchiato F6932			Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	FOH	Paint M60/130	Dulux Trade Satin	Light Grey NCS S 2002 Y50R	LRV 55		ATG confirmed satin 01.12.2020 (verbal instruction on-site)

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Stair 24 (153 / VIP / Circle Ramp)	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Stairs & circulation spaces	Linoleum	Tarkett Veneto Sicuro xF R10	Silk 625	LRV 31		
	Flooring	Nosing's to stairs	M50/751	Gradus EAR1140	Coffee insert	LRV 6.05		
	Walls	Walls generally	Paint as Paint M60/115	Dulux Diamond Eggshell	Off-white 00YY 63/024	LRV 63	Agreed 05/08/20	
	Skirting	To all circulation areas	Hardwood as P20/130	Contractors choice	Walnut	LRV 15.8		TBC following confirmation of floor finish and wall colour
	Ceiling	Solid and perforated plasterboard	Paint as Paint M60/110	Dulux Trade Vinyl Matt	White RAL 9010	LRV 84	Agreed 05/08/20	
	Doors	FOH circulation	Laminate	Formica Laminate	Formica Macchiato F6932	LRV 15.8		Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	FOH	Paint M60/130	Dulux Trade Satin	Light Grey NCS S 2002 Y50R	LRV 55		ATG confirmed satin 01.12.2020 (verbal instruction on-site)

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



153 Offices (Mid & Upper Circle)	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	153 office and GM office	Carpet tile M50/131	Paragon Greda	8775 Ghost Machine	LRV TBC		Tile size 500 x 500
	Wall finish	153 office and GM office	Matt Paint M60/115	Dulux Diamond Matt	White 50YR 83/003	LRV 83		
	Ceiling	153 office and GM office	Lay in grid K40/114		Self colour: White			
	Kitchen Unit	153 Office	Cabinet doors	Contractors choice	High gloss, white flat slab		Agreed 05/08/20	
	Kitchen Counter	153 Office	contractors choice	Howdens 38mm bullnose	Light stone WOK0160			
	Doors	BOH	Laminate	Formica Laminate	Vintage Brush F8859	LRV 22	Agreed 16/10/19	Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	BOH	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)
	Skirting	153 office and GM office	MDF as P20/200 painted as M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)



Auditorium	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Stalls	Resin M12/110	Vebrospeed Quartz	Dark Grey 703 (equivalent)	LRV 11.86	Agreed 16/10/19	
	Wall	Stalls Skirting	Stainless steel	As part of wall panelling	Stainless Steel			
	Flooring	Circle generally (treads of tiered seats only, treads and risers of all aisle gangways and treads and risers of vomitory stairs)	Carpet M51/111	Newhey Express	18392 Colourway 13	LRV 2.2		
	Flooring	Nosing to seating tiers	Black PVC Nosing M51/551	Contractors choice	Black	TBC		
	Flooring	Plywood to tier risers	Refer to Theatresearch specification & schedule	Refer to Theatresearch specification & schedule	Dark Brown NCS S 5040Y10R	LRV 14		
	Wall finishes	Auditorium Walls	Paint M60/115	Refer to Theatresearch specification & schedule	Green NCS S 1040 G	LRV 50	Agreed 05/08/20	Refer to Theatre Search drawing: TS-1911-101
	Wall finishes	Auditorium Walls	Paint M60/115	Refer to Theatresearch specification & schedule	Lighter Yellow NCS S 0530Y10R	LRV 77	Agreed 05/08/20	Refer to Theatre Search drawing: TS-1911-101
	Wall finishes	Auditorium Walls	Paint M60/115	Refer to Theatresearch specification & schedule	Dark Brown & Glaze NCS S 5040Y10R	LRV 14	Agreed 05/08/20	Refer to Theatre Search drawing: TS-1911-101
	Stage front	Stage	Paint M60/115 on T&G panelling	Refer to Theatresearch specification & schedule	Dark Brown NCS S 5040Y10R	LRV 14	Agreed 05/08/20	Refer to Theatre Search drawing: TS-1911-100
	Proscenium Arch	Proscenium	Paint M60/115	Refer to Theatresearch specification & schedule	Green NCS S 1040 G	LRV 50	Agreed 05/08/20	Refer to Theatre Search drawing: TS-1911-100
	Proscenium Arch	Proscenium	Paint M60/115	Refer to Theatresearch specification & schedule	Deep Yellow NCS S 1050Y10R	LRV 61	Agreed 05/08/20	Refer to Theatre Search drawing: TS-1911-100
	Proscenium Arch	Proscenium	Paint M60/115	Refer to Theatresearch specification & schedule	Lighter Yellow NCS S 0530Y10R	LRV 77	Agreed 05/08/20	Refer to Theatre Search drawing: TS-1911-100
	Wall finishes	Panelling	Laminate	Formica	Formica Macchiato F6932	LRV 15.8		Refer to Space A(42) Series drawings
	Skirting	Below stalls wall & Stalls bar wall panelling	Resin M12/110	Vebrospeed Quartz	Dark Grey 703	LRV 11.86		
	Skirting	All areas without wall panelling	Hardwood to match existing as P201/35	To match existing / lost original fabric	Walnut	LRV 15.8		
	Wall finish	Circle skirtings, wall panelling and decorative features	To match existing fabric as P201/35-decoration to Theatresearch requirements	To match existing fabric - decoration to Theatresearch requirements	Refer to Theatresearch specification & schedule			Existing panelling / profiles to be repaired, made good or replaced to match existing materials
	Ceiling	Auditorium Ceiling	Paint M60/115	Refer to Theatresearch specification & schedule	Green NCS S 1040 G	LRV 50	Agreed 05/08/20	Refer to Theatre Search drawing: TS-1911-104
	Ceiling	Auditorium Ceiling	Paint M60/115	Refer to Theatresearch specification & schedule	Deep Yellow NCS 1050Y10R	LRV 61	Agreed 05/08/20	Refer to Theatre Search drawing: TS-1911-104
	Ceiling	Auditorium Ceiling	Paint M60/115	Refer to Theatresearch specification & schedule	Lighter Yellow NCS S 0530Y10R	LRV 77	Agreed 05/08/20	Refer to Theatre Search drawing: TS-1911-104
	Ceiling	Auditorium Ceiling	Refer to Theatresearch specification & schedule	Refer to Theatresearch specification & schedule	Gardenia BS 10B15	LRV 72	Agreed 05/08/20	Refer to Theatre Search drawing: TS-1911-104
	Stalls Removable Seats	Seat back (all backs)	Camira	Xtreme	(Green - bespoke special)			As instruction CE61777
	Stalls Removable Seats	Seat squabs (all squabs)	Camira	Xtreme	(Green - bespoke special)			As instruction CE61777
	Circle Seats	Seat squabs (all squabs)	Camira	Xtreme	(Green - bespoke special)			As instruction CE61777 - Refer to Theatresearch drawing TS-1911-105
	Circle Seats	Seat backs (60% of total seat backs)	Camira	Xtreme	(Green - bespoke special)			As instruction CE61777 - Refer to Theatresearch drawing TS-1911-105
	Circle Seats	Seat backs (20% of total seat backs)	Camira	Xtreme	Solano - YS072			As instruction CE61777 - Refer to Theatresearch drawing TS-1911-105
	Circle Seats	Seat backs (20% of total seat backs)	Camira	Xtreme	Nougat - YS091			As instruction CE61777 - Refer to Theatresearch drawing TS-1911-105
	Doors	FOH circulation	Laminate	Formica Laminate	Formica Macchiato F6932		To be agreed	Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	FOH	Paint M60/130	Refer to Theatresearch specification & schedule	Light Grey NCS S 2002 Y50R	LRV 55		
	Bar counter and back bar	Auditorium bar	By others	By others	By others		By others	Refer to Gastronorth design and specification

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Stalls Bar	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Stalls	Resin M12/110	Vebrospeed Quartz	Dark Grey 703	LRV 11.86	Agreed 16/10/19	
	Wall finishes	Panelling	Laminate	Formica Laminate	Formica Macchiato F6932	LRV 15.8		
	Skirting	Stalls bar wall panelling	Stainless steel	Stainless steel as part of wall panelling	Stainless Steel			
	Wall finishes	Above Wall panelling	Paint M60/115	Refer to Theatresearch specification & schedule	Green NCS S 1040 G	LRV 50		
	Ceiling	Stalls bar ceiling (inc coffered sections and bar bulkheads)	Paint M60/110	Refer to Theatresearch specification & schedule	Lighter Yellow NCS S 0530Y10R. Internal areas of perforations to be painted black.	LRV 77		
	Doors	FOH circulation	Laminate	Formica Laminate	Formica Macchiato F6932	LRV 15.8	To be agreed	Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	FOH	Paint M60/130	Refer to Theatresearch specification & schedule	Light Grey NCS S 2002 Y50R	LRV 55		
	Bar counter and back bar	Stalls bar	By others	By others	By others		By others	Refer to Gastronorth design and specification

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Stalls lobbies & adj FOH circulation	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Stalls	Resin M12/110	Vebrospeed Quartz	Dark Grey 703	LRV 11.86	Agreed 16/10/19	
	Wall finishes	Walls above skirting level	Refer to Theatresearch specification & schedule	Refer to Theatresearch specification & schedule	Green NCS S 1040 G	LRV 50	Agreed 05/08/20	
	Skirting	All walls	Hardwood to match wall panelling as P20/135	Walnut	Walnut	LRV 15.8	Agreed 05/08/20	
	Ceiling	Stalls lobbies and adj FOH circulation	Painted plasterboard as Paint M60/110	Refer to Theatresearch specification & schedule	Lighter Yellow NCS S 0530Y10R	LRV 77	Agreed 05/08/20	
	Doors	FOH circulation areas	Laminate	Formica Laminate	Formica Macchiato F6932		To be agreed	Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	FOH	Refer to Theatresearch specification & schedule	Refer to Theatresearch specification & schedule	Light Grey NCS S 2002 Y50R	LRV 55		



WC'S - Link Ground Floor 153	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Link WCs and lobby's inc covered skirting	M50/157	Polyflor - Polysafe Stone	Deep Fossil 5082	LRV 22		As instructed as part of CE59488
	Flooring	Capping to covered skirting	M50	Gradus HCS48 / TC48 where tiled	Black	LRV 4.62		
	Wall finish	Link WC lobby	Paint as M60/115	Dulux Diamond Eggshell	Off white 27YY 77/042	LRV 77		As instructed as part of CE59488 - Details TBC by ATG / SBC
	Wall finish	All WCs	M40/TBC	Solux Fabien	Adam 5FAB467	LRV TBC		As instructed as part of CE59488
	Wall finish	All WCs	M40/TBC	Solux Fabien	Airdale 5FAB474	LRV TBC		As instructed as part of CE59488
	Wall finish	Link WCs	Paint M60/115	Dulux Diamond Eggshell	Off white 27YY 77/042	LRV 77		As instructed as part of CE59488
	Ceiling	Link WCs	Paint M60/110	Dulux Diamond Eggshell	Deep Rust 30YR 141365	LRV 14		As instructed as part of CE59488
	Ceiling	Link WCs bulkhead	Paint M60/110	Dulux Diamond Eggshell	Off white 27YY 77/042	LRV 77		As instructed as part of CE59488
	IPS	IPS Duct panels and flash gaps	K32/126/151/152	Formica SGL	F8853 Rural Oak	LRV 32.9		As instructed as part of CE59488
	WC Panel Cubicles	Cubicle partitions	K32/121	Formica SGL	F7949 Soft White	LRV 85.6		As instructed as part of CE59488
	WC Panel Cubicles	Cubicle doors	K32/121	Formica SGL	F7961 Fog	LRV 36.6		Client change 26.11.2020
	WC Panel Cubicles	WC pilasters	K32/121	Formica SGL	F7837 Graphite	LRV 10.8		As instructed as part of CE59488
	Vanity Unit	Male & Female WCs	N13/340	Formica SGL	F8853 Rural Oak	LRV 32.9		
	Vanity top	Male & Female WCs	N13/340	Formica SGL	Grey Dust F1787	LRV 37		
	Doors	FOH circulation areas	FOH Laminate	Formica	F5583 Steel Metal	LRV 22.9		Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	FOH	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Lobby & Acc WC - VIP 153	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	VIP Acc WC	As M50/158	Gerflor Taralay Impression Control	0523 Genova	LRV 40.9		
	Flooring	Capping to coved skirting	M50/744	Gradus HCS48	Stone	LRV 19.3		
	Flooring	Lobby	M50/111	Amico Signature	Wild Walnut AR0W7620	LRV 10		
	Wall finish	VIP Acc WC	Paint M60/115	Dulux Diamond Eggshell	Green 30GG 16/137	LRV 16		
	Wall finish	Lobby	Paint M60/115	Dulux Diamond Eggshell	Green 30GG 16/137	LRV 16		
	Skirting	Lobby	MDF as P20/200 painted as M60/130	Dulux Diamond Eggshell	White to match RAL 9010	LRV 84		
	Wall finish	VIP Acc WC	As M40/TBC	Solux Aria	Aria Green 5TAC034	LRV TBC		
	Wall finish	VIP Acc WC	As M40/TBC	Solux Aria	Aria Black 5TAC036	LRV TBC		
	Ceiling	Whole ceiling	As Paint M60/110	Dulux Trade Vinyl Matt	White to match RAL 9010	LRV 84		
	Doors	FOH circulation areas	Laminate	Formica Laminate	Formica Macchiato F6932	LRV 15.8		Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	FOH	Paint M60/130	Dulux Trade Gloss or Satin	White RAL 9010	LRV 84		

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



153 Kitchen	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Kitchen inc coved skirt to wall cladding transition strip	Slip resistant vinyl sheet M50/150 type 02A	Forbo Flooring Surestep R11	Charcoal 171992 R11	LRV6		
	Wall finishes	Kitchen and prep areas	Hygienic wall cladding as M50/150	Altro Whiterock	White	LRV 92		
	Ceiling	Kitchen and prep areas	New Moisture Resistant/ Hygiene Lay-in Grid Mineral Ceiling as K40/112	Ecophon Hygiene Foodtec A C3	White	LRV TBC		
	Doors	BOH	Laminate	Formica Laminate	Vintage Brush F8859	LRV 22		Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	BOH	Paint M60/130	Dulux Trade Gloss or Satin	RAL 7024	LRV 7		

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



BOH WCs & Shower Rooms	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	BOH WC	Vinyl sheet M50/151	Tarkett safetred ion contrast	Mid grey 26766006	LRV 36.9	Agreed 16/10/19	
	Flooring	Capping to covered skirting of BOH WC's	M50/744	Gradus HCS48 / TC48 where tiled	Granite	LRV 10.44		
	Flooring	Shower rooms	Vinyl sheet M50/159	Forbo safestep aqua lava	180592	LRV 10		
	Flooring	Capping to covered skirting of BOH Shower rooms	M50/744	Gradus HCS48 / TC48 where tiled	Black	LRV 4.62		
	Wall finish	BOH WC & shower room	Wall tiling M40/113	Solus Fabien	Agatha Gloss 5FAB111	LRV TBC		Horizontal brick bond, Anthracite grout
	Wall finish	Above tiling WC	Paint M60/115	Dulux trade diamond matt or satin	Light Grey 00NN 62/000	LRV 62	Agreed 16/10/19	
	Wall finish	Above tiling showers	Paint M60/115	Dulux trade mouldshield fungicidal eggshell	Light Grey 00NN 62/000	LRV 62	Agreed 16/10/19	
	Wall finish	Shower enclosure	Cladding M50/120	Altro Whiterock	Cesco 53	LRV 71	Agreed 05/08/20	
	Ceiling	All BOH WC and Shower areas	Paint M60/110		White RAL 9010	LRV 84		
	Grout	Wall tiling	Grout M40/114	Mapei Ultracolour plus	colour 114 Anthracite	N/A	Agreed 16/10/19	
	Vanity unit & counter top	All BOH vanity units	Vanity units N10/150 - laminate finish	Formica SGL	Graphite Twill F8829	LRV 11.3	Agreed 05/08/20	
	Doors	BOH	Laminate L20/411, 412, 413	Formica Laminate	Vintage Brush F8859	LRV 25		
	Door frames & architraves	BOH Doors	Paint M60/130	Dulux Trade Gloss or Satin	RAL 7024	LRV 7		



FOH WC's Generally	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	All FOH WCs & lobby's (NOT heritage, link or VIP)	Vinyl sheet M50/151	Gerflor Taralay Impression Control	0543 Cemento Brescia	LRV 32.5	Agreed 05/08/20	
	Flooring	Capping to vinyl	M50/744	Gradus HCS48 / TC48 where tiled	Black	LRV 4.62		
	Wall finish	WC area	Tiling M40/114	Solus Ceramics - Melbourne	Banyule 5PGY104 300 x 100	LRV TBC	Agreed 16/10/19	Installed horizontal brickbond
	Wall finish	WC area	Tiling M40/114	Solus Ceramics - Melbourne	Coburg 5PGY108 300 x 100	LRV TBC	Agreed 16/10/19	Installed as 1 course of tiling between covered skirting and main wall tiles
	Wall finish	Above tiling	Paint M60/115	Dulux Trade Diamond Eggshell	00YY 63/024 (off white)	LRV 63	Agreed 05/08/20	
	Wall finish	Lobby's	Paint M60/115	Dulux Trade Diamond Eggshell	00YY 63/024 (off white)	LRV 63	Agreed 05/08/20	
	Ceiling	All FOH WCs & lobby's (NOT heritage, link or VIP)	Paint M60/115	Dulux Trade Matt Vinyl	White to match RAL 9010	LRV 84		
	Grout	Wall tiling	Grout M40/114	Mapei Ultracolor plus	colour 114 Anthracite	N/A	Agreed 16/10/19	
	WC Panel cubicles	Cubicle doors, vanity fronts, IPS	Panel Cubicles K32/121, 126, 151, 152	Formica SGL	Graphite Twill F8829	LRV 11.3	Agreed 05/08/20	IPS flash gaps as panel colour
	WC Panel cubicles	WC cubicle partitions and pilasters	Panel Cubicles	Formica SGL	Soft White F7949	LRV 85.6	Agreed 05/08/20	
	Vanity top	All FOH WC's	Sanitary fittings N13/340	Formica SGL	Graphite Twill F8829	LRV 85.6	Agreed 05/08/20	
	Doors	FOH circulation areas	Laminate	Formica Laminate	Formica Macchiato F6932		To be agreed	Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	FOH	Refer to Theatresearch specification & schedule	Refer to Theatresearch specification & schedule	Light Grey NCS S 2002 Y50R	LRV 55		

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



FOH Male Heritage WC	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Heritage WC (Only male)	Existing terrazzo	N/a	N/a		Agreed 16/10/19	Cleaned, ground and made good where applicable
	Wall finish	Heritage WC (Only male)	Existing terrazzo	N/a	N/a		Agreed 16/10/19	Cleaned, ground and made good where applicable
	Wall finish	Above terrazzo	Paint as Paint M60/115	Dulux trade diamond matt or satin	00NN 62/000 (Light grey)	LRV 62	TBC	To be agreed at next finishes meeting
	WC cubicles & lobby divider	WC & lobby partitions	Panel cubicles as K32/123	Existing terrazzo	N/a		Agreed 16/10/19	Cleaned, ground and made good where applicable. Dividers to be suitably re-fixed and restrained.
	Cubicle doors	Doors to front of original terrazzo dividers	N/A - Original retained	N/A - Original retained	Refer to Theatresearch specification & schedule			Original doors to be re-instated subject to condition or replica doors to match original
	Cubicle dividers	Cubicle dividers	Original reinstated and suitably secured - if this is not possible new dividers to match existing as M12/111	Original reinstated and suitably secured - if this is not possible new dividers to match existing as M12/111	Colour to match original			Terrazzo dividers are to have supporting pilasters and suitable base fix as req. to ensure robust fixing is achieved



Lower Circle Bar	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Lower Circle Bar & Associated Circulation	Linoleum	Tarkett Veneto Sicuro xF R10	Silk 625	LRV 31		Main body to match circulation routes set within a feature border to reflect historic terrazzo detailing
	Flooring	Feature inlay to Lower Circle Bar & Associated Circulation	Linoleum	Tarkett Veneto Sicuro xF R10	Chocolate 632 with black seams	LRV 9		Main body to circulation routes set within a feature border to reflect historic terrazzo detailing
	Flooring	Bar area inc. coved skirting	Slip resistant vinyl sheet M50/150 type 02A	Forbo Flooring Surestep R11	171992 R11		Agreed 16/10/19	
	Wall finish	Panelling	Laminate	Formica	Formica Macchiato F6932	LRV 15.8		
	Wall finish	Above wall panelling	Paint M60/115	Refer to Theatresearch specification & schedule	Green NCS S 1040 G	LRV 50		
	Wall finish	Window elevation	Paint M60/115	Refer to Theatresearch specification & schedule	Green NCS S 1040 G	LRV 50	To be agreed	
	Wall finish	Walls of back bar and adjacent stores	Paint M60/115	Dulux trade diamond eggshell	Green NCS S 1040 G	LRV 50		
	Wall finish	Walls and upstands of plinths to glass wash, freezers	Hygienic wall cladding	Altro Whiterock	White			
	Skirting	Circle bar	Hardwood P20/125	Contractors choice	Walnut	LRV 15.8	Agreed 16/10/19	
	Ceiling	Main body of ceiling (flat areas)	Paint M60/110	Refer to Theatresearch specification & schedule	Lighter Yellow NCS S 0530Y10R	LRV 77		
	Ceiling	Oval coffers, rectangular coffer & ceiling features	Paint M60/110	Refer to Theatresearch specification & schedule	Varies - Green , Lighter Yellow , Deep Yellow, refer Theatresearch specification & schedule	Varies		Refer to Theatresearch drawings for colour requirements to ceiling features.
	Ceiling	Bar bulkhead, ceiling to bar area & adjacent stores	Paint M60/110	Refer to Theatresearch specification & schedule	Green NCS S 1040 G to vertical surfaces. Lighter Yellow NCS S 0530Y10R to Horizontal surfaces of ceiling	Varies		
	Lower Circle Bar	By others	By others	By others	Refer to Gastronorth design and specification		Agreed 16/10/19	
	Doors	FOH circulation areas	Laminate	Formica Laminate	Formica Macchiato F6932		To be agreed	Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	FOH	Refer to Theatresearch specification & schedule	Refer to Theatresearch specification & schedule	Light Grey NCS S 2002 Y50R	LRV 55		Confirmation of frame / architrave colour required to FOH doors

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Green Room & Dressing Rooms	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Green room & dressing room flooring inc coved skirting	Vinyl sheet M50/151	Tarkett safetred ion contrast	Mid grey 26766006	LRV 36.9	Agreed 16/10/19	
	Flooring	Capping to coved vinyl skirting	M50/744	Gradus HCS48	Granite	LRV 10.44		
	Wall finish	Green room & dressing room walls.	Paint M60/115	Dulux trade diamond matt or satin	Grey NCS 2002-Y50R	LRV 55		Client change 23.10.2020
	Kitchen Units	Green room & dressing room	contractors choice	Contractors choice	High gloss, white flat slab		Agreed 05/08/20	
	Kitchen Counter	Kitchen Units	contractors choice	Howdens 38mm bullnose	Light stone WOK0160			
	Dressing Unit Counter	Dressing rooms	contractors choice	Howdens 38mm bullnose	Light stone WOK0160			Refer to drawing K00186-SPACE-ZZ-XX-DR-A-70-0001
	Dressing Unit Back Panel & Hat Shelf	Dressing rooms	Laminate	Formica	Fox F1994	LRV 42.4		Refer to drawing K00186-SPACE-ZZ-XX-DR-A-70-0001
	Splashbacks	Dressing room sinks	Hygienic wall cladding	Altro whiterock	Cesco 53	LRV 71	Agreed 05/08/20	
	Ceilings	Dressing rooms	Lay in grid as K40/114	Armstrong	Ultima op+ 7678M			
	Blinds	Window blinds	N10/2450	Contractors Choice	Dark Grey	N/A	Agreed 05/08/20	
	Doors	BOH	Laminate	Formica Laminate	Vintage Brush F8859	LRV 25		Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	BOH	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Annexe Office	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	153 office and GM office	Carpet tile M50/131	Paragon Greda	8775 Ghost Machine	LRV TBC		500 x 500mm
	Wall finish	153 office and GM office	Matt Paint M60/115	Dulux Diamond Matt	Grey NCS 2002-Y50R	LRV 55		Client change 23.10.2020
	Ceiling	153 office and GM office	Lay in grid K40/114		Self colour: White			
	Skirting	Walls	P20/200 painted as M60/130	Dulux Trade Gloss or Satin	RAL 7024	LRV 7	Agreed 05/08/20	
	Doors	BOH	Laminate	Formica Laminate	Vintage Brush F8859	LRV 25		Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	BOH	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Dimmer Room & AV room off gallery	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Floor	Antistatic vinyl as M50/154	Tarkett Primo SD	Dark cool grey 0563	LRV 15		
	Wall finish	Walls	Matt Paint M60/115	Dulux Diamond Matt	Grey NCS 2002-Y50R	LRV 55		Client change 23.10.2020
	Ceiling	No ceiling						
	Skirting	Walls	P20/200 painted as M60/130	Dulux Trade Gloss or Satin	RAL 7024	LRV 7		
	Doors	BOH	Laminate	Formica Laminate	Vintage Brush F8859			Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	BOH	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Tech, Workshop Store, Band Room & below stage crossover	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Floors generally	Epoxy paint M60/182	Armstead Trade Anti slip	RAL 7024	LRV 7	Agreed 05/08/20	
	Walls	Bandroom, workshop & perimeter walls as indicated on finishes plan	Paint M60/115	Dulux Diamond Eggshell	Above dado Black 1 inch strip dado. Below Dado - NCS S 3560G10Y / Above Dado - NCS S 1015Y		Agreed 05/08/20	Works started on site. Scheme to remain as is.
	Ceiling	Ceilings where applicable	Paint M60/110	Dulux Trade Matt Vinyl	White RAL 9010	LRV 84		
	Skirtings	Walls generally	P20/200 painted as M60/130					Confirmation of colour required 26.10.20
	Doors	BOH	Laminate	Formica Laminate	Vintage Brush F8859			Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	BOH	Paint M60/130	Dulux Trade Gloss or Satin	RAL 7024	LRV 7		Confirmation of colour required 26.10.20

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Stage & Fly Tower	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Stage - pre-shrunk hardboard	K11/760	2 Coats of Black emulsion to sacrificial hardboard layer on stage	Black RAL 9017	LRV 2		
	Flooring	Gallery floors	Rubber flooring on steel plate or plywood substrate M50/156	Rubbertech Gymnasium EPDM floor roll	Black/Grey (main body black with grey fleck)	LRV TBC		
	Wall finish	Rear face (stage side) of Proscenium	Paint M60/115	Dulux Diamond Eggshell	Off-white		Agreed 05/08/20	Refer to Theatresearch specification & schedule
	Wall finish	All fly tower wall (excluding proscenium)	Paint M60/115	Dulux Diamond Eggshell	Black RAL 9017	LRV 2	Agreed 05/08/20	Refer to Theatresearch specification & schedule
	Wall finish	All walls above Grid	Paint M60/115	Dulux Diamond Eggshell	Off-white		Agreed 05/08/20	Refer to Theatresearch specification & schedule
	Gallery balustrades	Plywood facing to gallery balustrades	Paint M60/115	Dulux Diamond Eggshell	Black RAL 9017	LRV 2	Agreed 05/08/20	Refer to Theatresearch specification & schedule
	Doors (Proscenium)	BOH	Laminate	Formica Laminate	Vintage Brush F8859	LRV 25		Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Doors (Stage Left)	BOH	Laminate	Formica Laminate	Diamond Black F2253	LRV 2		
	Door frames & architraves	BOH	Paint M60/130	Dulux Trade Gloss or Satin	RAL 7024 to Vintage Brush doors, RAL 9017 to Diamond Black Doors (Stage)			Stage access from annexe to have Luminescent ironmongery.

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Orchestra Pit	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Pit lift floor	Floor sealer only	Refer to S.E. specification	N/A		Agreed 05/08/20	
	Flooring	Pit lift floor	Removable pre-shrunk hardboard to (match stage finish) K11/760	2 Coats of Black emulsion to sacrificial hardboard layer on stage	Black RAL 9017	LRV 2		
	Wall finish	Curved wall and side flanking walls	Paint M60/115	Dulux Diamond Eggshell	Black RAL 9017	LRV 2	Agreed 05/08/20	Refer to Theatresearch specification & schedule
	Wall finish	Stage front T&G effect boarding	Paint M60/115	Refer to Theatresearch specification & schedule	Dark Brown NCS S 5040Y10R	LRV 14	Agreed 05/08/20	Refer to Theatresearch specification & schedule
	Doors	FOH	Paint grade door painted as M60/130	Refer to Theatresearch specification & schedule	Dark Brown NCS S 5040Y10R	LRV 14	Agreed 05/08/20	Theatresearch to advise
	Door frames & architraves	FOH	Paint M60/130	Refer to Theatresearch specification & schedule	Dark Brown NCS S 5040Y10R	LRV 14		

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Annexe Plant Areas	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Floor generally	no finish - omitted	none	none			
	Walls	Walls generally	Matt Paint M60/115	Dulux Diamond Matt	Grey NCS 2002-Y50R	LRV 55		Client change 23.10.2020
	Skirting	Walls generally	P20/200 painted as M60/130	Dulux Trade Gloss or Satin	White 50YR 83/003	LRV 83		
	Ceilings	Ceilings generally	no ceiling - omitted	none	none			
	Doors	BOH	Laminate	Formica Laminate	Vintage Brush F8859	LRV 25		Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	BOH	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Annexe Laundry	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Floors generally	Epoxy paint M60/182	Armstead Trade Anti slip	RAL 7024	LRV 7	Agreed 05/08/20	
	Walls	Walls generally	Matt Paint M60/115	Dulux Diamond Matt	Grey NCS 2002-Y50R	LRV 55		Client change 23.10.2020
	Skirting	Walls generally	P20/200 painted as M60/130	Dulux Trade Gloss or Satin	RAL 7024	LRV 7		
	Ceiling	Ceiling generally	No ceiling					
	Doors	BOH	Laminate	Formica Laminate	Vintage Brush F8859	LRV 25		Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	BOH	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)
	Worktop	Laundry work area	contractors choice	Howdens 38mm bullnose	Light stone WOK0160	N/A		

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Globe Former projection room and adjacent areas	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring		No finishes					
	Walls		No finishes					
	Skirting		No finishes					
	Ceiling		No finishes					
	Doors	BOH	Laminate	Formica Laminate	Vintage Brush F8859			Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	BOH	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		ATG confirmed satin 01.12.2020 (verbal instruction on-site)

Project Title: Stockton Globe
 Project Number: 07682
 Revision: 006
 Date: 04.12.2020

Interior Finishes Schedule



Stores (Generally)	Item	Area	Specification	Product	Colour/ref.		Approved by ATG/SBC/Theatre Search Conservation officer	Notes
	Flooring	Floors generally	Epoxy paint M60/182	Dulux Floorshield	RAL 7024	LRV 7	Agreed 05/08/20	Colour TBA by SBC / Theatresearch
	Walls	Walls generally	Paint M60/115	Dulux Diamond Eggshell	White 50YR 83/003	LRV 83		
	Skirting	Walls generally	P20/200 painted as M60/130	Dulux Trade Gloss or Satin	White 50YR 83/003	LRV 83		
	Ceiling	Ceilings (where specified)	Paint M60/110	Dulux Trade Vinyl Matt	White 50YR 83/003	LRV 83		Note: not all stores have ceilings
	Doors	BOH	Laminate	Formica Laminate	Vintage Brush F8859	LRV 25		Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002
	Door frames & architraves	BOH	Paint M60/130	Dulux Trade Satin	RAL 7024	LRV 7		Refer to SPACE door schedule K00186-SPACE-ZZ-XX-SH-A-32-0002