



PROPOSED FRONT ELEVATION



PROPOSED SIDE ELEVATION



PROPOSED FRONT ELEVATION



012 Earth

GENERAL

All building materials to comply with BSS and used in accordance with the relevant Codes of Practice.

EXISTING WALLS

Strip back all existing render to existing brick wall and clean down to create dust free base.
RWP's temporarily removed and refitted after application of render

RENDER

Substrate Primer/Suction Control: Accrolor 2 – Substrate Primer
Base Coat/First Coat: TRADIBATARD GM – Incorporating VPI MESH 10
Mesh: VPI Mesh 10 – Stress Areas as standard – Full Mesh – Optional
Primer: SOLOFOND
Finish Coat/Top Coat: Crepilane T/TM – Fin (fine grain), Gros (coarse grain) – (Colour - Earth)

Rev.	Revision Note	Date
Proposed alterations to No. 2 Holywell Dene Road Holywell Northumberland - NE25 0LB		Scale 1:100
		Date 16.03.21
Title Proposed Elevations		Sheet No. 002