

The Commercial Kitchen Filtration Experts

Specification & EMAQ Report

Project: Dodo Pizza – High Street Cheltenham

Prepared for: Concept

Prepared by: Andrew James

Date: 29th March 2021

Contact details:

T: 01708755414

F: 01708721488

Email: andrew.james@purifiedair.com

Interpretation of Requirements

Following our conversation today I am pleased to provide an equipment selection for an odour control solution.

As with any project we get involved in we always recommend to our clients that they should closely follow the EMAQ guide for guidance on odour control equipment selection.

This ensures that what they propose will be in line with local authority's requirements and if the system is maintained correctly they will not exhaust nuisance odours leading to complaints from nearby residents.

With this in mind I carried out a risk assessment as detailed in Appendix 3 of the EMAQ Guide. Taking into consideration the level of discharge, proximity of receptors, size of kitchen and cooking type your project requires a high level of odour control to comply.

We have scored as below and as taken from Appendix 3: Risk Assessment for Odour;

Dispersion = 10

Proximity of receptors = 10

Size of kitchen = 1

Cooking type = 4

Total score = 25

The type of odour abatement system that complies is as below, taken directly from the EMAQ Guide and must be to a high level of control;

Odour arrestment plant performance

High level odour control may include:

1. Fine filtration or ESP followed by carbon filtration (carbon filters rated with a 0.2 – 0.4 residence time).
2. Fine filtration or ESP followed by UV ozone system to achieve the same level of control as 1.

CRITERIA	SCORE	SCORE	DETAILS
Dispersion	Very Poor	20	Low level discharge into courtyard or restriction on stack
	Poor	15	Not low level but below eaves, or discharge at below 10 m/s
	Moderate	10	Discharging 1m above eaves at 10 – 15 m/s
	Good	5	Discharging 1m above ridge at 15 m/s
Proximity of receptors	Close	10	Closest sensitive receptor less than 20m from kitchen discharge
	Medium	5	Closest sensitive receptor between 20 and 100m from kitchen discharge
	Far	1	Closest sensitive receptor more than 100m from kitchen discharge
Size of Kitchen	Large	5	More than 100 covers or large sized take away
	Medium	3	Between 30 and 100 covers or medium sized take away
	Small	1	Less than 30 covers or small sizes take away
Cooking type (odour and grease loading)	Very High	10	Pub (high level of fried food), fried chicken, burgers or fish and chips. Turkish, Middle Eastern, or any premises cooking with solid fuel.
	High	7	Vietnamese, Thai or Indian, Japanese, Chinese or Steakhouse
	Medium	4	Cantonese, Italian, French, Pizza (gas fired)
	Low	1	Most pubs, (no fried food, mainly reheating and sandwiches etc.), Tea rooms..

The System

The first stage of control should be our Pleated Panel Filters.

Our pleated panel filters are constructed using a core of pleated fibrous media designed specifically for use in air filtration. This is then thermally bonded onto a galvanised steel support mesh for maximum rigidity which is then fully bonded into a moisture resistant rigid white lined card frame.

These filters are used as stand-alone pre filter to absorb oil and grease.

After the pre filter our UVO1000 unit should be fitted; this uses UV technology by producing Ozone to neutralise the cooking odours.

This will be designed and installed with a 2 second dwell time ensuring the system designed meets EMAQ guidelines.



Unlike other UV-C systems, our UV-O units are located outside of the kitchen extract duct and are connected via a spigot and small diameter ducting.

The UV-O range uses UV-C technology to produce ozone and hydroxyl free radicals to oxidise cooking odours through a process of ozonolysis.

Although it is widely accepted that the best way to apply UV-C is directly in-line with the air stream itself, this can incur the problem of the lamps getting dirty and thus greatly reducing their effectiveness.

With our UV-O units the air flow does not come from the exhaust duct but from the ambient air around the unit, which is filtered on entry. This means that it is able to provide a uniform supply of ozone and hydroxyl free radicals into the extract system with an extremely low pressure loss. As with our UV-C range, for optimum performance we would recommend 2 seconds of dwell time to allow the ozone to work effectively upon the malodorous gasses within the duct.

As you can see the system that has been specified is in line with EMAQ guidance.

Specification

2No 594 x 594 x 95mm Pleated Panel Filters in a side access casing.

1No. UV-O 1000 Unit.

Specification per unit

Air Volume Max	2m ³ /s
Electrical Supply	220/240V 50HV 1ph
Power Consumption	700W
Weight	50 Kg
Min/Max Working Temperature	4/56°C
Max Relative Humidity	75%

