

Project The Toll Centre, Burntisland - Burntisland Playgroup				Job no. 2020-P098	
Calcs for Entrance Building - Soakaway Design				Start page no./Revision 1 0	
Calcs by RIG	Calcs date 09/02/2021	Checked by RIG	Checked date 05/04/21	Approved by RIG	Approved date 05/04/21

## SOAKAWAY DESIGN

### In accordance with BRE Digest 365 - Soakaway design

Tedds calculation version 2.0.03

#### Design rainfall intensity

Location of catchment area	Other
Impermeable area drained to the system	A = <b>68.0</b> m <sup>2</sup>
Return period	Period = <b>30</b> yr
Ratio 60 min to 2 day rainfall of 5 yr return period	r = <b>0.300</b>
5-year return period rainfall of 60 minutes duration	M5_60min = <b>14.5</b> mm
Increase of rainfall intensity due to global warming	p <sub>climate</sub> = <b>20</b> %

#### Soakaway / infiltration trench details

Soakaway type	Rectangular
Minimum depth of pit (below incoming invert)	d = <b>1000</b> mm
Width of pit	w = <b>1750</b> mm
Length of pit	l = <b>3656</b> mm
Percentage free volume	V <sub>free</sub> = <b>30</b> %
Soil infiltration rate	f = <b>10.0</b> × 10 <sup>-6</sup> m/s
Wetted area of pit 50% full	a <sub>s50</sub> = l × d + w × d = <b>5405871</b> mm <sup>2</sup>

#### Table equations

Inflow (cl.3.3.1)	I = M30 × A
Outflow (cl.3.3.2)	O = a <sub>s50</sub> × f × D
Storage (cl.3.3.3)	S = I - O

Duration, D (min)	Growth factor Z1	M5 rainfalls (mm)	Growth factor Z2	30 year rainfall, M30 (mm)	Inflow (m <sup>3</sup> )	Outflow (m <sup>3</sup> )	Storage required (m <sup>3</sup> )
5	0.34;	5.9;	1.45;	8.6;	0.58;	0.02;	0.57
10	0.49;	8.5;	1.48;	12.6;	0.86;	0.03;	0.82
15	0.59;	10.3;	1.49;	15.3;	1.04;	0.05;	0.99
30	0.77;	13.4;	1.49;	20.0;	1.36;	0.10;	1.26
60	1.00;	17.4;	1.48;	25.8;	1.76;	0.19;	1.56
120	1.25;	21.8;	1.47;	31.9;	2.17;	0.39;	1.78
240	1.57;	27.3;	1.45;	39.7;	2.70;	0.78;	1.92
360	1.78;	31.0;	1.44;	44.6;	3.03;	1.17;	1.87
600	2.12;	36.9;	1.42;	52.5;	3.57;	1.95;	1.62
1440	2.84;	49.4;	1.38;	68.0;	4.62;	4.67;	0.00

Required storage volume S<sub>req</sub> = **1.92** m<sup>3</sup>

Soakaway storage volume S<sub>act</sub> = l × d × w × V<sub>free</sub> = **1.92** m<sup>3</sup>

**PASS - Soakaway storage volume**

Time for emptying soakaway to half volume t<sub>s50</sub> = S<sub>req</sub> × 0.5 / (a<sub>s50</sub> × f) = 4hr 55min 59s

**PASS - Soakaway discharge time less than or equal to 24 hours**