

FORUM ENERGY CONSULTANTS.

LEMANIS HOUSE, STONE STREET, LYMPNE, Nr HYTHE, KENT CT21 4JN.
TEL 01303 260656 E-MAIL : forumenergy@btinternet.com
Website : www.forumenergyconsultants.co.uk

ELMHURST ACCREDITED OCDEA. ATTMA ACCREDITED AIR PRESSURE TESTING ORG.

Mr S Latham
Design and Build Services
2 Colkins Cottages, Clockhouse, Boughton,
Faversham,
Kent, ME13 9LU.

P.R. Correspondence?	
REF:	
15 MAR 2021	Init'l
CHK. DET. £	
DRAWN	

Dear Simon,

8th January 2021.

**Re : New Dwelling, Site Rear of 7 Horselees Road, Boughton, Faversham, Kent ME13 9TG
Planning – 50 % DER / TER Reduction, Building Regulations, Part L1A Compliance Requirements.**

I have now completed a draft SAP Rating on the dwelling.

The dwelling has been assessed under Part L1A 2013 and SAP 2012. The DER must be 50 % improved when compared to the TER as a requirement of Planning.

The draft results for the proposed dwelling are as follows ;

Ground Floor. 150 mm ground bearing concrete slab and DPM
 150 mm Celotex Insulation and separating layer
 65 mm screed.

All floor 'U' values are calculated on each individual floor perimeter length. The Floor 'U' value is 0.14 w/m2k.

External Walls 103 mm Brickwork
Brick Outer 100 mm cavity filled with 100 mm Dritherm 32 batts
 (thermal conductivity 0.032)
 100 mm Thermalite Shield Blocks (thermal conductivity 0.15)
 13 mm Plaster.

'U' value calculated as being 0.26 w/m2k.

NEW BUILD SAP / DER / TER RATINGS. PEA's & EPC's. PART L1A & B CALCULATIONS. ENERGY SURVEYS.

AIR PRESSURE TESTING. (ATTMA REGISTERED)

PRINCIPAL : Mr A Ironmonger MCIAT, (Chartered Architectural Technologist) ELMHURST Accredited OCDEA, ATTMA.ORG.

Boarded Upper Timber Frame Walls	<p>Boarding battens and vented construction over 65 mm Celotex insulation over 12 mm external quality ply 100 mm timber studs fully filled with Rigid Mineral wool batts 12.5 mm moisture resistant plasterboard and skim.</p> <p>'U' value calculated as being 0.19 w/m²k.</p>
Exposed Upper Floor	<p>22 mm chipboard flooring 200 mm Mineral wool insulation between joists 12.5 mm + 15 mm Plasterboard & skim 12 mm ply soffit board.</p> <p>'U' value calculated as being 0.21 w/m²k.</p>
Ashlar Walls	<p>100 mm Celotex insulation between studs and 50 mm Celotex across face of studs with 12.5 mm duplex grade plasterboard and skim finish.</p> <p>'U' value calculated as being 0.18 w/m²k.</p>
Windows and External Doors	<p>Timber Framed, double glazed, manufacturers written declaration for 'U' value of 1.4 w/m²k for Windows and 1.4 w/m²k for the doors to be provided / confirmed.</p>
Rooflights	<p>Proprietary manufactured Velux rooflights from their standard range achieve a U value of 1.30 w/m²k.</p>
Main Flat Ceiling Line.	<p>200 mm Knauf Earthwool (0.040 conductivity) between ties 250 mm Knauf Earthwool (0.040 conductivity) over butted tightly In opposite direction. 12.5 mm duplex plasterboard and skim finish.</p> <p>'U' value calculated as being 0.10 w/m²k.</p>
Raking ceiling	<p>100 mm Celotex insulation between rafters 50 mm Celotex under rafters 12.5 mm duplex plasterboard and skim</p> <p>'U' value calculated as being 0.18 w/m²k.</p>

Design Air
Permeability

This is the Designers responsibility to specify, I have included the lower rate of 5.

Design Air Permeability Rate 5m³ / hm² (@50 Pa).

The dwelling will require an Air Pressure Test at completion.

Thermal
Bridging

Assessors can no longer simply state 'Robust Details' and stipulate the 'Y' value.

We either enter a default 'Y' value of 0.15 which is high and detrimental to the overall result or the *client will need to confirm in writing* that
'Approved Accredited Construction Details' will be fully adopted for each Thermal Bridging junction.

As a result, I have calculated the 'Y' value and the figure calculated is 0.076 w/m²k.

A sample letter will be produced and forwarded for your use with the declaration.

Low Energy
Lighting

Low energy light fittings are defined as those with lamps of greater than 45 lumens per circuit watt and output greater than 400 lumens.

These do not need to be dedicated fittings, IE standard fittings supplied with low energy lamps will comply.

I have included for 100 % low energy lighting.

Extractor Fans

Normal extractor fans included for.

Heating

Normal Electrical Tariff
Mains Gas fired Condensing Combi Boiler with a minimum SEDBUK value of 89 %
Boiler Interlock
Delayed start room Thermostats
Radiators fitted with TRV's
Time and Temperature Zone Controls required

Secondary Heating	None specified.
Hot Water	Hot water via Combination boiler
Internal Water Use.	Maximum internal use not to exceed 110 litres per person per Day.
Photo Voltaic Array	To South East orientated roof slope. (45 degrees) 2.20 kWp loading - (approx. 8no panels) Metering and inverted connected to dwelling electric intake.

With all of the above specifications included the draft results for the dwelling are as follows ;

Rear of 7 Horselees	SAP	92.	EI	92.	
	DER	10.21	TER	21.67	= 52.88 % reduction
	DFEE	60.47	TFEE	69.12	

The dwelling Passes the requirements of Part L1A and SAP.
The dwelling achieves a 52.88 % reduction in DER set against TER therefore complies with Planning Policy requirements.

Design Final. (for information but a requirement)

In order to issue the Design Final Documentation, I require a written letter confirming the use of the 'Accredited Construction Details'.

(drafted attached).

I also require a copy of the Architectural scheme drawings with all of the specifications indicated within this document included for.

I will then upon receipt of the information, print out the necessary documentation to indicate Building control submission compliance. I will also forward a copy in PDF format for your own use.

You will then also need to forward these to Building Control, together with copies of your upgraded drawings and other written information.

Information will remain on computer memory until required.

Should you like to discuss the enclosed please do not hesitate to contact me at your earliest convenience.

Completion. (for information but a requirement)

At completion and prior to upgrading to 'as built' and the issue of the EPC, I will require the following ;

Written confirmation that *'the dwelling is constructed in accordance with the Architectural scheme drawings and any recommendations made by Forum Energy Consultants'*.

Written confirmation from the builder that, *' the specific junctions have been built in accordance with the Accredited Construction Details and that the associated checklists have been completed'*.

Or advice on alterations to the Design Stage assessed information for upgrading.

A Certified copy of the Air Pressure Test Results,

Boiler make & model as installed to dwelling.

Confirmation of MCS Certification and details of the PV loading as installed.
The correct address and Post Code for EPC lodgement.

Yours sincerely,

A. Ironmonger.

Mr Alan Ironmonger. MCIAT, Elmhurst Accredited OCDEA. ATTMA. ORG.
Forum Energy Consultants.

BASIC COMPLIANCE REPORT

Calculation Type: New Build (As Designed)

Property Reference	Rear of 7 horselees	Issued on Date	08/01/2021
Assessment Reference	Rear of 7 Horselees	Prop Type Ref	

Property	Rear of 7 horselees, Horselees Road, Boughton, Faversham, Kent, ME13
----------	--

SAP Rating	92 A	DER	10.21	TER	21.67
Environmental	92 A	% DER<TER	52.88		
CO ₂ Emissions (t/year)	0.51	DFEE	60.47	TFEE	69.12
General Requirements Compliance	Pass	% DFEE<TFEE	12.51		

Assessor Details	Mr. Alan Ironmonger, Forum Energy Consultants, Tel: 01303 260656, forumenergy@btinternet.com	Assessor ID	L609-0001
------------------	--	-------------	-----------

Client	
--------	--

SUMMARY FOR INPUT DATA FOR New Build (As Designed)

Criterion 1 – Achieving the TER and TFEE rate

1a TER and DER

Fuel for main heating	Mains gas
Fuel factor	1.00 (mains gas)
Target Carbon Dioxide Emission Rate (TER)	21.67 kgCO ₂ /m ²
Dwelling Carbon Dioxide Emission Rate (DER)	10.21 kgCO ₂ /m ²
	-11.46 (-52.9%) kgCO ₂ /m ²

Pass

1b TFEE and DFEE

Target Fabric Energy Efficiency (TFEE)	69.12 kWh/m ² /yr
Dwelling Fabric Energy Efficiency (DFEE)	60.47 kWh/m ² /yr
	-8.6 (-12.4%) kWh/m ² /yr

Pass

Criterion 2 – Limits on design flexibility

Limiting Fabric Standards

2 Fabric U-values

Element	Average	Highest	
External wall	0.21 (max. 0.30)	0.26 (max. 0.70)	Pass
Floor	0.21 (max. 0.25)	0.21 (max. 0.70)	Pass
Roof	0.17 (max. 0.20)	0.18 (max. 0.35)	Pass
Openings	1.39 (max. 2.00)	1.40 (max. 3.30)	Pass

2a Thermal bridging

Thermal bridging calculated from linear thermal transmittances for each junction

3 Air permeability

Air permeability at 50 pascals	5.00 (design value)
Maximum	10.0

Pass

Limiting System Efficiencies

4 Heating efficiency

Main heating system	Boiler system with radiators or underfloor - Mains gas Data from manufacturer X X Combi boiler Efficiency: 89% Minimum: 88%
---------------------	--

Pass

BASIC COMPLIANCE REPORT

Calculation Type: New Build (As Designed)

Secondary heating system

None

5 Cylinder insulation

Hot water storage

No cylinder

6 Controls

Space heating controls

Time and temperature zone control

Pass

Hot water controls

No cylinder

Boiler interlock

Yes

Pass

7 Low energy lights

Percentage of fixed lights with low-energy fittings

91

%

Minimum

75

%

Pass

8 Mechanical ventilation

Not applicable

Criterion 3 – Limiting the effects of heat gains in summer

9 Summertime temperature

Overheating risk (South East England)

Slight

Pass

Based on:

Overshading

Average

Windows facing North East

8.78 m², Overhang width less than twice window, ratio 0.05

Windows facing South West

0.54 m², Overhang width less than twice window, ratio 0.05

Windows facing North West

2.48 m², Overhang width less than twice window, ratio 0.05

Air change rate

4.00 ach

Blinds/curtains

None

Criterion 4 – Building performance consistent with DER and DFEE rate

Air permeability and pressure testing

3 Air permeability

Air permeability at 50 pascals

5.00 (design value)

Maximum

10.0

Pass

10 Key features

Roof U-value

0.10

W/m²K

Photovoltaic array

2.20

kW

This report has not been submitted through the Elmhurst Energy members' portal, therefore results are subject to change when the dwelling is completed.