


MATERIAL FINISHES

- 1 Bitumen Road surface
 - 2 Tarmac Pavement
 - Tarred finish with coloured chip, Golden
 - Proposed Tree Planting/ Landscaping
 - 1200 x 1200 entrance platt with 900 path in concrete slabs
 - Boundary Type A - 1.8m High walling roughcast with base course in brick finish "Ibstock", "Hadrian buff" buff pointing with grey precast saddle back precast concrete cope.
 - Boundary Type B - 1.8m High brick walling "Ibstock", "Hadrian Buff" buff pointing with grey precast saddle back precast concrete cope.
 - Boundary Type C - 1.8m High standard timber fencing
 - Boundary Type 3 - Box hedging 700mm high
- All driveways to be grey - tarmac finish unless specified on plan.
Refer to landscape drawings for landscape information.



HALLIDAY FRASER MUNRO
CHARTERED ARCHITECTS & PLANNING CONSULTANTS

Project:
N2, N13 parcels
Countesswells, Aberdeen

Client:
Barratt North Scotland

Title:
Boundary Treatments and Material Finishes

Document Reference					
Revision	Description	Date	Author	Checked	Number
003	11642 - HFM - ZZ - ZZ - DR - P - (00)				

Drawing Status: **Planning** Revision: _____
Scale: 1:1000 @ A1 / 1:2000 @ A3 Date: **March 2021**

Do not scale this drawing.
Ordnance Survey material is reproduced with the permission of the controller of her Majesty's Stationery Office Crown Copyright reserved.
The copyright of this drawing subsists in Halliday Fraser Munro Ltd.

Registered Office:
8 Victoria Street,
Aberdeen, AB10 1XB
T: 01224 388 700
E: info@hfm.co.uk
W: hfm.co.uk

External Finishes

Material	Palette - 01 BASECOURSE + MINOR FEATURES	Palette - 02 BASECOURSE + FEATURES
	(A)	(B)
Render	Drydash - Nordic White Chip on white by "Stone Pack"	Drydash - Nordic White Chip on white by "Stone Pack"
Roof tiles	"Russell" "Highland" Smooth Grey	"Russell" "Highland" Smooth Grey
Stone	Brickwork Base and Minor Features "Ibstock" "Hadrian Buff" with Buff pointing	Brickwork Base & Features "Ibstock" "Hadrian Buff" with Buff pointing
Window sills	PC conc. in Grey	PC conc. in Grey
Windows	Grey uPVC	Grey uPVC
Soffits	Grey uPVC	Grey uPVC
RW goods	Black uPVC	Black uPVC
Front door	Grey uPVC	Grey uPVC
Back door	Grey uPVC	Grey uPVC
Garage door	Grey uPVC	Grey uPVC