



Copyright of this document is reserved by Dougall Baillie Associates Ltd.
DO NOT scale from this drawing

- Notes:
1. ALL CONSTRUCTION DETAILS TO COMPLY WITH CLACKMANNANSHIRE COUNCIL, ROADS DEVELOPMENT GUIDE AND THE DESIGN MANUAL FOR ROADS AND BRIDGES.
 2. THE SPECIFICATION FOR THIS PROJECT IS THE SPECIFICATION FOR HIGHWAY WORKS.
 3. ALL DRAINAGE TO COMPLY WITH 'SEWERS FOR SCOTLAND 3'
 4. ALL STORM AND FOUL SEWERS TO BE SET ON COMPLETION AND CCTV INSPECTION CARRIED OUT.
 5. ALL GULLEY TAILS TO BE 150mm DIAMETER.
 6. ALL DISCONNECTOR PIPEWORK TO BE 150 DIA LAID AT A MINIMUM GRADE OF 1 IN 60.
 7. DISCONNECTOR MANHOLE SPECIFICATION TO BE AGREED WITH BUILDING CONTROL, SCOTTISH WATER AND NHC PRIOR TO WORKS COMMENCEMENT.

- LEGEND
- PROPOSED FOUL SEWER NETWORK 1: 71No PLOTS DRAINING TO SCOTTISH WATER APPROVED FOUL PUMPING STATION TO THE SOUTH. 19No PLOTS PHASE 9/10, 37No PLOTS PHASE 8b & 15No PLOTS PHASE 8a (SCOTTISH WATER ADOPTABLE)
 - PROPOSED FOUL SEWER NETWORK 2: (SCOTTISH WATER ADOPTABLE)
 - PROPOSED FOUL SEWER NETWORK 3: (SCOTTISH WATER ADOPTABLE)
 - PROPOSED STORM NETWORK NUMBER 1 DRAINING TO APPROVED SUDS FEATURE (SCOTTISH WATER ADOPTABLE)
 - PROPOSED STORM NETWORK NUMBER 2 DRAINING TO NEW SUDS FEATURE & FLOWS RESTRICTED TO 5litres/sec. (SCOTTISH WATER ADOPTABLE)
 - EXISTING SCOTTISH WATER STORM WATER SEWER
 - EXISTING SCOTTISH WATER FOUL WATER SEWER
 - EXISTING SCOTTISH WATER COMBINED SEWER
 - EXISTING SCOTTISH WATER STORM WATER TRUNK SEWER

Phase 1b

Phase 1b

FOR DETAILED PHASE 7 DRAINAGE REFER TO DRAWING NUMBER 15120-500-100revZ.

FOR DETAILED PHASE 8b DRAINAGE REFER TO DRAWING NUMBER 18015-500-100.

FOR DETAILED PHASE 8a DRAINAGE REFER TO DRAWING NUMBER 18015-501-100.

APPROVED PUMP STATION FOR 71No PLOTS TOTAL, 15No (PHASE 8a), 37No (PHASE 8b) & 19No (PHASE 9/10). SCOTTISH WATER REF 771684

APPROVED SUDS FEATURE TO THE SOUTH TAKING CONTRIBUTING FLOWS FROM PHASE 7 (1.118ha), PHASE 8a (0.373ha), PHASE 8b (0.789ha) & PHASE 9/10 (0.882ha). TOTAL CONTRIBUTING AREA 3.162ha.

APPROVED SUDS FEATURE DRG REF. 15120-500-100revZ (AS BUILT). SCOTTISH WATER APPROVAL REF. 725768.

B	SITE LAYOUT UPDATED TO SUIT ARCHITECTS REVISED REV G SITE PLAN.	S.P.	P.R.
A	SITE LAYOUT UPDATED TO SUIT ARCHITECTS REVISED REV G SITE PLAN.	S.P.	P.R.
Rev:	Checked:	Date:	Date:
Client: ALLANWATER DEVELOPMENTS LTD			
Project: ALLOA PARK, PHASE 9 & 10			
Drawing Title: PRELIMINARY DRAINAGE LAYOUT			
Drawn:	S.P.	Checked:	P.R.
Date:	10.08.20	Date:	10.08.20
Scale:	1:500	Dep. No.:	2013-500-100
Drawn Status:	PRELIMINARY		
Dougall Baillie Associates 1 Glenfield Road, Arbroath East Kilbride G74 0RA T: 01335 354600 F: 01335 321991 E: enquiries@dougallbaillie.com W: www.dougallbaillie.com			

