

Kennel Building Specification



Kennel Building Specifications (Example of appearance)

- Approximate dimensions of unit are 12' depth x 20' wide
- 2.3 " Heavy duty framework
- 9mm Rebate allowing the timber to expand and contract through weather systems
- Ex 16.5mm high quality tanalised shiplap for maximum strength
- Heavy duty felted roof constructed of Ex 16mm x 125mm tongue & groove shiplap for maximum strength
- Floor will have installed underfloor heating.
- Pedestrian access into Kennel
- 2 latches per door with padlock facility for added security
- Pop hole into Kennel (approx. size 62cm H x 35 cm W) with sliding hatch
- Anti-chew insulation system consisting of 30mm polystyrene and 2mm PVC with wall thickness to 45mm. No exposed timber to give extreme anti-chew finish. Hygienic and anti-bacterial properties also prevent odours.
- Deluxe hygienic washable floor using a 12mm phenolic coated board, non-slip and prevents odours building up.