

SITE TRAFFIC MANAGEMENT PLAN

LAND EAST OF 8 SPROATLEY ROAD, PRESTON EAST RIDING OF YORKSHIRE, HU12 8TT

The following items are mandatory on this site:

- Hours of site operation are 7:00am-6pm Mon-Fri; 8am – 1pm Saturday with no works taking place on Sundays or Bank Holidays.
- All site operatives, including sub-contractors personnel & visitors shall wear high visibility garments at all times on this site.
- Reversing movements of vehicles and plant on site where the operator/driver has restricted visibility shall only be undertaken under the guidance of a banksman.
- All mobile ride on plant will be fitted with mirrors to enable all-round vision.
- All plant and vehicles working on or delivering to site shall have fitted clean, undamaged reversing mirrors or operational CCTV reversing cameras.
- All plant on site shall have operational amber beacons at all times.
- Overhead obstructions shall be protected by the erection of high visibility goalposts and signage advising of the hazard.
- Excavations alongside or adjacent to traffic routes shall have physical barriers and appropriate signage warning of the hazard erected and maintained.
- Materials loading, unloading & storage areas shall have physical barriers erected around them to prevent unauthorised pedestrian access.
- Where site operatives are working on or immediately adjacent to traffic routes high visibility barriers and signage shall be erected to warn operators of plant and drivers of vehicles of the hazard.

The following item is to be undertaken where reasonably practicable:

- Any door or gate which is intended for use by pedestrians and which leads directly on to a traffic route shall be separated from the traffic route to enable pedestrians to see any approaching plant or vehicle from a place of safety.

Sketch attached showing the traffic routes and the location of loading, unloading and materials storage areas.

Where possible traffic routes should be designed to allow forward movement of plant and vehicles at all times.