



TYPE OF BUILDING - Agricultural

USE OF BUILDING - Feed bunkers and machinery store

ROOF CLADDING

Profile 6 Natural grey fibre cement sheets
 Profile 6 Natural grey fibre cement closed ridge cappings
 Natural grey plain wing fibre cement barge boards

GRP roof lights highlighted grey

GUTTERING

170mm Black PVC deep flow guttering
 110mm Black PVC circular downpipes

WALL CLADDING

Front of the building to be left open
 3no Bays at back, clad down to concrete panels
 3no Bays at back, clad down to finished floor level
 1no Gable end, clad down to concrete panels
 1no Gable end, clad down to finished floor level

Concrete panels - Natural grey colour

Cladding to be 0.5mm Plastisol coated box
 profiled steel sheets - Juniper Green colour

REV MARK	DESCRIPTION	By	Date	By	Date
		CREATED		CHECKED	
CLIENT: D B Gibbons (Construction) Ltd					
PROJECT: Feed bunkers and Machinery store building					
DRAWING TITLE: PROPOSED SIDE ELEVATIONS					
CONTRACT: Border Lines, Western Lane, West Harptree, Bristol, BS40 6EW					
DRAWN BY: afg			ISSUE DATE: 15.04.2021		
CONTRACT NO: ACJ7562			SCALE @ A2: 1:100		
DRAWING NO: G [3]			REVISION No.:		

