

WT5-LED-UWL

Colour	White, Cool
CCT (K)	5000K
Lumens/Watt @ Current - Test	119 lm/W
CRI (Colour Rendering Index)	85
Viewing Angle	115°
Lumens	3800lm
Face polished 316 stainless	150mm
Body Hard anodised	50mm
Light Emitting area	70mm Diameter
Lens Type	Flat, defused
RGB	30W-10W per colour
RGB cable	6-core 7-2-6a PVC insulation
RGB Lumens	Green 690lm Red 550lm Blue 650 Total 1890lm
WT-Driver (inline)	24V DC
Wattage	32W @ 780mA
Driver control via Signal wire	PWM (Dimming)
Fixing	Thread fit into 1.5BSP
Cable	3 cores, 0.5mm ² wire size, 16/0.2mm (Blue Cathode) (Brown Anode) Green (signal)

