

Odour Control system, GDK Eastbank Street, Southport, PR8 1DW

The system would comprise of a purpose made filter housing incorporating the following filter types: -

4no 592x592x350 CP4 Fire Rated Bag Filter

General Description

The CP4, fire rated range of bag filters are used widely in government buildings, hospitals and other sensitive areas. This grade of filter would capture 90% of the grease left within the system after the canopy baffle filters.

Meets NHS HTM03 Filter Specification, Filter Class EN779:2012 G4

4no 592x592x300 RP Compact Medium/Fine Ridgid HEPA bag filters

General Description

The F9 grade ridgid bag filter are used within this system to capture the heavy particles of smoke from the cooking process and are 80% efficient.

The final exhaust position of the extract system terminal would be at high level through a louver grille.

Yours Sincerely

