

SUNNY TRIPOWER 12000TL-US / 15000TL-US / 20000TL-US / 24000TL-US / 30000TL-US



STP 12000TL-US-10 / STP 15000TL-US-10 / STP 20000TL-US-10 / STP 24000TL-US-10 / STP 30000TL-US-10



RATED FOR
1000 V DC & 600 V DC
SYSTEMS



Design flexibility

- 1000 V DC or 600 V DC
- Two independent DC inputs
- 15° to 90° mounting angle range
- Detachable DC Connection Unit

System efficiency

- 98.0% CEC, 98.6% Peak
- 1000 V DC increases system efficiency
- OptiTrac Global Peak MPPT

Enhanced safety

- Integrated DC AFCI
- Floating system with all-pole sensitive ground fault protection
- Reverse polarity indicator in combination with Connection Unit

Future-proof

- Complete grid management feature set
- Integrated Speedwire, WebConnect, ModBus interface
- Bi-directional Ethernet communications
- Utility-interactive controls for active and reactive power

SUNNY TRIPOWER 12000TL-US / 15000TL-US / 20000TL-US / 24000TL-US / 30000TL-US

The ultimate solution for decentralized PV plants, now up to 30 kilowatts

The world's best-selling three-phase PV inverter, the SMA Sunny Tripower TL-US, is raising the bar for decentralized commercial PV systems. This three-phase, transformerless inverter is UL listed for up to 1000 V DC maximum system voltage and has a peak efficiency above 98 percent, while OptiTrac Global Peak minimizes the effects of shade for maximum energy production. The Sunny Tripower delivers a future-proof solution with full grid management functionality, cutting edge communications and advanced monitoring. The Sunny Tripower is also equipped with all-pole ground fault protection and integrated AFCI for a safe, reliable solution. It offers unmatched flexibility with a wide input voltage range and two independent MPP trackers. Suitable for both 600 V DC and 1,000 V DC applications, the Sunny Tripower allows for flexible design and a lower levelized cost of energy.

www.SMA-America.com

Technical data	Sunny Tripower 12000TL-US	Sunny Tripower 15000TL-US	Sunny Tripower 20000TL-US	Sunny Tripower 24000TL-US	Sunny Tripower 30000TL-US
Input (DC)					
Max. array power	18000 Wp STC	22500 Wp STC	30000 Wp STC	36000 Wp STC	45000 Wp STC
Max. DC voltage	*1000 V				1000 V
Rated MPPT voltage range	300 V...800 V	300 V...800 V	380 V...800 V	450 V...800 V	500 V...800 V
MPPT operating voltage range	150 V...1000 V				
Min. DC voltage / start voltage	150 V / 188 V				
Number of MPP tracker inputs	2				
Max. operating input current / per MPP tracker	66 A / 33 A				
Max. short circuit current per MPPT / string input	53 A / 53 A				
Output (AC)					
AC nominal power	12000 W	15000 W	20000 W	24000 W	30000 W
Max. AC apparent power	12000 VA	15000 VA	20000 VA	24000 VA	30000 VA
Output phases / line connections	3 / 3-N-PE				3 / 3-N-PE, 3-PE
Nominal AC voltage	480 / 277 V WYE				480 / 277 V WYE, 480 V Delta
AC voltage range	244 V...305 V				
Rated AC grid frequency	60 Hz				
AC grid frequency / range	50 Hz, 60 Hz / -6 Hz...+5 Hz				
Max. output current	14.4 A	18 A	24 A	29 A	36.2 A
Power factor at rated power / adjustable displacement	1 / 0.0 leading...0.0 lagging				
Harmonics	< 3%				
Efficiency					
Max. efficiency / CEC efficiency	98.2% / 97.5%	98.2% / 97.5%	98.5% / 97.5%	98.5% / 98.0%	98.6% / 98.0%
Protection devices					
DC reverse polarity protection	●				
Ground fault monitoring / grid monitoring	●				
All-pole sensitive residual current monitoring unit	●				
DC AFCI compliant to UL 1699B	●				
AC short circuit protection	●				
Protection class / overvoltage category	I / IV				
General data					
Dimensions (W / H / D) in mm (in)	665 / 650 / 265 (26.2 / 25.6 / 10.4)				
Packing dimensions (W / H / D) in mm (in)	780 / 790 / 380 (30.7 / 31.1 / 15.0)				
Weight	55 kg (121 lbs)				
Packing weight	61 kg (134.5 lbs)				
Operating temperature range	-25°C...+60°C				
Noise emission (typical) / internal consumption at night	51 dB(A) / 1 W				
Topology	Transformerless				
Cooling concept / electronics protection rating	OptiCool / NEMA 3R				
Features					
Display / LED indicators (Status / Fault / Communication)	- / ●				
Interface: RS485 / Speedwire, WebConnect	○ / ●				
Data interface: SMA Modbus / SunSpec ModBus	● / ●				
Mounting angle range	15°...90°				
Warranty: 10 / 15 / 20 years	● / ○ / ○				
Certifications and approvals	UL 1741, UL 1741SA, CA Rule 21, UL 1998, UL 1699B, IEEE 1547, FCC Part 15 (Class A & B), CAN/CSA C22.2 107.1-1				
NOTE: US inverters ship with gray lids.	Data at nominal conditions, August 2017.		*Suitable for 600 V DC max. systems		
● Standard features ○ Optional features - Not available					
Type designation	STP 12000TL-US-10	STP 15000TL-US-10	STP 20000TL-US-10	STP 24000TL-US-10	STP 30000TL-US-10

Accessories



RS485 interface
DM-485CB-US-10



Connection Unit
CU 1000-US-11



SMA Cluster Controller
CLCON-10

