



Overflow car park

2.5m acoustic barrier

Site Footprint

97m x 61m
(does not include goal storage areas and 4m spectator hard-standing)

Match Play Pitch Markings

11v11 U11/U16 91m x 55m 1no. in white
11v7 U11/12 64m x 46m 1no. in blue
7v7 U9/10 55m x 37m 2no. in yellow
5v5 U7/8 37m x 27m 4no. in red

Fencing

All fencing and gates twin wire steel
powder coated moss green RAL 6005
Perimeter fence 4.5m high
Goal recess in hard-standing 2.0m high
Crowd rail to hard-standing 1.1m high

Floodlighting

6no. or 8no. column system
(depending on supplier)
LED system producing min./ove.
200 lux across playing surface

3G Pivoting Surface

60mm high pile height 3G with
60mm corner fill meeting
FIFA quality mark standard

Storage Container

1no. 6.1m x 2.4m (20' x 8') steel container
located in spectator hard-standing to
house 3G surface maintenance equipment

Project

Proposed 97m x 61m AGP and Alternative
Provision School for Blackpool F.C.
Community Trust, Seaside Way,
Blackpool. FY1 6JJ

Client

Blackpool F.C. Community Trust
Dwg. Title
Proposed AGP Pitch Plan



Churchill House, Mill Hill, Pontefract, West Yorkshire,
WF8 4HY t: 01977 797258 e: mail@stevewells-associates.com

Dwg. No.

205-068-1004

Rev.

A

Scale

1:500 @ A3

Date

April 2021

Drawn by

JLR

Checked

DKW

Copyright Notice:
This drawing is the copyright of Steve Wells Associates
and shall not be reproduced without permission. © 2021

Dwg. Purpose **Planning**

No.

A Acoustic fence amended

Revision / Issue

Date

9.4.21