

Close Spring Cottage - Oak extensio...



Our Normal Input is as follows: for Oak frames only

- Purchase and supply of Best Grade Green Construction Oak
- Frame drawings agreed via email after site survey
- The actual setting out and framing required, All framing is carried out in the traditional manner using mortise and tenon joints throughout, with drawbored joints using seasoned turned Oak pegs.
- Planed finish
- The actual delivery to your site on our transport on an agreed date

Green oak is a natural product and when wet will leach tannins that can stain surfaces.

Green oak as a natural finish will weather and when exposed to uv will change colour to silver/grey. Unless coated in a wood oil.

Coating of the green oak in clear wood oil will reduce tannins leaching out and the weathering process, however coating will require maintenance and regular upkeep.

Green oak will shrink and can shake as it dries out.

Our lead time from point of order is 12-14 weeks.

Payments

We work on the basis of 10% on placement of order, 40% once frame drawings are agreed, 40% once the oak frame is up on site and 10% on completion of our works.

I hope the above will be of interest to you and look forward to hearing from you in due course. In the meantime, if I can be of any further help, please do not hesitate to contact me.

Yours sincerely

