



| Ground Floor Window & External Door Schedule                                    |   |  |
|---|---|--|
| Number  | Size (Approx.)                                  | Notes  |
| D1  | 2100h x 1000w                                   | solid door with small vision panel, fixed light above, level access; Kitchen |
| D2  | 2100h x 1000w                                   | Utility  |
| D3  | 2100h x 1000w                                   | Office   |
| D4  | 2100h x 900w                                    | Fully glazed designed with link by specialist company; Lobby                 |
| D5  | 2350h x 3600w                                   | Fully glazed designed with link by specialist company; Lobby                 |
| D6  | 2100h x 1800w (doors)<br>2100h x 300w (windows) | French doors with side lights; Entrance hall                                 |
| All Ground Floor window heads 2400mm from dpc (except in Breakfast Room 2100mm) |   |  |
| W1  | 2400h x 3700w                                   | Staircase  |
| W2  | 600h x 2700w                                    | Kitchen  |
| W3  | 1050h x 1340w                                   | Utility  |
| W4  | 2000h x 440w                                    | Office   |
| W5  | 1050h x 1340w                                   | Office   |
| W6  | 1050h x 1340w                                   | Kitchen  |
| W7  | 1050h x 900w                                    | Kitchen  |
| W8  | 1050h x 1800w                                   | Bathroom   |
| W9  | 1050h x 1800w                                   | Bedroom 2  |
| W10   | 1050h x 1200w                                   | Escape; Bedroom 2  |
| W11   | 1050h x 900w                                    | Living Area  |
| W12   | 1050h x 900w                                    | Living Area  |
| W13   | 1050h x 900w                                    | Escape; Bedroom 1  |
| W14   | 1050h x 900w                                    | Bedroom 1 Ensuite  |
| W15   | 2no. 600h x 2800w                               | Bedroom 1  |

| 1st Floor Window & Rooflight Schedule |                |               |
|---------------------------------------|----------------|---------------|
| Number                                | Size (Approx.) | Notes         |
| W16                                   | 1840h x 3700w  | Staircase     |
| W17                                   | 600h x 650w    | Bed 4 Ensuite |
| W18                                   | 1050h x 900w   | Bed 4         |
| W19                                   | 900h x 900w    | Escape; Bed 4 |
| W20                                   | 1050h x 900w   | Escape; Bed 3 |
| W21                                   | 1050h x 600w   | Bed 3 Ensuite |

10 no. 550x778mm Velux Rooflights as shown on plan

Glazed link between Kitchen and Utility to be designed by specialist company

Garden Room glazing to be designed by others

T TOUGHENED OR LAMINATED GLASS

**DO NOT SCALE FROM THIS DRAWING**

**PLEASE NOTE:**

**ALL DIMENSIONS SHOWN ARE APPROXIMATE FOR THE PURPOSE OF OBTAINING ESTIMATES AND MUST BE CHECKED ON SITE PRIOR TO ORDER, MANUFACTURE AND INSTALLATION OF WINDOWS AND DOORS**

Do not scale from this drawing  
 All dimensions shown are approximate for the purpose of obtaining estimates and must be checked on site prior to order, manufacture and installation of windows and doors.  
 Any discrepancies, contact the issuer.

|   |  |
|---|--|
|   |  |
| Lara Turner Architectural Services ©<br>High Street<br>Bury Park<br>Salford, Greater Manchester<br>M6 9JN | Lara Turner Architectural Services ©<br>Tel: 01494 737428<br>Email: enquiries@lraarchitect.co.uk |
| <b>CLIENT:</b><br>MR & MRS M THACKER<br>BARIN CONVERSION AT<br>ABBEY FARM, BURY ROAD<br>COCKFIELD         | <b>PROJECT:</b><br>WINDOW & DOOR SCHEDULE  |
| <b>SCALE:</b> 1:20 @ A1<br>Job No. AFTT1018   | <b>DATE:</b> January 2019<br>DRG No. 08C   |