



TYPICAL OAK MULLION PLAN ON 7-7
1:2

Notes:

Take site dimensions prior to manufacture

Cockspur handles and casement stays to be handmade by David Butler blacksmith.
Tel: 01379 640182
E-mail: david@countryforge.co.uk

Purpose made softwood windows with hardwood cills complete with check grooves and weather seals, allow for clearance.

Glazing to be 12mm slim-line double glazing units U-Value 1.6w/m²k fixed in place with appropriate putty.



The Studio, 37 Church Street, Eye
IP23 7BD
01728 860 830
gmtd@gorniakandmckechnie.co.uk
www.gorniakandmckechnie.com

Drawn by	Scales @ A3	Project	Drawing Title	Client	Issue date	Project No	Drawing No	Rev
SCJ Checked by TMcK	1:2	Threeways, Great Wenham, Suffolk, CO7 6QE	Typical Oak Mullion Window Plan on 5-5	Mr. & Mrs. Gould	02/06/21	1845	410	A