

Sampson & Partners Fencing

"Specialists in Perimeter Security"

Prima 358 Weldmesh



Prima 358 or 'prison mesh' as it is commonly known is a security mesh fencing system with narrow apertures. This prevents the 'would be intruder' having any foot or finger holds therefore making it extremely difficult to climb. Prima panels are overlapped at each post and secured by a full-length clamp strip, domed headed bolts and permacone security fixings. The introduction of colour has now made the Prima 358 system a popular choice when security is paramount.

Standard heights: 2135, 2440 and 3000mm.

All other heights available on request.

Posts: Set at 2440mm nominal centres.

2440mm - 80 x 40 RHS or 60 x 60 SHS

Wire: 4mm diameter with a mesh size of 76.2 x 12.7mm.

Fixings: Galvanised bolt, permacone security nut and full length clamp bar or post clamp and threaded inset with security nut.

Finish: Posts and clamp bar - Hot Dip Galvanised to BS EN 1461 or Galvanised & Polyester Powder Coated.

Panels - Galvfan or Galvanised and Polyester Powder Coated.

