




- Key 1:500
- Remove tree. Refer to tree report for more information.
 - Site boundary
 - Lift and remove existing concrete paving, re-use sub base where possible.
 - Remove structure, wall or step. Re-use materials where possible.
 - Remove gravel. Re-use alongside and sub base if possible.
 - Remove all turf and sub base to be returned to land.
 - Remove surface turf layer. Reduce existing sub layers to new levels where possible.



The driveway bridge over the cedar path has been inspected by Curtis Structural Engineers and confirmed as structurally unsafe. It is proposed to remove the crown of the bridge and install the frame with compacted material suitable for 'paved' tarmac.

| Rev | Comment | Date |
|-----|--------------------------------|------------|
| P00 | Public consultation submission | 08/04/2021 |
| P01 | ISSUED FOR PLANNING | 14/04/2021 |

Tom Stuart-Smith Ltd
 80/83 Cowcross Street
 London EC1M 6BF
 Tel: +44 (0)207 253 2100

Status: Planning

Project:
Cuerden Hall

Drawing:
 Landscape removals, retentions and demolitions

Scale: 1:500@A0
 Dwg: 376-L-P-110 Rev: P01

Drawn: MH
 Date: 07/04/2021
 H:\376 Cuerden Hall\Drawings\Cuerden Hall - Removals.dwg