



**Proposed Works**

- 1 - Existing internal wall and door to be removed. Engineer to inspect and confirm if loadbearing. If wall is loadbearing please refer to engineer drawings. Repair any damaged surfaces to receive new finishes.
- 2 - Existing internal wall and door to be removed. Engineer to inspect and confirm if loadbearing. If wall is loadbearing please refer to engineer drawings. Repair any damaged surfaces to receive new finishes.
- 3 - Existing internal walls and door to be removed. Repair any damaged surfaces to receive new finishes.
- 4 - Existing External door to be removed and blocked. Repair any damaged surfaces to receive new finishes.
- 5 - Existing internal wall and door to be removed. Engineer to inspect and confirm if loadbearing. If wall is loadbearing please refer to engineer drawings. Repair any damaged surfaces to receive new finishes.
- 6 - Opening to be created for proposed window. Engineer to Confirm Structural support (Lintol). Repair any damaged surfaces to receive new finishes.
- 7 - Existing door to be removed and opening widened. opening to be filled with new bi-fold door. Engineer to confirm structural support (Lintol). Repair any damaged surfaces to receive new finishes.

Revision

ANGUS DESIGN ASSOCIATES LTD

Proposed Demo

Drawing No: AL(0)007  
Scale (A3): 1 : 50

**Building Warrant**

All sizes dimensions and heights are to be checked on site and confirmed before work commences. Sites sizes take preference to

1 Proposed Demo Plan  
1 : 50



VISUAL SCALE 1:50