

**Material Schedule - Exterior**



-----  
 de Rijke Marsh Morgan Ltd  
 Architects  
 -----  
 Magdalen House  
 136-148 Tooley St  
 London SE1 2TU  
 T +44 (0)20 7803 0777  
 -----

Project Name	THE GRANARY
Location	GREATHAM
Author	dRMM
Client	SHIRE BARNS DEVELOPMENT
Purpose of Issue	FOR PLANNING
Doc. reference	0534-dRMM-ZZ-ZZ-SC-A-0210
Date:	10.05.2021
Revision:	P1

ITEM & LOCATION	DESCRIPTION	IMAGE
<b>EXTERIOR MATERIAL SCHEDULE</b>		
<b>WINDOWS/DOORS</b>		
<b>01</b> - Front door - Granary	Glazed composite door (Oak framed door to the inside and anodised aluminium - RAL 7016 to the outside) + Timber shutter to the inside on rail To match window finishes	
<b>02</b> - Doors to bedrooms	Glazed composite door (Oak framed door to the inside and anodised aluminium - RAL 7016 to the outside) + Painted timber shutter to the outside	
<b>03</b> - Garage doors + All solid doors	Painted dark grey timber door to match windows	
<b>03a</b> - Door to south of Granary	Half glazed, half painted dark grey solid timber door to match windows	
<b>04</b> - All window/ glazed door elements (including Roof lights)	Composite Windows/Doors To the inside: Oak framed windows, doors, sliding doors and fixed panels. To the outside: Anodised aluminium, dark grey, RAL 7016	
<b>05</b> - Window sills	Dark grey zinc window sills To match window finishes	
<b>EXTERNAL WALL FINISHES</b>		
<b>06</b> - External cladding - The Granary	Dark grey weatherboard	

<p><b>07</b> - Reclaimed bricks - Stable block and Guest Suite</p>	<p>Reclaimed bricks from existing walls taken down</p>	
<p><b>08</b> - Gable wall - Granary</p>	<p>Retained existing brick gable wall - exposed bricks</p>	
<p><b>ROOFS</b></p>		
<p><b>09</b> - Tiles - The Stable block and Guest suite</p>	<p>Tiles matching existing roofs</p>	
<p><b>10</b> - Standing Seam Zinc Roof - Link Building</p>	<p>Pre-patinated dark grey zinc roof</p>	
<p><b>LINK BUILDING - EXTERNAL METAL FRAME</b></p>		
<p><b>11</b> - Frame - Including external columns</p>	<p>4 no. circular galvanised steel columns - Dark grey 9 no. Horizontal galvanised steel elements - Dark grey fabricated bespoke steel connectors</p>	
<p><b>EXTERNAL WALKWAY</b></p>		
<p><b>12</b> - External walkway connecting the Granary to the Dairy</p>	<p>Stone paving</p>	
<p><b>RAIN WATER PIPES/ GUTTERS</b></p>		
<p><b>13</b> - All rainwater pipes/gutters</p>	<p>RWP and gutters to match existing fascias</p>	
<p><b>LANDSCAPE</b></p>		
<p><b>14</b> - Soft Landscape areas and walkway in private garden</p>	<p>Limestone chippings</p>	